



Maine Turnpike Authority *Schedule of Items*

Bridge Repairs 3 Locations - Boom Road Underpass Mile 33.4 Beech Ridge Road Underpass Mile 41.4 Grove Street Underpass Mile 43.7

Item No.	Description	Quantity	UOM
202.127	REMOVING EXISTING BITUMINOUS PAVEMENT (1260 SY)	1.00	LS
202.202	REMOVING PAVEMENT SURFACE	1,405.00	SY
203.2	COMMON EXCAVATION	41.00	CY
304.1	AGGREGATE SUBBASE COURSE - GRAVEL	32.00	CY
403.208	HOT MIX ASPHALT - 12.5 mm NOMINAL MAXIMUM SIZE	222.00	Ton
403.213	HOT MIX ASPHALT, 12.5 mm NOMINAL MAXIMUM SIZE (BASE AND INTERMEDIATE COURSE)	119.00	Ton
409.15	BITUMINOUS TACK COAT RS-1 OR RS1h - APPLIED	119.00	Gal
502.701	BRIDGE DRAIN GRATE MODIFICATIONS	4.00	EA
502.7011	WEEP DRAIN EXTENSIONS	1.00	LS
508.14	HIGH PERFORMANCE WATERPROOFING MEMBRANE (1260 SY)	1.00	LS
513.09	SLOPE PROTECTION - PORTLAND CEMENT CONCRETE	65.00	SY
515.201	PIGMENTED PROTECTIVE COATING FOR CONCRETE SURFACES	310.00	SY
515.202	CLEAR PROTECTIVE COATING FOR CONCRETE SURFACES	1,865.00	SY
518.1	ABUTMENT REPAIRS	95.00	SF
518.2	PIER REPAIRS	215.00	SF
518.43	PARAPET JOINT REPAIRS	845.00	LF
518.75	FASCIA AND OVERHANG REPAIRS	50.00	SF
518.8	PARTIAL DEPTH CONCRETE DECK REPAIRS	160.00	SF
520.211	EXPANSION DEVICE MODIFICATIONS (BOOM ROAD)	1.00	LS
520.212	EXPANSION DEVICE MODIFICATIONS (BEECH RIDGE ROAD)	1.00	LS
520.213	EXPANSION DEVICE MODIFICATIONS (GROVE STREET)	1.00	LS
526.306	TEMPORARY CONCRETE BARRIER, TYPE I – SUPPLIED BY AUTHORITY	1.00	LS
613.319	EROSION CONTROL BLANKET	75.00	SY
615.07	LOAM	8.00	CY
618.14	SEEDING METHOD NUMBER 2	2.00	Unit
619.1201	MULCH-PLAN QUANTITY	2.00	Unit
619.1202	TEMPORARY MULCH	1.00	LS
619.1401	EROSION CONTROL MIX	28.00	CY
627.712	WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2,435.00	LF
639.19	FIELD OFFICE, TYPE B	1.00	EA
652.3	FLASHING ARROW BOARD	10.00	EA
652.312	TYPE III BARRICADE	6.00	EA
652.331	DRUM	1.00	LS
652.34	CONE	75.00	EA
652.35	CONSTRUCTION SIGNS	4,783.00	SF
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
652.38	FLAGGERS	1,300.00	HR
652.41	PORTABLE-CHANGEABLE MESSAGE SIGN	6.00	EA
652.45	TRUCK MOUNTED ATTENUATOR	84.00	Cal.
652.451	AUTOMATED TRAILER MOUNTED SPEED LIMIT SIGN	42.00	Cal.
652.46	TEMPORARY PORTABLE RUMBLE STRIPS	84.00	Unit
656.5	BALED HAY, IN PLACE	36.00	EA
656.632	30 INCH TEMPORARY SILT FENCE	455.00	LF
659.1	MOBILIZATION	1.00	LS