



Maine Turnpike Authority

Schedule of Items

Portland Area Pavement Rehabilitation Southbound Mile 42.0 to 49.3

Item No.	Description	Quantity	UOM
202.202	Removing Pavement Surface – Mainline	33,000.00	SY
202.2026	Removing Pavement Surface - Drainage Paths	960.00	SF
202.205	Rumble Strips	54,000.00	EA
304.14	Aggregate Base Course - Type A	275.00	CY
403.2081	Hot Mix Asphalt - 12.5 mm Nominal Maximum Size (Polymer Modified)	23,000.00	T
403.211	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size (Shimming)	650.00	T
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate Base course)	2,800.00	T
409.152	Bituminous Tack Coat Trackless - Applied	21,000.00	Gal
424.3231	Asphalt Rubber Mastic Crack Sealer - Applied	36,000.00	LB
424.324	Asphalt Rubber Mastic Crack Sealer With Aggregate	4,000.00	LB
427.09	Pavement Crack Repair	175.00	LF
470.08	Berm Dropoff Correction - Grindings	41,700.00	LF
470.081	Berm Correction	1,950.00	LF
520.23	Asphaltic Plug Joint	242.00	LF
604.18	Adjusting Manhole or Catch Basin to Grade	16.00	EA
606.178	Guardrail Beam	625.00	LF
606.353	Reflectorized Flexible Guardrail Marker	10.00	EA
606.3621	Guardrail Adjust, Single Rail	3,400.00	LF
606.3622	Guardrail Adjust, Double Rail	2,400.00	LF
606.471	Single Offset Block - W-Beam	10.00	EA
606.48	Single Galvanized Steel Post	15.00	EA
627.73	Temporary 6 Inch Pavement Marking Tape	3,400.00	LF
627.731	Temporary 6 Inch Black Pavement Marking Tape	2,600.00	LF
627.78	Temporary Pavement Marking Line	20,000.00	LF
627.812	Temporary Raised Pavement Markers	8,300.00	EA
627.94	Pavement Marking Tape	2,700.00	LF
627.941	Pavement Marking Tape – Dotted White Lane Line, 6-inch Width	3,250.00	LF
627.944	Pavement Markings - Recessed Tape - Words, Arrow and Stop Bars	170.00	SF
629.05	Hand Labor, Straight Time	30.00	HR
631.12	All Purpose Excavator (including operator)	25.00	HR
631.133	Skid Steer (including operator)	20.00	HR
631.172	Truck-large (including operator)	30.00	HR
631.36	Foreman	25.00	HR
652.3	Flashing Arrow	2.00	EA
652.312	Type III Barricades	15.00	EA
652.35	Construction Signs	1,860.00	SF



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.41	Portable-Changeable Message Sign	4.00	EA
652.4502	Truck Mounted Attenuator	2.00	EA
652.4503	Truck Mounted Attenuator	8.00	WK
652.47	Sequential Flashing Warning Lights	40.00	EA
659.1	Mobilization	1.00	LS