



Maine Turnpike Authority

Schedule of Items

Pavement Rehabilitation - Exit 75 Auburn

Item No.	Description	Quantity	UOM
201.11	Clearing	4.00	AC
202.202	Removing Pavement Surface	17,100.00	SY
202.2026	Removing Pavement Surface - Drainage Paths	240.00	SF
203.2	Common Excavation	7,200.00	CY
403.2081	Hot Mix Asphalt, 12.5mm (Polymer Modified)- RAP	1,750.00	Ton
409.15	Bituminous Tack Coat - Applied	1,100.00	GAL
424.324	Asphalt Rubber Mastic Crack Sealant	6,000.00	LB
470.08	Berm Dropoff Correction - Grindings	3,500.00	LF
470.081	Berm Correction	1,500.00	LF
603.179	18 inch Culvert Pipe Option III	50.00	LF
610.08	Plain Riprap	5.00	CY
613.319	Erosion Control Blanket	750.00	SY
615.07	Loam	230.00	CY
618.1401	Seeding Method Number 2, Plan Quantity	3.00	UNIT
619.1202	Temporary Mulch	1.00	LS
626.122	Quazite Junction Box (18x11)	2.00	EA
626.221	Non-Metallic Conduit	350.00	LF
626.33	30 inch Diameter, 8 feet or less Foundation	1.00	EA
627.712	Pavement Marking Line White or Yellow	11,200.00	LF
627.75	White or Yellow Pavement & Curb Marking	800.00	SF
627.78	Temporary Pavement Marking Line	10,000.00	LF
627.812	Temporary Raised Pavement Markers	1,300.00	EA
629.05	Hand Labor, Straight Time	15.00	HR
631.1	Air Compressor (including operator)	10.00	HR
631.11	Air Tool (including operator)	10.00	HR
631.12	All Purpose Excavator (including operator)	40.00	HR
631.172	Truck - Large (including operator)	40.00	HR
631.32	Culvert Cleaner (including operator)	10.00	HR
631.36	Foreman	40.00	HR
631.53	Electrician	10.00	HR
634.2312	Conventional Light Standard with Authority Supplied LED Fixture	1.00	EA
634.2313	Remove and Dispose Light Standard	1.00	EA
652.3	Flashing Arrow	3.00	EA
652.312	Type III Barricades	12.00	EA
652.35	Construction Signs	2,740.00	SF
652.3611	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	500.00	HR



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
652.411	Portable - Changeable Message Sign	4.00	EA
652.4502	Truck Mounted Attenuator	1.00	EA
652.46	Temporary Portable Rumble Strips (1 Unit = 3 Strips)	22.00	UNIT
656.5	Baled Hay, in place	30.00	EA
656.632	30 inch Temporary Silt Fence	100.00	LF
659.1	Mobilization	1.00	LS