



Maine Turnpike Authority

Schedule of Items

Androscoggin River Bridges Substructure Repairs Mile 78.9

Item No.	Description	Quantity	UOM
201.31	Removal of Debris	1.00	LS
504.885	Post-Tensioning Sleeve Repair	13.00	EA
514.06	Curing Box for Concrete Cylinders	1.00	EA
515.202	Clear Protective Coating for Concrete Surfaces	3,250.00	SY
515.23	Anti-Graffiti Coating	900.00	SY
518.4	Epoxy Injection Crack Repair	310.00	LF
518.401	Epoxy Injection Crack Repair - Below Waterline	470.00	LF
518.51	Repair of Upward Facing Surfaces - Below Reinforcing Steel < 8 inches	43.00	SF
518.6	Repair of Vertical Surfaces < 8 inches	2,950.00	SF
518.601	Repair of Vertical Surfaces < 8 inches - Below Waterline	18.00	SF
518.7	Repair of Overhead Surfaces < 8 inches	91.00	SF
520.224	Joint Armor Repair	1.00	LS
523.56	Cleaning and Painting Bearing	42.00	EA
523.561	Repair Bearing	1.00	EA
523.562	Repair Bearing Keeper Strap	10.00	EA
524.301	Temporary Structural Support	1.00	LS
524.6	Temporary Access Platforms for Pier Inspection and Repair	1.00	LS
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority	1.00	LS
527.341	Work Zone Crash Cushion - TL-3	1.00	UN
627.712	White or Yellow Pavement Marking Line	4,300.00	LF
627.73	Temporary 6 Inch Pavement Marking Tape	6,300.00	LF
627.731	Temporary 6 Inch Black Pavement Marking Tape	1,500.00	LF
627.77	Removing Existing Pavement Marking	2,100.00	SF
629.05	Hand Labor, Straight Time	20.00	HR
631.1	Air Compressor (including operator)	10.00	HR
631.11	Air Tool (including operator)	10.00	HR
631.172	Truck - large (including operator)	20.00	HR
631.36	Foreman	10.00	HR
652.3	Flashing Arrow	1.00	EA
652.33	Drum	50.00	EA
652.34	Cone	50.00	EA
652.35	Construction Signs	420.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.41	Portable-Changeable Message Sign	1.00	EA
652.45	Truck Mounted Attenuator	20.00	CD
652.452	Automated Trailer Mounted Speed Limit Sign	1.00	EA
652.46	Temporary Portable Rumble Strip	20.00	UN



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
656.64	Boom Supported Floating Silt Fence	302.00	LF
659.1	Mobilization	1.00	LS