



Maine Turnpike Authority

Schedule of Items

Emergency Vehicle Ramps - High Street MM 103.6

Item No.	Description	Quantity	UOM
201.11	Clearing	0.56	AC
201.23	Removing Single Tree Top Only	2.00	EA
201.24	Removing Stump	2.00	EA
203.2	Common Excavation	2,700.00	CY
203.24	Common Borrow	3,500.00	CY
203.25	Granular Borrow	625.00	CY
304.1	Aggregate Subbase Course-Gravel	1,540.00	CY
304.14	Aggregate Base Course - Type A	430.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size (Base)	300.00	TON
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Surface)	186.00	TON
409.15	Bituminous Tack Coat RS-1 or RS1h - Applied	87.00	GAL
419.3	Sawing Bituminous Pavement	800.00	LF
603.159	12" Culvert Pipe OPT III	10.00	LF
603.179	18" Culvert Pipe OPT III	43.00	LF
603.199	24" Culvert Pipe OPT III	110.00	LF
604.169	Remove Catch Basin	1.00	EA
604.246	Catch Basin Type F5	1.00	EA
606.1301	31" W-Beam Guardrail, Mid-Way Splice-Single Faced	225.00	LF
606.1304	31" W-Beam Guardrail, Mid-Way Splice-Over 15' Radius	225.00	LF
606.1305	31" W-Beam Guardrail, Mid-Way Splice-Flared Terminal	1.00	EA
606.1351	31" W-Beam Guardrail, Mid-Way Splice-Terminal End - Anchored End	6.00	EA
606.353	Reflectorized Flexible Guardrail Marker	6.00	EA
606.3561	Delineator Post - Remove and Reset	6.00	EA
607.17	Chain Link Fence - 6 foot	200.00	LF
607.32	Bracing Assembly Type I - Metal Posts	4.00	EA
607.33	Bracing Assembly Type II - Metal Posts	5.00	EA
609.31	Curb Type 3	50.00	LF
610.08	Plain Riprap	10.00	CY
610.181	Temporary Stone Check Dam	20.00	CY
613.319	Erosion Control Blanket	1,280.00	SY
615.07	Loam	450.00	CY
618.14	Seeding Method Number 2	37.00	UNIT
619.1201	Mulch - Plan Quantity	37.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	55.00	SY
629.05	Hand Labor, Straight Time	30.00	HR
631.12	All Purpose Excavator (including operator)	30.00	HR



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
631.171	Truck - small (including operator)	60.00	HR
631.32	Culvert Cleaner (including operator)	8.00	HR
631.36	Foreperson	16.00	HR
645.271	Regulatory, Warning, Confirmation and Route Assembly Sign, Type 1	67.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	100.00	HR
656.5	Baled Hay, in place	30.00	EA
656.632	30 inch Temporary Silt Fence	1,840.00	LF
659.1	Mobilization	1.00	LS
827.37	Electrical Conduit Trenching	35.00	LF