MAINE TURNPIKE AUTHORITY

ADDENDUM NO. 1

CONTRACT 2018.02

EXIT 47 INTERSECTION IMPROVEMENTS, PAVEMENT REHABILITATION, AND CLEAR ZONE IMPROVEMENTS MILE 47

The bid	opening	date is	Thursday	8/30/2018 at	11:00 am.

The following changes are made to the Proposal:

PROPOSAL

Proposal Sheets P-2 through P-8, attached hereto, are inserted after Proposal Sheet P-1.

The total number of pages included with this addendum is Eight (8).

All bidders are requested to acknowledge the receipt of the Addendum No. 1 by signing below and faxing this sheet to Nathaniel Carll, Purchasing Department, Maine Turnpike Authority at 207-871-7739. Bidders are also required to acknowledge receipt of this Addendum No. 1 on Page P-9 of the bid package.

Business Name	
Print Name and Title	
Signature	
Date August 9, 2018	
	Very truly yours, MAINE TURNPIKE AUTHORITY
	Nathaniel Carll
	Purchasing Department
	Maine Turnpike Authority

SCHEDULE OF BID PRICES CONTRACT NO. 2018.02

Intersection Improvements, Pavement Rehabilitation, and Clear Zone Improvements Exit 47

Item No	Item Description	Units	Approx. Quantities	Unit Prices		Bid Amount in Numbers	
	·		1	Dollars	Cents	Dollars	Cents
202.202	Removing Pavement Surface	Square Yard	28,600				
202.2026	Removing Pavement Surface - Drainage Paths	Square Foot	530				
202.203	Pavement Butt Joint	Square Yard	625				
203.20	Common Excavation	Cubic Yard	780				
203.24	Common Borrow	Cubic Yard	1,836				
304.10	Aggregate Subbase Course - Gravel	Cubic Yard	560				
304.14	Aggregate Base Course - Type A	Cubic Yard	190				 -
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	Ton	350				
403.2081	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size, (Polymer Modified) RAP	Ton	2,630				
403.212	Hot Mix Asphalt, 4.75 mm Nominal Maximum Size (Shim)	Ton	150				
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate)	Ton	2,280				

						! [
203.20	Common Excavation	Cubic Yard	780			
203.24	Common Borrow	Cubic Yard	1,836			
304.10	Aggregate Subbase Course - Gravel	Cubic Yard	560			
304.14	Aggregate Base Course - Type A	Cubic Yard	190			
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	Ton	350			
403.2081	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size, (Polymer Modified) RAP	Ton	2,630			
403.212	Hot Mix Asphalt, 4.75 mm Nominal Maximum Size (Shim)	Ton	150			
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate)	Ton	2,280			
				CARRIED FORW	APD:	
				CARRIED FORW	AND.	

CARRIED FORWARD:	

			1 1	CON	ITRACT NO: 2018.02				
Item No	Item Description	Units	Approx. Quantities	Unit Prices in Numbers	Bid Amount in Numbers				
				Dollars Cents	Dollars Cents				
	BROUGHT FORWARD:								
409.15	Bituminous Tack Coat, Applied	Gallon	2,520						
419.30	Sawing Bituminous Pavement	Linear Foot	1,200						
470.08	Berm Dropoff Correction - Grindings	Ton	180						
520.23	Asphaltic Plug Joint	Linear Foot	195						
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority (1020')	Lump Sum	1						
527.341	Work Zone Crash Cushion TL-2	Each	3						
603.175	18 inch Reinforced Concrete Pipe Class III	Linear Foot	8						
603.209	30 inch Culvert Pipe Option III	Linear Foot	144						
603.28	Concrete Collar	Each	1						
604.18	Adjusting Manhole or Catch Basin to Grade	Each	4						
604.184	Rebuild Catch Basin to Grade - Type II	Each	4						
606.13	31" W-Beam Guardrail - Mid- Way Splice (7' Steel Post, 8" Offset Blocks, Single Faced)	Linear Foot	150	 					

31" W-Beam Guardrail - Mid- Way Splice (7' Steel Post, 8" Offset Blocks, Single Faced)	Linear Foot	150			
			CARRIED FORW	ARD:	
		P-3	Addendum No. 1	I	

			1	001	TRACT NO: 2018.	02
Item No	Item Description	Units	Approx. Quantities	Unit Prices in Numbers	Bid Amour in Number	
	· ·			Dollars Cents	Dollars	Cents
				BROUGHT FORWARD:		1
606.131	31" W-Beam Guardrail - Mid- Way Splice (8' Steel Post, 8" Offset Blocks, Single Faced)	Linear Foot	450			
606.1723	Bridge Transition Type III	Each	1			
606.178	Guardrail Beam	Linear Foot	200			
606.352	Reflectorized Beam Guardrail Delineator	Each	230			
606.3531	Permanent Flexible Delineator Post	Each	4			
606.355	Delineator Post - Remove and Stack	Each	10			
606.356	Underdrain Delineator Post	Each	3			
606.3621	Guardrail Adjust - Single Rail	Linear Foot	3,200			
606.3622	Guardrail Adjust - Double Rail	Linear Foot	2,050			
606.471	Single Offset Block-W-Beam	Each	200			
606.791	Guardrail - Flared Terminal - 31" W-Beam Guardrail	Each	1			
610.08	Plain Riprap	Cubic Yard	100			

000.701	31" W-Beam Guardrail	Luon	·	i !		
610.08	Plain Riprap	Cubic Yard	100			
				CARRIED FORW	ARD:	
			P-4	Addendum No. 1		

	<u> </u>		1	COr	NTRACT NO: 2018.02					
Item No	Item Description	Units	Approx. Quantities	Unit Prices in Numbers	Bid Amount in Numbers					
				Dollars Cents	Dollars Cents					
	BROUGHT FORWARD:									
610.181	Temporary Stone Check Dam	Cubic Yard	4							
613.319	Erosion Control Blanket	Square Yard	1,900							
615.07	Loam	Cubic Yard	420							
618.14	Seeding Method Number 2	Unit	34							
619.1201	Mulch - Plan Quantity	Unit	34							
619.1202	Temporary Mulch	Lump Sum	1							
620.58	Erosion Control Geotextile	Square Yard	240							
626.12	36" x 24" x 21" Quazite Junction Box	Each	4							
626.21	Metallic Conduit	Linear Foot	50							
626.22	Non-metallic Conduit	Linear Foot	3,000							
626.223	Horizontal Directional Drilled Conduit	Linear Foot	600							
626.332	30-inch Diameter, greater than 8-feet long, and all 36- inch and 42-inch Diameter Foundations	Cubic Yard	4							

		Foot	-,			
626.223	Horizontal Directional Drilled Conduit	Linear Foot	600			
626.332	30-inch Diameter, greater than 8-feet long, and all 36- inch and 42-inch Diameter Foundations	Cubic Yard	4			
				CARRIED FORWAI	RD:	
			P-5	Addendum No. 1		

	T		1	COr	NTRACT NO: 2018.02				
Item No	Item Description	Units	Approx. Quantities	Unit Prices in Numbers	Bid Amount in Numbers				
110	Rom Boompaon	O'iito	Quantitioo	Dollars Cents	Dollars Cents				
	BROUGHT FORWARD:								
626.35	Controller Cabinet Foundation	Each	1	 					
627.712	White or Yellow Pavement Marking Line	Linear Foot	19,650						
627.75	White or Yellow Pavement and Curb Marking	Square Foot	1,500						
627.77	Remove Existing Pavement Markings	Square Foot	1,900	 					
627.78	Temporary Pavement Marking Line, White or Yellow	Linear Foot	8,150	 					
627.812	Temporary Raised Pavement Marker	Each	1,100						
627.9411	Pavement Marking Tape - Dotted White or Yellow Lane Line - 6" Width	Linear Foot	100						
629.05	Hand Labor, Straight Time	Hour	50						
631.10	Air Compressor (Including Operator)	Hour	40						
631.11	Air Tool (Including Operator)	Hour	40						
631.12	All Purpose Excavator (including operator)	Hour	50						
631.17	Truck - Large (Including Operator)	Hour	50						

631.17	Truck - Large (Including Operator)	Hour	50					
	CARRIED FORWARD:							
		P-6 Addendum No. 1						

	T	T		COI	TRACT NO: 2018.02	
Item No	Item Description	Units	Approx. Quantities	Unit Prices in Numbers	Bid Amount in Numbers	
				Dollars Cents	Dollars	Cents
				BROUGHT FORWARD:		
631.32	Culvert Cleaner (Including operator)	Hour	8			
631.36	Foreman	Hour	50			
634.175	Replacement LED Fixture, Installed	Each	1		1	
643.72	Temporary Traffic Signal	Lump Sum	1	 	 	
643.80	Traffic Signal Modifications at Exit 47 and Rand Road	Lump Sum	1		1	
643.83	Video Detection System Supply and Install	Lump Sum	1		1	
645.1061	Relocate Existing Sign Assembly and Post	Each	4		1	
645.271	Regulatory, Warning, Confirmation and Route Assembly Sign, Type II	Square Foot	72		1	
652.30	Flashing Arrow Board	Each	1		1	
652.33	Drum	Each	55		1	
652.34	Cone	Each	55			
652.35	Construction Signs	Square Foot	3,200			
L	1	1		I		

	P-7 Addendum No. 1											
				CARRIED FORW	ARD:		i 					
					<u> </u>							
		Foot			 							
652.35	Construction Signs	Square	3,200		ļ							

				CC	ONTRACT NO: 2018.	02
Item	Item Description	Units	Approx. Quantities	Unit Prices in Numbers	Bid Amount in Numbers	
No		Units		Dollars Cen		Cents
	•			BROUGHT FORWARI		
				BROUGHT FORWARD	J.	
652.361	Maintenance of Traffic Control Devices	Lump Sum	1			
652.38	Flaggers	Hour	240			
652.381	Traffic Officers	Hour	20			
652.41	Portable-Changeable Message Sign	Each	4			
652.45	Truck Mounted Attenuator	Calendar Day	10			
655.16	Fiber Optic Cable	Linear	650			
		Foot				
655.165	Fiber Optic Splice Panel	Each	2			
656.50	Baled Hay,in place	Each	15			
656.60	Temporary Berms	Linear Foot	1,100			
656.632	30" Temporary Silt Fence	Linear Foot	1,150			
659.10	Mobilization	Lump Sum	1			
	1	1		TOTAI	_:	