

MAINE TURNPIKE AUTHORITY

MAINE TURNPIKE

CONTRACT DOCUMENTS

CONTRACT 2018.10

BRIDGE AND CULVERT REPAIRS

4 LOCATIONS

MILE 75.8 TO MILE 91.9

NOTICE TO CONTRACTORS

PROPOSAL

CONTRACT AGREEMENT

CONTRACT BOND

FINAL LIEN AND CLAIM WAIVER AND AFFIDAVIT

SPECIFICATIONS

MAINE TURNPIKE AUTHORITY

SPECIFICATIONS

The Specifications are divided into two parts:
Part I, Supplemental Specifications and Part II, Special
Provisions.

The Maine Turnpike Supplemental Specifications are additions
and alterations to the 2014 Maine Department of
Transportation Standard Specifications. See Subsection 100.1.

TABLE OF CONTENTS

	<u>PAGE</u>
NOTICE TO CONTRACTORS	N-1
PROPOSAL	P-1
CONTRACT AGREEMENT	C-1
CONTRACT BOND	CB-1
FINAL LIEN AND CLAIM WAIVER AND AFFIDAVIT	F-1

ARRANGEMENT OF SPECIFICATIONS

PART I – SUPPLEMENTAL SPECIFICATIONS

Available at: <http://www.maineturnpike.com/Projects-Planning/Construction-Contracts.aspx>

PART II - SPECIAL PROVISIONS	SP-1
------------------------------	------

MAINE TURNPIKE AUTHORITY

NOTICE TO CONTRACTORS

Sealed Proposals will be received by the Maine Turnpike Authority for:

CONTRACT 2018.10

BRIDGE AND CULVERT REPAIRS

4 LOCATIONS

MILE 75.8 TO MILE 91.9

at the office of the Maine Turnpike Authority, 2360 Congress Street, Portland, ME, until 11:00 a.m., prevailing time as determined by the Authority on January 18, 2018, at which time and place the Proposals will be publicly opened and read. Bids will be accepted from Contractors **prequalified** by the Maine Department of Transportation for Bridge Construction Projects. All other bids may be rejected. This Project includes a wage determination developed by the State of Maine Department of Labor.

The work consists of general repairs and modifications at the Danville Corner Road Bridge in Auburn, the Fisher Farm Road Bridge in Sabattus, and the Center Road Bridge in Litchfield over the Maine Turnpike and the Curtis Brook Culvert on Fisher Farm Road in Sabattus. The work includes pavement and membrane replacement, concrete deck, parapet, fascia, fascia overhang, pier, and abutment repairs, concrete wing wall and culvert wall repairs, bridge joint repairs, protective coatings, milling and paving, maintenance of traffic and all other work incidental thereto in accordance with the Plans and Specifications.

Plans and Contract Documents may be examined by prospective Bidders weekdays between 8:00 a.m. and 4:30 p.m. at the office of the Maine Turnpike Authority, 2360 Congress Street, Portland, Maine. **The half size Plans** and Contract Documents may be obtained from the Authority upon payment of One Hundred (\$100.00) Dollars for each set, which payment will not be returned. Checks shall be made payable to: Maine Turnpike Authority. The Plans and Contract Documents may also be downloaded from a link on our website at <http://www.maineturnpike.com/project-and-planning/Construction-Contracts.aspx>.

For general information regarding Bidding and Contracting procedures, contact Nate Carll, Purchasing Manager, at (207)482-8115. For information regarding Schedule of Items, plan holders list and bid results, visit our website at <http://www.maineturnpike.com/project-and-planning/Construction-Contracts.aspx>. For Project specific information, fax all questions to Nate Carll, Purchasing Manager, at (207) 871-7739 or email ncarll@maineturnpike.com. Responses will not be prepared for questions received by telephone. Bidders shall not contact any other Authority staff or Consultants for clarification of Contract provisions, and the Authority will not be responsible for any interpretations so obtained.

All work shall be governed by the Specifications entitled "State of Maine, Department of Transportation, Standard Specifications, Revision of November 2014", "Standard Details, Revision of November 2014" and "Best Management Practices for Erosion and Sediment Control", latest issue. Copies and recent updates to these publications can be downloaded at: <http://www.maine.gov/mdot/contractors/publications/> .

Proposals must be accompanied by an original bid bond, certified or cashier's check payable to the Maine Turnpike Authority in an amount not less than Five (5%) Percent of the Total Amount in the Proposal, but not less than \$500.00. The Bidder to whom a Contract is awarded will be required to furnish a Surety Corporation Bond, satisfactory to the Authority, on the standard Contract Bond form of the Authority, for a sum not less than the Total Amount of the Proposal.

Proposals must be made upon the Proposal Forms furnished by the Authority separately with the Contract Documents, and must be enclosed in the sealed special addressed envelope provided therefore bearing the name and address of the Bidder, the name of the Contract, and the date and time of Proposal opening on the outside.

A pre-bid conference will be held on January 4, 2018 at 11:00 a.m. at the Maine Turnpike Authority, 2360 Congress Street, Portland, Maine.

The Authority reserves the unqualified right to reject any or all Proposals and to accept that Proposal which in its sole judgment will under all circumstances serve its best interest.

MAINE TURNPIKE AUTHORITY

Nate Carll
Purchasing Manager
Maine Turnpike Authority

Portland, Maine

Maine Turnpike Authority

MAINE TURNPIKE

PROPOSAL

CONTRACT 2018.10

BRIDGE AND CULVERT REPAIRS

4 LOCATIONS

MILE 75.8 TO MILE 91.9

MAINE TURNPIKE AUTHORITY

PROPOSAL

CONTRACT 2018.10

BRIDGE AND CULVERT REPAIRS

4 LOCATIONS

MILE 75.8 TO MILE 91.9

TO MAINE TURNPIKE AUTHORITY:

The work consists of general repairs and modifications at the Danville Corner Road Bridge in Auburn, the Fisher Farm Road Bridge in Sabattus, and the Center Road Bridge in Litchfield over the Maine Turnpike and the Curtis Brook Culvert on Fisher Farm Road in Sabattus. The work includes pavement and membrane replacement, concrete deck, parapet, fascia, fascia overhang, pier, and abutment repairs, concrete wing wall and culvert wall repairs, bridge joint repairs, protective coatings, milling and paving, maintenance of traffic and all other work incidental thereto in accordance with the Plans and Specifications.

This Work will be done under a Contract known as Contract 2018.10 according to the Plans and Specifications which are on file in the office of the Maine Turnpike Authority, 2360 Congress Street, Portland, Maine.

On the acceptance of this Proposal for said Work, the undersigned will give the required bond with good security conditioned for the faithful performance of said Work, according to said Plans and Specifications, and the doing of all other work required by said Specifications for the consideration herein named and with the further condition that the Maine Turnpike Authority shall be saved harmless from any and all damages that might accrue to any person, persons or property by reason of the carrying out of said Work, or any part thereof, or by reason of negligence of the undersigned, or any person or persons under his employment and engaged in said Work.

The undersigned hereby declares that he/she has carefully examined the Plans, Specifications and other Contract Documents, and that he/she will contract to carry out and complete the said Work as specified and delineated at the price per unit of measure for each scheduled item of Work stated in the Schedule of Prices as follows:

It is understood that the TOTAL AMOUNT stated by the undersigned in the following Schedule of Prices is based on approximate quantities and will be used solely for the comparison of bids, and that the quantities stated in the Schedule of Prices for the various items are estimates only and may be increased or decreased all as provided in the Specifications.

**SCHEDULE OF BID PRICES
CONTRACT NO. 2018.10
Bridge and Culvert Repairs
4 Locations (Mile 75.8 to Mile 91.9)**

Item No.	Item Description	Units	Approx. Quantities	Unit Prices in Numbers		Bid Amount in Numbers	
				Dollars	Cents	Dollars	Cents
202.127	REMOVING OF EXISTING BITUMINOUS PAVEMENT (2075 SY)	Lump Sum	1				
202.191	REMOVING EXISTING DRAIN TROUGHS	Lump Sum	1				
202.202	REMOVING PAVEMENT SURFACE	Square Yard	1,290				
203.24	COMMON BORROW	Cubic Yard	5				
403.208	HOT MIX ASPHALT, 12.5MM NOMINAL MAXIMUM SIZE	Ton	278				
403.213	HOT MIX ASPHALT, 12.5MM NOMINAL MAXIMUM SIZE (BASE AND INTERMEDIATE COURSE)	Ton	171				
409.15	BITUMINOUS TACK COAT - APPLIED	Gallon	218				
507.095	ALUMINUM BRIDGE RAILING - SPLICE MODIFICATION	Each	38				
508.14	HIGH PERFORMANCE WATERPROOFING MEMBRANE (2075 SY)	Lump Sum	1				
511.07	COFFERDAM	Lump Sum	1				

CARRIED FORWARD:		
-------------------------	--	--

Item No.	Item Description	Units	Approx. Quantities	Unit Prices in Numbers		Bid Amount in Numbers	
				Dollars	Cents	Dollars	Cents
BROUGHT FORWARD:							
515.201	PIGMENTED PROTECTIVE COATING FOR CONCRETE SURFACES	Square Yard	1,015				
515.202	CLEAR PROTECTIVE COATING FOR CONCRETE SURFACES	Square Yard	1,720				
518.10	ABUTMENT REPAIRS	Square Foot	70				
518.20	PIER REPAIRS	Square Foot	260				
518.39	GRANITE CURB JOINT MORTAR AND BEDDING MORTAR REPAIR	Linear Foot	270				
518.40	EPOXY INJECTION CRACK REPAIR	Linear Foot	65				
518.43	PARAPET JOINT REPAIR	Linear Foot	1,310				
518.75	FASCIA AND OVERHANG REPAIRS	Square Foot	105				
518.80	PARTIAL DEPTH CONCRETE DECK REPAIRS	Square Foot	570				
518.81	FULL DEPTH CONCRETE DECK REPAIRS	Square Foot	30				
520.2211	EXPANSION DEVICE MODIFICATIONS (DANVILLE CORNER ROAD)	Each	2				
520.2211	EXPANSION DEVICE MODIFICATIONS (FISHER FARM ROAD)	Each	2				
CARRIED FORWARD:							

Item No.	Item Description	Units	Approx. Quantities	Unit Prices in Numbers		Bid Amount in Numbers	
				Dollars	Cents	Dollars	Cents
BROUGHT FORWARD:							
520.2211	EXPANSION DEVICE MODIFICATIONS (CENTER ROAD)	Each	2				
526.306	TEMPORARY CONCRETE BARRIER, TYPE 1 - SUPPLIED BY AUTHORITY	Lump Sum	1.0				
527.341	WORK ZONE CRASH CUSHIONS - TL-3	Unit	6				
603.91	PRESSURE TREATED WOOD DRAIN TROUGH	Linear Foot	70				
607.17	CHAIN LINK FENCE - 6 FOOT	Linear Foot	355				
607.171	CHAIN LINK FENCE - 6 FOOT PVC PRIVACY FENCE	Linear Foot	1,750				
607.23	CHAIN LINK FENCE GATE	Each	2				
607.34	BRACING ASSEMBLY CHAIN LINK FENCE	Each	20				
610.08	PLAIN RIPRAP	Cubic Yard	8				
615.07	LOAM	Cubic Yard	60				
618.14	SEEDING METHOD NUMBER 2	Unit	5				
619.1201	MULCH - PLAN QUANTITY	Unit	5				
CARRIED FORWARD:							

Item No.	Item Description	Units	Approx. Quantities	Unit Prices in Numbers		Bid Amount in Numbers	
				Dollars	Cents	Dollars	Cents
BROUGHT FORWARD:							
619.1202	TEMPORARY MULCH	Lump Sum	1				
619.1401	EROSION CONTROL MIX	Cubic Yard	50				
620.58	EROSION CONTROL GEOTEXTILE	Square Yard	24				
627.733	4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	Linear Foot	1,990				
639.19	FIELD OFFICE, TYPE B	Each	1				
643.712	FLASHING BEACON - SOLAR POWERED	Each	1				
652.30	FLASHING ARROW BOARD	Each	6				
652.312	TYPE III BARRICADES	Each	12				
652.331	DRUM	Lump Sum	1.0				
652.35	CONSTRUCTION SIGNS	Square Foot	4,850				
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	Lump Sum	1.0				
652.41	PORTABLE-CHANGEABLE MESSAGE SIGN	Each	6				
CARRIED FORWARD:							

Item No.	Item Description	Units	Approx. Quantities	Unit Prices in Numbers		Bid Amount in Numbers	
				Dollars	Cents	Dollars	Cents
BROUGHT FORWARD:							
652.45	TRUCK MOUNTED ATTENUATOR	Cal. Day	42	200	00	8400	00
652.451	AUTOMATED TRAILER MOUNTED SPEED LIMIT SIGN	Cal. Day	42	75	00	3150	00
652.46	TEMPORARY PORTABLE RUMBLE STRIPS	Unit	126	75	00	9450	00
656.632	30 INCH TEMPORARY SILT FENCE	Linear Foot	325				
659.10	MOBILIZATION	Lump Sum	1				
TOTAL:							

Acknowledgment is hereby made of the following Addenda received since issuance of the Plans and Specifications: _____

Accompanying this Proposal is an original bid bond, cashiers or certified check on _____ Bank, for _____, payable to the Maine Turnpike Authority. In case this Proposal shall be accepted by the Maine Turnpike Authority and the undersigned should fail to execute a Contract with, and furnish the security required by the Maine Turnpike Authority as set forth in the Specifications, within the time fixed therein, an amount of money equal to Five (5%) Percent of the Total Amount of the Proposal for the Contract awarded to the undersigned, but not less than \$500.00, obtained out of the original bid bond, cashier's or certified check, shall become the property of the Maine Turnpike Authority; otherwise the check will be returned to the undersigned.

The performance of said Work under this Contract will be completed during the time specified in Subsection 107.1.

It is agreed that time is of the essence of this Contract and that I (we) will, in the event of my (our) failure to complete the Work within the time limit named above, pay to Maine Turnpike Authority liquidated damages in the amount or amounts stated in the Specifications.

The undersigned is an Individual/Partnership/Corporation under the laws of the State of _____, having principal office at _____, thereunto duly authorized.

_____ (SEAL)

_____ (SEAL)

*Affix Corporate Seal
or Power of Attorney
Where Applicable*

_____ (SEAL)

By: _____

Its: _____

Information below to be typed or printed where applicable:

INDIVIDUAL:

(Name)	(Address)
--------	-----------

PARTNERSHIP - Name and Address of General Partners:

(Name)	(Address)
--------	-----------

(Name)	(Address)
--------	-----------

(Name)	(Address)
--------	-----------

(Name)	(Address)
--------	-----------

INCORPORATED COMPANY:

(President)	(Address)
-------------	-----------

(Vice-President)	(Address)
------------------	-----------

(Secretary)	(Address)
-------------	-----------

(Treasurer)	(Address)
-------------	-----------

MAINE TURNPIKE AUTHORITY

MAINE TURNPIKE

YORK TO AUGUSTA

CONTRACT AGREEMENT

This Agreement made and entered into between the Maine Turnpike Authority, and sometimes termed the "Authority", and _____

_____ herein termed the "Contractor":

WITNESSETH: That the Authority and the Contractor, in consideration of the premises and of the mutual covenants, considerations and agreements herein contained, agree as follows:

FIRST: The parties hereto mutually agree that the documents attached hereto and herein incorporated and made a part hereof collectively evidencing and constituting the entire Contract to the same extent as if herein written in full, are the Notice to Contractors, the Accepted Proposal, the Specifications, the Plans, this Agreement, the Contract Bond and all Addenda to the Contract Documents duly issued and herewith enumerated:

SECOND: The Contractor for and in consideration of certain payments to be made as hereafter specified, hereby covenants and agrees to perform and execute all of the provisions of this Contract and of all documents and parts attached hereto and made a part thereof, and at his own cost and expense to furnish and perform everything necessary and required to construct and complete, ready for its intended purpose, in accordance with the Contract and such instructions as the Engineer may give, acceptable to the Authority, in the times provided, all of the Work covered and included under Contract No. _____ covering _____ as herein described.

THIRD: In consideration of the performance by the Contractor of his covenants and agreements as herein set forth, the Authority hereby covenants and agrees to pay the Contractor according to the Schedule of Prices set forth in the Proposal with additions and deductions as elsewhere herein provided in the times and in the manner stated in the Specifications. This Agreement shall insure to the benefit of, and shall be binding upon the parties hereto, and upon their respective successors and assigns; but neither party hereto shall assign or transfer his interest herein in whole or in part without the consent of the other, except as herein provided.

IN WITNESS WHEREOF the parties to this Agreement have executed the same in quintuplicate.

AUTHORITY -

MAINE TURNPIKE AUTHORITY

By: _____

Title: CHAIRMAN

Date of Signature: _____

ATTEST:

Secretary

CONTRACTOR -

CONTRACTOR

By: _____

Title: _____

Date of Signature: _____

WITNESS:

CONTRACT BOND

KNOW ALL MEN BY THESE PRESENTS that _____
of _____ in the County of _____ and State of _____
as Principal, and _____ a Corporation duly organized under the
laws of the State of _____ and having a usual place of business in _____

As Surety, are held and firmly bound unto the Maine Turnpike Authority in the sum of _____ Dollars (\$_____.____),
to be paid to said Maine Turnpike Authority, or its successors, for which payment, well and truly
to be made, we bind ourselves, our heirs, executors, successors and assigns jointly and severally
by these presents.

The condition of this obligation is such that the Principal, designated as Contractor in the
foregoing Contract No. _____ shall faithfully perform the Contract on his part and
satisfy all claims and demands incurred for the same and shall pay all bills for labor, material,
equipment and all other items contracted for, or used by him, in connection with the Work
contemplated by said Contract, and shall fully reimburse the Obligee for all outlay and expense
which the Obligee may incur in making good any default of said Principal, then this Obligation
shall be null and void; otherwise it shall remain in full force and effect.

Signed and sealed this _____ day of _____, A.D., 201____

Witnesses:

CONTRACTOR

_____ (SEAL)

SURETY

_____ (SEAL)

(Surety must attach copy of Power of Attorney showing authority of Office or Agent to execute bonds)

FINAL LIEN AND CLAIM WAIVER AND AFFIDAVIT

Upon receipt of the sum of _____, which sum represents the total amount paid, including the current payment for work done and materials supplied for Project No. _____, in _____, Maine, under the undersigned's Contract with the Maine Turnpike Authority.

The undersigned, on oath, states that the Final Payment of _____ is the final payment for all work, labor, materials, services and miscellaneous (all of which are hereinafter referred to as "Work Items") supplied to the said Project through _____ and that no additional sum is claimed by the undersigned respecting said Project.

The undersigned, on oath, states that all persons and firms who supplied Work Items to the undersigned in connection with said Project have been fully paid by the undersigned for such Work Items or that such payment will be fully effected immediately upon receipt of this payment.

In consideration of the payment herewith made, the undersigned does fully and finally release and hold harmless the Maine Turnpike Authority, and its Surety, if any, from any and all claims, liens or right to claim or lien, arising out of this Project under any applicable bond, law or statute.

It is understood that this Affidavit is submitted to assure the Owner and others that all liens and claims relating to the Work Items furnished by the undersigned are paid.

(Contractor)

By: _____

Title: _____

State of MAINE
County of _____

I, _____, hereby certify on behalf of _____
(Company Officer) *(Company Name)*
its _____, being first duly sworn and stated that the foregoing representations are
(Title)
are true and correct upon his own knowledge and that the foregoing is his free act and deed in said capacity and the free act and deed of the above-named _____.
(Company Name)

The above-named, _____, personally appeared before me this ____ day of _____ and swears that this is his free act and deed.

(SEAL)

Notary Public

My Commission Expires: _____

MAINE TURNPIKE AUTHORITY

SPECIFICATIONS

PART I – SUPPLEMENTAL SPECIFICATIONS

Available at: <http://www.maineturnpike.com/Projects-Planning/Construction-Contracts.aspx>

(Rev. November 10, 2016)

MAINE TURNPIKE AUTHORITY

SPECIFICATIONS

PART II – SPECIAL PROVISIONS

PART II - SPECIAL PROVISIONS

<u>SECTION</u>	<u>TITLE</u>	<u>PAGE</u>
—	GENERAL DESCRIPTION OF WORK	SP-1
—	PLANS	SP-1
101.2	DEFINITION	SP-1
103.4	NOTICE OF AWARD	SP-1
104.3.8	WAGE RATES AND LABOR LAWS	SP-2
104.4.6	UTILITY COORDINATION	SP-4
104.4.7	COOPERATION WITH OTHER CONTRACTORS	SP-4
105.2.4.2	LEAD PAINT	SP-4
105.8.2	PERMIT REQUIREMENTS	SP-5
107.1	CONTRACT TIME AND CONTRACT COMPLETION DATE	SP-6
107.4.6	PROSECUTION OF WORK	SP-6
202.	REMOVING STRUCTURES AND OBSTRUCTIONS (Removing Existing Drain Troughs)	SP-7
202.	REMOVING STRUCTURES AND OBSTRUCTIONS (Removing Existing Bituminous Pavement)	SP-9
401.	HOT MIX ASPHALT PAVEMENT	SP-10
403.	HOT MIX ASPHALT PAVEMENT	SP-15
409.	BITUMINOUS TACK COAT	SP-17
507.	RAILINGS (Aluminum Bridge Railing – Splice Modification)	SP-19
515.	PROTECTIVE COATING FOR CONCRETE SURFACES (Pigmented Concrete Protective Coating)	SP-20
515.	PROTECTIVE COATING FOR CONCRETE SURFACES (Clear Concrete Protective Coating)	SP-24
518.	STRUCTURAL CONCRETE REPAIR (Granite Curb Joint Mortar and Bedding Mortar Repair)	SP-27

<u>SECTION</u>	<u>TITLE</u>	<u>PAGE</u>
	(Parapet Joint Repair)	
518.	STRUCTURAL CONCRETE REPAIR (Epoxy Injection Crack Repair)	SP-29
520.	EXPANSION DEVICES – NON MODULAR (Expansion Joint Modifications)	SP-31
524.	TEMPORARY STRUCTURAL SUPPORTS (Protective Shielding – Steel Girders)	SP-33
526.	CONCRETE BARRIER (Temporary Concrete Barrier Type I – Supplied by Authority)	SP-35
527.	ENERGY ABSORBING UNIT (Work Zone Crash Cushion)	SP-38
603.	PIPE CULVERTS AND STORM DRAINS (Pressure Treated Wood Drain Trough)	SP-40
607.	FENCES (Chain Link Fence – PVC Privacy Fence) (Bracing Assembly Type 1 – Metal Post)	SP-42
619.	MULCH (Mulch – Plan Quantity) (Temporary Mulch)	SP-43
643.	TRAFFIC SIGNALS (Flashing Beacon – Solar Powered)	SP-45
652.	MAINTENANCE OF TRAFFIC (Temporary Portable Rumble Strips)	SP-47
652.	MAINTENANCE OF TRAFFIC (Specific Project Maintenance of Traffic Requirements)	SP-49
652.	MAINTENANCE OF TRAFFIC (Automated Speed Limit Sign)	SP-51

MAINE TURNPIKE AUTHORITYSPECIFICATIONSPART II - SPECIAL PROVISIONS

All work shall be governed by the Maine Department of Transportation Standard Specifications, Revision of November 2014, except for that work which applies to sections of the Maine Department of Transportation Standard Specifications which are amended by the Maine Turnpike Supplemental Specifications and the following modifications, additions and deletions.

General Description of Work

The work consists of general repairs and modifications at the Danville Corner Road Bridge in Auburn, the Fisher Farm Road Bridge in Sabattus, and the Center Road Bridge in Litchfield over the Maine Turnpike and the Curtis Brook Culvert on Fisher Farm Road in Sabattus. The work includes pavement and membrane replacement, concrete deck, parapet, fascia, fascia overhang, pier, and abutment repairs, concrete wing wall and culvert wall repairs, bridge joint repairs, protective coatings, milling and paving, maintenance of traffic and all other work incidental thereto in accordance with the Plans and Specifications.

Plans

The drawings included in these Contract Documents, and referred to as the Plans, show the general character of the work to be done under this Contract. They bear the general title "Maine Turnpike Authority– Contract 2018.10 – Bridge and Culvert Repairs 4 Locations, Danville Corner Road Underpass (Mile 75.8) Curtis Brook Culvert (Mile 87.49) Fisher Farm Road Underpass (Mile 87.5) Center Road Underpass (Mile 91.9)". The right is reserved by the Resident to make such minor corrections or alterations in the Plans as he deems necessary without change in the unit prices on the Schedule of Prices of the Proposal.

101.2 DefinitionHolidays

The following is added after Memorial Day in the Supplemental Specifications:

Independence Day 2018
(Fourth of July)

Noon Tuesday to Noon Thursday

103.4 Notice of Award

The following sentence is added:

The Maine Turnpike Authority Board is scheduled to consider the Contract Award on January 25, 2018.

104.3.8 Wage Rates and Labor Laws

Section 104.3.8 Wage Rates and Labor Laws has been amended as follows:

The fair minimum hourly rates determined by the State of Maine Department of Labor for this Contract are as follows:

TO BE ISSUED BY ADDENDUM

104.4.6 Utility Coordination

This Subsection is amended by the addition of the following:

There are no utility impacts anticipated with this Contract. The Contractor shall conduct his work to avoid impacting the utilities at the various construction sites.

104.4.7 Cooperation With Other Contractors

This Subsection is amended by the addition of the following:

Adjacent contracts currently scheduled for the 2018 construction season include:

MTA Contract 2017.10 – Roadside Clearing, includes MM 85.0 to 100.8

MTA Contract 2018.04 – Bridge Painting, includes MM 101.7

MTA Contract 2018.07 – Androscoggin River Bridge Repair, MM 78.9

MTA Contract 2018.12 – Mainline Paving, MM 74.9 to 79.9

MTA Contract 2018.15 – Cobbosseecontee Stream Bridge Repair, MM 99.2

MTA Contract 2018.17 – Exit 75 Toll System Improvements, MM 75.0

The following Subsection is added:

105.2.4.2 Lead Paint

The Contractor shall note that the existing bridge structures contain lead based paint. The Contractor shall institute every precaution when working with materials coated with lead based paints.

Lead Paint Removal

The Contractor is required to remove and dispose of lead based paint and paint residue before cutting, grinding, drilling and sandblasting existing materials in preparation of completing the work except as provided under the Drilling of Lead Based Paint subsection in this Special Provision. All lead based paint and paint residue shall be removed, handled, stored and disposed of in conformance with all local, State and Federal laws and regulations governing lead based paint. The Contractor may use his own properly trained employees to abate the lead based paint in accordance with applicable regulations and requirements; or he may hire a licensed lead abatement subcontractor to abate the lead based paint in accordance with applicable regulations and requirements.

The Contractor, or licensed lead abatement subcontractor, shall submit a Project specific Health and Safety (OSHA) Plan and a Hazardous Waste Management Plan (EPA/DEP) a minimum of two (2) weeks prior to undertaking the removal of lead based paint.

Drilling of Lead Based Paint

The Contractor may drill lead based painted steel, without lead based paint removal, provided the Contractor collects and recycles the drill cuttings at a licensed metal recycling facility. If the Contractor chooses not to collect and recycle the drill cuttings at a licensed metal recycling facility he will be required to abate the area where drilling is to occur in full accordance with the lead based paint removal, storage and disposal requirement of this Special Provision.

The Authority will require a signed statement from the Contractor stating the drill cuttings were collected and recycled at a licensed metal recycling facility and the name the recycling facility.

Health and Safety Plan

The Health and Safety Plan submittal shall describe how the Contractor/licensed lead abatement subcontractor intends to remove the lead based paints; and shall outline how the Contractor/licensed lead abatement subcontractor will adhere to all Federal, State and local ordinances which govern worker (including authorized representatives of the Authority) exposure to lead based paints, and ensure the safety of the workers performing lead removal. Copies of current worker training certificates (OSHA), medical screenings, and respirator fit up shall be included in the submittal.

The following Subsection is added:

105.8.2 Permit Requirements

The Project is subject to the requirements of the Maine Pollutant Discharge Elimination System (MPDES) General Permit for Stormwater Discharge from Construction Activity, as promulgated by the US Environmental Protection Agency (US EPA) and Administrated by the Maine Department of Environmental Protection (DEP). A Notice of Intent (NOI) was not submitted by the Authority to the DEP for coverage under the Maine Construction General Permit (MCGP) due to the Limit of Disturbance (LOD) being less than one acre.

The LOD for this Contract has been estimated to be 0.15 acre for Danville Road Bridge, 0.09 acre for Curtis Brook Culvert, 0.16 acre for Fisher Farm Road Bridge, and 0.16 acre for Center Road Bridge for a total of 0.56 acre LOD.

At any time during the Contract, if the Limit of Disturbance needs to be adjusted to accommodate construction activities, the Contractor shall resubmit the LOD plan (including any additional erosion and sedimentation control measures needed) to the Resident for review and approval prior to any additional disturbance taking place:

- If the cumulative area of disturbance exceeds the estimated LOD noted above, by less than one acre, the Resident shall have a minimum of five (5) working days to approve the revised LOD plan.
- If the cumulative area of disturbance exceeds the estimated LOD noted above, by over one acre, the Resident shall first approve of the plan and then possibly submit

the NOI for MaineDEP approval. The approval may take a minimum of 21 working days.

Compliance with the erosion and sedimentation control requirements outlined in this Contract is required by the Contractor.

107.1 Contract Time and Contract Completion Date

This Subsection is amended by the addition of the following:

All work shall be completed on or before November 16, 2018.

Supplemental Liquidated damages on a calendar day basis in accordance with Subsection 107.8 shall be assessed for each calendar day that completion is not achieved.

107.4.6 Prosecution of Work

The following activities must be completed by the date specified:

- The Contractor will be allowed to close Danville Corner Road Bridge a maximum of twenty-one (21) calendar days. Work requiring lane or shoulder closures on the Mainline shall be scheduled to be complete by June 15, 2018. Supplemental Liquidated damages on a calendar day basis in the amount of one thousand dollars (\$1000) shall be assessed for each calendar day that completion is not achieved.
- The Contractor will be allowed to close Fisher Farm Road Bridge a maximum of fourteen (14) calendar days. The Contractor shall coordinate this closure around hay farming activities by Fisher Farm and provide them access across the bridge when practicable. Supplemental Liquidated damages on a calendar day basis in accordance with Subsection 107.8 shall be assessed for each calendar day that road closure extends beyond the allowed maximum.
- The Contractor will be allowed to close Center Road Bridge a maximum of twenty-one (21) calendar days. Supplemental Liquidated damages on a calendar day basis in accordance with Subsection 107.8 shall be assessed for each calendar day that road closure extends beyond the allowed maximum.
- Repairs to the bridge culvert over Curtis Brook shall be completed during the Fisher Farm Road closure and between June 15th and October 1, 2018. Supplemental Liquidated damages on a calendar day basis in accordance with Subsection 107.8 shall be assessed for each calendar day that road closure extends beyond the allowed maximum.

The Contractor shall submit to the Authority a construction schedule which shall document that the Contractor has the necessary labor and equipment to work immediately and continuously at the project site once the bridge is closed. The intent of this specification is to minimize the amount of time for bridge closure, while providing the Contractor sufficient time to complete the work in a diligent manner and reopen the bridge as prescribed by the project's Substantial Completion date.

SPECIAL PROVISION

SECTION 202

REMOVING STRUCTURES AND OBSTRUCTIONS

(Removing Existing Drain Troughs)

202.01 Description

The following paragraph is added:

The work shall consist of removing and disposing of the exposed portions of the existing drain troughs attached to, or in front of, the abutment bridge structures.

The work shall also consist of removing and disposing of the exposed portions of the existing drain trough downspouts, and plugging or sealing inlets of the downspout pipes buried in the abutment embankments at the bridge structures.

The filling and shaping of the void left by the removal of the existing drain troughs shall be filled with Granular Borrow and considered incidental to this item.

The following Subsections are added:

202.011 Materials

Plug material shall be Class A structural concrete, or a packaged structural concrete material from the MaineDOT's Qualified Products List.

Seal material shall be sheet metal, minimum 12 gauge.

202.025 General

All drain trough components removed shall be disposed of by the Contractor off of the turnpike right-of-way in accordance with the Maine Department of Environmental Protection Solid Waste Management Requirements.

Concrete plugs shall be a minimum of 24 inches long by the pipe diameter.

Seals shall be mechanically attached or welded to the pipe ends, and shall be caulked to prevent infiltration of water.

202.07 Method of Measurement

The following paragraph is added:

Removing Existing Drain Troughs shall be measured by the lump sum.

202.08 Basis of Payment

The following sentences are added:

Removing Existing Drain Troughs shall be paid for at the Contract lump sum price which includes all removals, disposal, granular borrow, plugs, seals and caulking, equipment and labor necessary to satisfactorily complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
202.191 Removing Existing Drain Troughs	Lump Sum

SPECIAL PROVISION

SECTION 202

REMOVING STRUCTURES AND OBSTRUCTIONS

(Removing of Existing Bituminous Pavement)

202.01 Description

This section is amended by the addition of the following:

All materials removed as part of this work shall become the property of the Contractor unless otherwise noted. The Contractor shall provide the Resident with an affidavit stating the final location of all disposed material and that the material was disposed of in accordance with the Maine Department of Environmental Protection Solid Waste Regulations.

202.031 Removing Existing Bituminous Pavement and Concrete Wearing Surface from Bridges and Scarifying the Top of Deck.

The first paragraph is amended by the addition of the following:

The use of milling equipment to remove existing bituminous pavement is not allowed.

SPECIAL PROVISIONSECTION 401HOT MIX ASPHALT PAVEMENT

Section 401 of the Maine Turnpike Authority 2016 Supplemental Specifications is modified as follows:

401.01 Description

The following paragraph is added:

A Quality Control Plan(QCP) is required.

401.02 Materials

Section 401.02 is deleted in its entirety and replaced with the following:

Aggregates for HMA Pavements Coarse Aggregate and fine aggregate for HMA pavements shall be graded such that when combined in the proper proportions, including filler if required, the resultant blend will meet the composition of mixture for the type of pavement specified. Materials shall meet the requirements specified in Section 700 – Materials:

Asphalt Cement	702.01
Aggregates for HMA Pavement	703.07
RAP for HMA Pavement	703.08
HMA Mixture Composition	703.09

Surface HMA Coarse aggregate: The material retained on the No. 4 sieve, shall consist of angular fragments obtained from crushed quarry stone and be free of dirt or other objectionable materials. Coarse aggregate shall have a Micro-Deval value of 16.0 percent or less as determined by AASHTO T 327. The crushed stone shall have a maximum of 1.5% material finer than the No. 200 mesh when tested in accordance with AASHTO T-11. Flat and elongated particles shall not exceed a maximum of 8% at a 5:1 ratio in accordance with ASTM D-4791. Coarse aggregate angularity shall be a minimum of 95/90 in accordance with AASHTO T-335.

Surface HMA Fine aggregate: The material passing the No. 4 sieve, shall be crushed manufactured sand free from dirt, clay balls, or other objectionable material. Natural sand may be incorporated into the mix at a rate no greater than 13 percent by weight of total aggregate. The unconfined void content of the fine aggregate blend shall be a 45 minimum value when tested in accordance with AASHTO T-304, method A. AASHTO T-176 sand equivalent value shall be 45 minimum.

Asphalt Low Modulus Joint Sealer: Asphalt Low Modulus Joint Sealer shall be a modified asphalt and rubber compound designed for sealing and improving the strength and performance of the base asphalt cement and shall conform to ASTM D6690 Type IV and the following specifications:

Cone Penetration	90-150
Flow @ 60°C [140°F]	3.0mm [1/8 in] max
Bond, non-immersed	Three 12.7mm [1/2 in] specimens pass 3 cycles @ 200% extension @ -29°C [-20°F]
Resilience, %	60 min
Asphalt Compatibility, ASTM D5329	pass*

* There shall be no failure in adhesion, formation of any oily exudate at the interface between the sealant and asphaltic concrete or other deleterious effects on the asphaltic concrete or sealant when tested at 60°C [140°F].

The contractor shall provide the Resident or authorized representative with a copy of the material manufacturer's recommendations pertaining to heating, application, and reheating prior to the beginning of operations or the changing of materials.

Section 401.03 Composition of Mixtures

Section 401.03 is deleted in its entirety and replaced with the following:

The Contractor shall compose the Hot Mix Asphalt Pavement with aggregate, Performance Graded Asphalt Binder (PGAB), and mineral filler if required. HMA shall be designed and tested according to AASHTO R35 and the volumetric criteria in Table 1. The Contractor shall size, uniformly grade, and combine the aggregate fractions in proportions that provide a mixture meeting the grading requirements of the Job Mix Formula (JMF). The Contractor may use a maximum of 15 percent reclaimed asphalt pavement (RAP) in any base, binder, surface, or shim course, unless otherwise noted. Current MaineDOT approved designs will be allowed on local roads.

The Contractor shall submit a job mix formula (JMF) developed for each specified mixture at least 30 days prior to placement.

The JMF shall establish a single percentage of aggregate passing each sieve size within the limits shown in Subsection 703.09. The mixture shall be designed and produced, including all production tolerances, to comply with the allowable control points for the particular type of mixture as outlined in Subsection 703.09. The JMF shall state the original source, gradation, and percentage to be used of each portion of the aggregate and mineral filler if required. It shall also state the proposed PGAB content, the name and location of the refiner, the supplier, the source of PGAB submitted for approval, the type of PGAB modification if applicable, and the location of the terminal if applicable.

In addition, the Contractor shall provide the following information with the proposed JMF:

- Properly completed JMF indicating all mix properties (Gmm, VMA, VFB, etc.).
- Stockpile Gradation Summary.
- Individual aggregate consensus properties
- Design Aggregate Structure Consensus Property Summary.
- Design Aggregate Structure Trial Blend Gradation Plots (0.45 power chart).
- Trial Blend Test Results for at least three different aggregate blends.
- Selected design aggregate blend.
- Test results for the selected design aggregate blend at a minimum of three binder contents.
- Test results for final selected blend compacted to N_{max} .
- Specific Gravity and temperature/viscosity charts for the PGAB to be used.
- Recommended mixing and compaction temperatures from the PGAB supplier.
- Material Safety Data Sheets (MSDS) For PGAB.
- Asphalt Content vs. Air Voids trial blend curve.
- Test report for Contractor's Verification sample.
- Summary of RAP test results (if used), including count, average and standard deviation of binder content and gradation.

At the time of JMF submittal, the Contractor shall identify and make available the stockpiles of all proposed aggregates at the plant site. There must be a minimum of 150 ton for stone stockpiles, 75 ton for sand stockpiles, and 50 ton of blend sand before the Authority will sample. The Authority shall obtain samples for laboratory testing. The Contractor shall also make available to the Authority the PGAB proposed for use in the mix in sufficient quantity to test the properties of the asphalt and to produce samples for testing of the mixture. Before the start of paving, the Contractor and the Authority shall split a production sample for evaluation. The Contractor shall test its split of the sample and determine if the results meet the requirements. If the results are found to be acceptable, the Contractor will forward their results to the Authority's Lab, which will test the Authority's split of the sample. The results of the two split samples will be compared and shared between the Authority and the Contractor. If the Authority finds the mixture acceptable, an approved JMF will be forwarded to the Contractor. The Authority will then notify the Contractor that paving may commence. The first day's production shall be monitored, and the approval may be withdrawn if the mixture exhibits undesirable characteristics such as checking, shoving or displacement. The Contractor shall be allowed to submit aim changes within

24 hours of receipt of the first Acceptance test result for an individual JMF. Adjustments will be allowed of up to 2% on the percent passing the 2.36 mm sieve through the 0.075 mm and 3% on the percent passing the 4.75 mm or larger sieves. Adjustments will be allowed on the %PGAB of up to 0.2 percent. Adjustments will be allowed on GMM of up to 0.010.

The Contractor shall submit a new JMF for approval each time a change in material source or materials properties is proposed. The same approval process shall be followed. The cold feed percentage of any aggregate except natural sand may be adjusted up to 10 percentage points from the amount listed on the JMF, however no aggregate listed on the JMF shall be eliminated. Natural sand may be adjusted up to 5 percent from the amount listed on the JMF but shall not exceed 13% by weight of total aggregates. The cold feed percentage for RAP may be reduced up to five percentage points from the amount listed on the JMF and shall not exceed the percentage of RAP approved in the JMF or for the specific application.

TABLE 1
VOLUMETRIC DESIGN CRITERIA

Design ESAL's (Millions)	Required Density (Percent of G _{mm})			Voids in the Mineral Aggregate (VMA)(Minimum Percent)					Voids Filled with Binder (VFB) (Minimum %)	Fines/Eff. Binder Ratio
				Nominal Maximum Aggregate Size (mm)						
	N _{initial}	N _{design}	N _{max}	25	19	12.5	9.5	4.75		
10 to <30	≤89.0	96.0	≤98.0	13.0	14.0	15.0	16.0	16.0	65-80*	0.6-1.2

* For 9.5 mm nominal maximum aggregate size mixtures, the maximum VFB is 82.

* For 4.75 mm nominal maximum aggregate size mixtures, the maximum VFB is 84.

* For 4.75mm nominal maximum aggregate size mixtures, the Fines/Effective Binder Ratio is 0.6-1.4

As part of the JMF submittal, there are Hamburg Wheel Tracker requirements, the Contractor shall provide the Authority the test results in accordance with AASHTO T324. The results shall be generated by a third party independent testing laboratory as approved by the Authority. The test results shall meet the requirements of Table 1A

TABLE 1A
HAMBURG WHEEL TRACKER REQUIREMENTS

Specified PG Binder Grade	Test Temperature (°C)	Maximum Rut Depth (mm)	Minimum Number of Passes	Minimum Allowable SIP*
64-28	45	12.5	20,000	15,000
64E-28	45	8.0	20,000	15,000

* As calculated by the most recently published version of the Maine DOT HWT worksheet, which is available online at <http://www.maine.gov/mdot/contractors/publications/>

Section 401.091 Material Transfer Vehicle (MTV)

The fourth paragraph shall be deleted and replaced with:

The MTV shall be designed so that the mix receives additional mixing action.

Section 401.165 Longitudinal Joint Density

The first paragraph shall be deleted and replaced with:

When noted in Special Provision Section 403, the Authority will measure the pavement density of longitudinal joints between adjoining mainline travel lanes in both the unconfined and confined condition as determined by the days paving operation.

The eighth paragraph shall be deleted and replaced with:

The minimum density of the completed pavement shall be 91.5 percent of the theoretical maximum density obtained. Two consecutive failing tests shall result in production shut down. Prior to resuming paving operations, the contractor quality control unit shall satisfy the Authority that the paving operation will produce joint densities in compliance with the Specifications.

The eleventh paragraph and associated table shall be deleted and replaced with:

Payment reduction will be applied to each subplot that has a density lower than 91.5% as outlined below.

PERCENT COMPACTION	PERCENT PAY
91.5 or greater	100
90.0 to 91.4	95
89.9 or less	90

Section 401.17 Joints

The fourth paragraph shall be deleted and replaced with:

When required by Special Provision Section 403, Mainline Longitudinal joints shall be constructed as notched-wedge joint and constructed in a manner that will best ensure joint integrity.

Section 401.191 Inspection/Testing

In paragraph nine delete and replace Item #8 with:

- 8. Secure High Speed Internet Access

SPECIAL PROVISIONSECTION 403HOT MIX ASPHALT PAVEMENT

Course	HMA Grading	Item Number	Total Thickness	No. of Layers	Complimentary Notes
--------	-------------	-------------	-----------------	---------------	---------------------

Danville Corner Road Bridge
Fisher Farm Road Bridge
Center Road Bridge

Wearing	12.5mm	403.208	1.5"	1	B,C,E,J,L,N
Base	12.5mm	403.213	1.5"	1	B,C,E,J,L,N

Bridge Approaches Mill and Fill

Wearing	12.5mm	403.208	1.5"	1	B,C,E,J,L,N
---------	--------	---------	------	---	-------------

COMPLEMENTARY NOTES

- A. The required PGAB for this mixture shall be **64E-28**.
- B. The required PGAB for this mixture shall be **64-28**.
- C. A maximum of 15 percent RAP may be used.
- D. RAP may not be used.
- E. The Maine DOT will conduct the job mix verification. The aggregate qualities shall meet the design traffic level of 3 to <10 million ESALS for mix placed under this contract. The design verification, Quality Control, and Acceptance tests for this mix will be performed at **75 gyrations**. (N design) Minimum and Maximum PGAB content shall not apply.
- F. The MTA will conduct the job mix verification. The aggregate qualities shall meet the design traffic level of 10 to <30 million ESALS for mix placed under this contract. The design verification, Quality Control, and Acceptance tests for this mix will be performed at **75 gyrations**. (N design)
- G. A material transfer vehicle (MTV) shall be used for the placement of Hot Mix Asphalt wearing surface on all roadways including acceleration and deceleration lanes and all ramps.
- H. Joints shall be constructed as the “notched wedge” type in accordance with Subsection 401.17.
- I. Joint density will be measured in accordance with Subsection 401.165.
- J. Tack coat shall be applied between all layers of pavement at a rate of 0.04 G/SY.
- K. PGAB shall conform to the provisions of 403.02 – Polymer Modified PGAB for HMA
- L. The contractor shall furnish a quality control technician equipped with an approved densometer to ensure density requirements are met.
- M. Hydrated Lime shall be incorporated into the mixture.
- N. No vehicular loads shall be permitted on newly completed pavement until adequate stability has been attained and the material has cooled sufficiently to prevent distortion or loss of fines. The newly paved area may be opened to traffic after the internal temperature of the pavement has cooled to 120° F. The Resident will test the internal temperature of

the pavement and shall be the sole judge as to the opening to traffic. The period of time before opening to traffic may be extended at the discretion of the Resident. The lane closure may not be removed until the internal temperature has cooled to 120° F.

SPECIAL PROVISION

SECTION 409

BITUMINOUS TACK COAT

409.02 Bituminous Material

This Subsection is deleted and replaced with the following:

Bituminous material shall conform to the Specifications for Emulsified Asphalt RS-1h, of the AASHTO Designation M-140.

409.05 Equipment

Add “or as determined by the Resident”, after the words “gal/yd²” in the fourth line of the second paragraph of this Subsection.

409.06 Preparation of Surface

The following paragraph is added:

All existing pavement and shoulder areas on which bituminous concrete mixtures are to be placed shall receive a tack coat. The surface area where the tack coat is to be applied shall be dry and cleaned of all dirt, sand, and loose material. Cleaning shall be accomplished by use of revolving brooms or mechanical sweepers. Undesirable material not removed by the above means shall be cleaned by hand sweeping or scraping, or a combination of both. Small areas otherwise inaccessible may be swept with hand brooms. The tack coat shall be applied only when the existing surface is dry.

409.08 Method of Measurement

The following paragraphs are added:

Measurement will be based on delivery slips made out in duplicate by the Contractor and signed by the Resident, or his representative, at the point of delivery. One of these slips shall be retained by the Resident and one by the Contractor. Delivery slips shall be furnished by the Contractor and shall provide space for identifying the vehicle and driver, for stating the volume of material carried, the source of the material, the date, and the Resident or his representative's signature.

Material included in the delivery slips and not used or rejected shall be deducted from the amount being measured for payment. Each day's delivery slips shall be reconciled by the Contractor and the Resident within 24-hours.

Cleaning of the surface area where tack coat is to be applied shall be incidental to Item 409.15, Bituminous Tack Coat - Applied.

409.09 Basis of Payment

The following pay items are added:

<u>Pay Item</u>		<u>Pay Unit</u>
409.15	Bituminous Tack Coat – Applied	Gallon

SPECIAL PROVISION

SECTION 507

RAILINGS

(Aluminum Bridge Railing – Splice Modification)

507.01 Description

The following sentence is added:

This work consists of re-centering the existing 3'-0" cast aluminum splice bar in the center of the bridge rail splice joint and mechanically fastening the splice bar to the aluminum bridge rail on one side of the bridge rail splice joint per the details on the Plans.

507.08 Method of Measurement

Aluminum Bridge Railing – Splice Modification will be measured for payment by each, satisfactorily modified and accepted.

507.09 Basis of Payment

Aluminum Bridge Railing – Splice Modification will be paid at the Contract unit price per each which price shall be full compensation for all labor, materials, equipment and incidentals required for re-centering and mechanically fastening the splice bar as shown on the Plans, in accordance with these Specifications or as approved by the Resident.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
507.095 Aluminum Bridge Railing – Splice Modification	Each

SPECIAL PROVISIONSECTION 515PROTECTIVE COATING FOR CONCRETE SURFACES

(Pigmented Concrete Protective Coating)

Section 515, Protective Coating for Concrete Surfaces, is deleted in its entirety and replaced with the following:

515.01 Description

The work shall include the surface preparation and application of a pigmented concrete protective coating system, consisting of a clear penetrating sealer followed by a pigmented top coat, to protect new and existing concrete and masonry structures. The coating system shall be applied to piers, endposts, wingwalls, abutments, curbs and fascia in accordance with the Plans, Specifications and the manufacturer's published recommendations.

Where pigmented protective coatings are already present on concrete surfaces specified to receive new protective coatings, the work shall also include removing areas of existing protective coating that are blistered, flaking, peeling or otherwise loosely adhered to the concrete substrate prior to application of the new coating. The removal of loosely adhered pigmented protective coatings shall be completed by high-pressure washing. Where the removal of existing pigmented coatings is required the anticipated removal limits, and the anticipated quantity of removal, will be shown on the plans. The actual removal limits may vary and will be established and marked in the field by the Resident.

515.02 Materials

The pigmented penetrating sealer system shall be a two coat system consisting of Certi-Vex Guard Clear (primer/sealer) and Certi-Vex HBC Smooth (top coat), as manufactured by Vexcon Chemicals, Inc., or an approved equal, consisting of the following two parts:

- The primer shall be a vinyl toluene acrylic silane polymer blend or an approved equal. This primer shall provide the main protection against the ingress of water borne chlorides and sulfates.
- The top coat shall be solvent borne modified acrylic resins with selected pigments and fillers.

The products shall comply with regulations limiting the Volatile Organic Compound (VOC) content of architectural and industrial maintenance coatings.

The Contractor shall submit the Vexcon Chemical's product data sheets, material safety data sheets and recommended instructions for application of the Certi-Vex Guard Clear and Certi-Vex HBC Smooth.

The pigmented penetrating sealer color shall be Concrete Gray.

Materials shall be delivered to the site in original packages or containers bearing the manufacturer's labels and identification.

515.021 Substitute Materials

The Contractor shall submit a written request for approval of proposed substitute material naming the proposed manufacturer and product. This request shall be accompanied by:

1. Test data from an independent testing laboratory stating that the proposed substitute meets or exceeds the specified requirements as listed and has been tested in accordance with the specified test standards.
2. Documentation that the proposed material has a proven record of performance when used in the intended application as confirmed by actual field tests and successful installations in place on at least five similar projects.
3. Certification that if two or more types of products are intended to be used as part of a system they will be supplied by the same manufacturer to ensure compatibility of materials, and to maintain single source manufacturer responsibility.

The Resident reserves the right to require additional testing to evaluate any proposed substitute product at no additional cost to the Authority. The Resident's decision as to the acceptability or non-acceptability of the proposed product shall be final.

515.03 Surface Preparation

All caulking, patching, and joint sealant shall be installed prior to application of the sealer. The surface shall be prepared in strict accordance with the instructions of the approved manufacturer. Surface shall be fully cured, dry, and free from contamination such as asphalt coatings, oil, grease, loose particles, decaying matter, moss, algae growth, and curing compounds. For maximum penetration of the primer, the Contractor shall lightly sandblast the surface.

Existing form tie hole plugs which are loose or deteriorated shall be completely removed. The holes shall be reamed to sound concrete. All open form tie holes, new and existing shall be filled with an approved non-shrinking mortar, and after setting, rubbed level to the adjacent surface. Filled holes shall be cured for at least two (2) days prior to the application of the concrete protective coating.

Grass and vegetation adjacent to surfaces to be coated shall be removed or trimmed closely to permit proper preparation and application of the coating.

Where coatings are specified to be applied to concrete surfaces that have been previously covered with pigmented coating, the Contractor shall remove any protective coating that, in the judgement of the Resident, is blistered, flaking, peeling or otherwise loosely adhered to the concrete substrate. Loosely adhered coating shall be generally defined as any coating that can be removed by vigorously scraping the concrete surface using a 3" steel putty knife and firm pressure. The goal of the removal work is to remove areas of flaking, missing or otherwise compromised

coating systems; protective coatings that are tightly adhered to the concrete substrate need not be removed.

The removal of existing protective coatings shall be completed using high pressure washing. The specific pressure, flow rate, nozzle and standoff distance for the high-pressure washing operation shall be selected by the Contractor to remove loosely adhered coatings as specified. After high-pressure washing the Resident shall verify all loosely adhered coatings have been removed from the specified areas by scraping the surfaces with a putty knife. The Contractor will be required to complete additional pressure washing to remove any remaining loosely adhered coatings identified by the Resident

Following removal of existing coating systems all exposed surfaces of the substructure unit to be coated shall be cleaned and rinsed by pressure washing. The Contractor may use, when required, appropriate cleaning materials recommended by the sealer manufacturer in conjunction with high pressure water for cleaning the concrete or masonry. After pressure washing the concrete surfaces shall be allowed to air dry for a minimum of 48 hours prior to applying the new protective coating.

The Contractor will be responsible for controlling and filtering runoff resulting from the pressure washing operations in accordance with Supplemental Specification 656, and all local, state and federal requirements.

515.04 Application

The materials shall be mixed and applied in strict accordance with the instructions of the approved manufacturer. Spray or roll the primer at the recommended application rate. If the surface is very absorbent, the primer should be applied until surface is saturated per the manufacturer's written instructions. All areas not to receive coating shall be marked with straight, even lines as the limit lines.

The Contractor shall, in the presence of the Resident, apply the materials on a sample area which is representative of a jobsite application. When color and application methods are approved, the sample area shall serve as a standard of acceptance for all further work.

The primer shall not be applied in direct sunlight when the air or surface temperature is greater than 90°F, or when air or surface temperature is below 35°F. The top coat shall not be applied when air or surface temperature is below 45°F or as approved by the Resident.

For surfaces that have previously received pigmented coating the primer shall only be applied to areas where the existing coating was marked for removal and then removed by sandblasting. The primer application shall extend beyond the removal limits of the existing coating system by six inches on all sides.

The primer shall be allowed to dry for a minimum of two-hours before applying pigmented top coat. Under poor drying conditions this time shall be extended. The primer shall not be coated with top coat until the surface is dry. The top coat should be applied by brush, roller or suitable airless spray.

Top coat material shall be applied per the manufacturer’s recommended application rate and in strict accordance with the manufacturer’s written instructions. The top coat shall provide consistent color without light spots or shadows. The Resident reserves the right to have the Contractor recoat the top coat if the dried top coat(s) lack consistent color or show light spots or shadows.

For surfaces that have previously received pigmented coating the top coat shall be applied to the complete limits of pigmented coating application as described on the Contract Plans, not just the area of old coating removal.

Regardless of the application method used (sprayer, roller or brush) the Contractor shall be responsible for achieving 100% coverage of the concrete including the interior surfaces of concrete voids, recesses, or other depressions on the concrete surface.

Protect plants, grass, sealant, asphalt, traffic, etc. during application from spray.

515.05 Method of Measurement

Pigmented Concrete Protective Coating will be measured for payment by the square yard, satisfactorily applied and accepted.

The removal of existing pigmented protective coatings will not be measured for payment separately, but shall be incidental to the Pigmented Protective Coating for Concrete Surfaces pay item.

515.06 Basis of Payment

Pigmented Concrete Protective Coating will be paid at the Contract unit price per square yard which price shall be full compensation for all labor, materials, equipment and incidentals required for furnishing and applying the pigmented concrete protective coating as shown on the Plans, in accordance with these Specifications or as approved by the Resident.

Surface preparation, including high-pressure washing to remove existing pigmented coatings, vegetation removal, and protection of surfaces not designated for treatment will not be paid for separately, but shall be incidental to the Pigmented Concrete Protective Coating item.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
515.201 Pigmented Protective Coating for Concrete Surfaces	Square Yard

SPECIAL PROVISIONSECTION 515PROTECTIVE COATING FOR CONCRETE SURFACES

(Clear Concrete Protective Coating)

Section 515, Protective Coating for Concrete Surfaces, is deleted in its entirety and replaced with the following:

515.01 Description

The work shall include the surface preparation and application of a clear protective coating on concrete surfaces to protect new cast-in-place concrete, precast concrete and masonry structures. The coating system shall be applied to piers, endposts, curbs and fascia in accordance with the Plans, Specifications and the manufacturer's published recommendations.

515.02 Materials

The penetrating sealer shall be StandOff® SLX100 Water & Oil Repellent, as manufactured by ProSoCo, Inc., or an approved equal. The sealer shall have the following properties:

Active Substance:	modified alkyl alkoxy silane
Active Content:	> 90%
Form:	clear liquid
VOC:	< 3.5 pounds per gallon

The product shall comply with regulations limiting the Volatile Organic Compound (VOC) content of architectural and industrial maintenance coatings.

The Contractor shall submit the ProSoCo's product data sheets, material safety data sheets and recommended instructions for application of the StandOff® SLX100.

Materials shall be delivered to the site in original packages or containers bearing the manufacturer's labels and identification.

515.021 Substitute Materials

The Contractor shall submit a written request for approval of proposed substitute material naming the proposed manufacturer and product. This request shall be accompanied by:

1. Test data from an independent testing laboratory stating that the proposed substitute meets or exceeds the specified requirements as listed and has been tested in accordance with the specified test standards.

2. Documentation that the proposed material has a proven record of performance when used in the intended application as confirmed by actual field tests and successful installations in place on at least five similar projects.
3. Certification that if two or more types of products are intended to be used as part of a system, they will be supplied by the same manufacturer to ensure compatibility of materials, and to maintain single source manufacturer responsibility.

The Resident reserves the right to require additional testing to evaluate any proposed substitute product at no additional cost to the Authority. The Resident's decision as to the acceptability or non-acceptability of the proposed product shall be final.

515.03 Surface Preparation

All caulking, patching, and joint sealant shall be installed prior to application of the sealer. On new surfaces to be treated, all voids shall be dressed by dry rubbing to remove form marks and blemishes to present a neat appearance. Concrete and masonry surfaces shall be cleaned free of dust, surface dirt, oil, efflorescence and contaminants to ensure penetration of the sealer. The surface may be slightly damp at the time of treatment.

The Contractor may use, when required, appropriate cleaning materials recommended by the sealer manufacturer in conjunction with high pressure water for cleaning the concrete or masonry.

515.04 Application

The Contractor shall apply the clear concrete protective coating in strict accordance with the manufacturer's published recommendations.

The application shall not be conducted when surface and air temperatures are below 40°F or above 90°F. The work shall not be conducted when there is a chance of the surface temperature falling below 40°F in the 24-hours following application; nor should it be applied on hot, windy days.

The treatment shall not be applied during rain to wet surfaces or when there is a chance of rain within 24-hours after application. After treatment, surfaces should be protected from rain for not less than 48-hours. It shall not be applied when winds are sufficient to carry airborne chemicals to unprotected surfaces.

Prior to applying the sealer, the Contractor shall protect all surrounding non-masonry/non-concrete surfaces, landscape and lawn areas, and surfaces not designated for treatment, from contact with the penetrating sealer, and prevent overspray of the penetrating sealer caused by wind drift.

The Contractor shall ensure that all safety equipment, facilities and precautions recommended by the product manufacturer are furnished and/or strictly adhered to.

The sealer material shall be applied in the manner and with the equipment recommended by the product manufacturer. Coverage will vary depending on condition, texture and porosity of the surfaces. Pre-testing is required.

Sealer shall be applied as packaged without dilution or alteration. The sealer shall be applied with low pressure (20 psi) airless spray equipment or with a heavily saturated brush or roller unless otherwise permitted by the Resident. Sufficient material shall be applied to thoroughly saturate the surface making sure to brush out excess material that does not penetrate.

When the sealer is applied to horizontal surfaces, it shall be applied in a single saturating application with sufficient material and applied so the surface remains wet for one to two minutes before penetration into the concrete. Surface residues, pools and puddles shall be broomed-out thoroughly until they completely penetrate into the surface.

When the sealer is applied to vertical and sloped surfaces, it shall be applied in a "wet-on-wet" application for best results on most porous materials. In the case of extremely dense concrete, it may be necessary to restrict the amount of material applied to one saturating application in order to prevent surface darkening. Apply from the bottom up with sufficient material to thoroughly coat the surface and create a slight rundown below the spray pattern. Allow the first application to penetrate the concrete surface, and within a few minutes after the first coat appears dry, reapply in the same saturating manner.

When the sealer is applied to vertical and sloped surfaces, it shall be applied in two applications, 10 minutes apart, with a low pressure (20 psi) airless sprayer.

515.05 Method of Measurement

Clear Protective Coating for Concrete Surfaces will be measured for payment by the square yard, satisfactorily applied and accepted.

515.06 Basis of Payment

Clear Protective Coating for Concrete Surfaces will be paid at the Contract unit price per square yard which price shall be full compensation for all labor, materials, equipment and incidentals required for furnishing and applying the clear concrete protective coating as shown on the Plans, in accordance with these Specifications or as approved by the Resident.

Surface preparation, vegetation removal, and protection of surfaces not designated for treatment will not be measured separately for payment, but shall be incidental to the Clear Concrete Protective Coating item.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
515.202 Clear Protective Coating for Concrete Surfaces	Square Yard

SPECIAL PROVISION

SECTION 518

STRUCTURAL CONCRETE REPAIR

(Granite Curb Joint Mortar and Bedding Mortar Repair)
(Parapet Joint Repair)

518.01 Description

The following sentence is added:

This work shall consist of the removal and replacement of existing deteriorated granite curb joint mortar and granite curb bedding mortar as shown on the plans and as approved by the Resident.

Areas of existing deteriorated granite curb bedding mortar less than ½ inch in depth, will not be repaired under this pay item but shall be repaired as requested by the Resident using hand tools and equipment unit prices. Materials required shall be receipted costs plus 15%. Small tools, defined as those costing less than \$600, shall be incidental to the hand labor item.

This work shall also consist of the removal and replacement of existing deteriorated parapet joint sealant as approved by the Resident. The Contractor shall provide the Resident safe access to all the parapet joints for inspection before this work begins, including access to the fascia parapet joints.

518.02 Repair Materials

The following sentence is added:

Mortar shall be an approved epoxy resin mortar or an approved polymer modified cementitious repair mortar.

The following Subsection is added:

518.032 Construction Requirements

After the existing wearing surface is removed, the Resident will designate areas where the existing granite curb joint mortar and the existing granite curb bedding mortar is to be repaired.

In areas designated for Granite Curb Joint Mortar Repair, the existing granite curb joint mortar shall be removed between curb sections to a minimum depth of 1 in. from the face of curb. Any loose mortar shall also be removed. The repair area shall be repointed with new mortar and tooled concave at the face of curb. The mortar shall be proportioned, mixed, and applied in accordance with the Manufacturer's recommendations.

In areas designated for Granite Curb Bedding Mortar Repair, the existing granite bedding mortar shall be removed under the curb to a minimum depth of 1 in. from the face of curb. Any

loose or deteriorated mortar shall also be removed. The mortar shall be replaced with new mortar and finished flush with the face of curb. The mortar shall be proportioned, mixed, and applied in accordance with the Manufacturer's recommendations.

After the Resident has identified the joint repair locations, the Contractor shall remove the existing joint sealant to a minimum 3/8 inch depth, clean and prepare the concrete surfaces per sealant manufacturer recommendations, and replace the sealant to the edge of concrete with an approved polyurethane-based sealant such as Sikaflex-1a or other product on the MaineDOT approved products list as directed by the Resident.

518.10 Method of Measurement

The following sentence is added:

Granite Curb Joint Mortar and Bedding Mortar Repair will be measured for payment by the linear foot along the face of the curb, horizontally and vertically, complete and accepted.

The quantity of Parapet Joint Repair will be measured by the linear foot where the repair occurs.

518.11 Basis of Payment

The following sentence is added:

Granite Curb Joint Mortar and Bedding Mortar Repair will be paid for at the contract unit price per linear foot, which includes all materials, labor, equipment, and incidentals necessary to complete the work including removal of existing mortar.

Parapet Joint Repair will be paid for at the Contract unit price per linear foot, which includes all materials, labor, equipment, and incidentals necessary to complete the work including removal of existing joint sealant.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
518.39 Granite Curb Joint Mortar and Bedding Mortar Repair	Linear Foot
518.43 Parapet Joint Repair	Linear Foot

SPECIAL PROVISIONSECTION 518STRUCTURAL CONCRETE REPAIR

(Epoxy Injection Crack Repair)

518.01 Description

The following paragraphs are added:

The work includes epoxy injection crack repair as described below.

- Epoxy Injection Crack Repair includes all concrete crack widths equal to or greater than 0.06 inches as shown on the Plans or identified by the Resident.

518.02 Repair Materials

The following paragraphs are added:

Epoxy injection crack repair shall be completed using a high strength, low viscosity moisture tolerant epoxy resin as recommended by the manufacturer and approved by the Resident. The proposed repair materials shall be submitted to the Resident for approval.

The structural properties of all crack repair materials shall meet or exceed the following requirements:

Tensile Strength (@ 7 days)	5,000 psi	ASTM D638
Bond Strength (@ 14 days)	1,000 psi	ASTM C882
Compressive Strength (@ 3 days, 73 °F)	5,000 psi	ASTM D695
Compressive Modulus (@ 7 days)	250 ksi	ASTM D695
Flexural Strength (@14 days)	8,000 psi	ASTM D790

Wide cracks (1/2" +/- and greater) may be repaired with a non-shrink cementitious grout as recommended by the manufacturer. The following product shall be used:

- CONSPEC UW300 as manufactured by Dayton Superior, 7777 Washington Village Drive, Suite 130, Dayton OH, 45459

The following Subsection is added:

518.071 Placing Epoxy Injection Materials

- a) Mix epoxy components per manufacturer's instructions. Review pot life characteristics of combined materials and prepare quantities accordingly;
- b) Open all injection ports along the crack and ensure that all injection ports are securely fastened to the concrete substrate;

- c) Attach injection device to the lowest port on vertical cracks, or the first port in the series on horizontal cracks;
- d) Slowly and under constant pressure, inject the epoxy material into the first port until the epoxy flows out of the next port in the series. While maintaining constant pressure and flow at the first port, close the adjacent port and continue injection process until epoxy flows from the subsequent port in the series, or until no additional epoxy can be injected into the first port.
- e) Repeat the above procedure until all ports have been injected.

518.10 Method of Measurement

The following paragraph is added:

The quantity of Epoxy Injection Crack Repair will be measured by the linear foot.

518.11 Basis of Payment

The following paragraph is added:

Epoxy Injection Crack Repair will be paid at the Contract unit bid price per linear foot for each repair; which price shall include, but not necessarily be limited to, removal and disposal of materials, cleaning existing concrete, placing, curing and finishing epoxy and all materials, labor, equipment, tools and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
518.40 Epoxy Injection Crack Repair	Linear Foot

SPECIAL PROVISIONSECTION 520EXPANSION DEVICES – NON MODULAR

(Expansion Joint Modifications)

520.01 Description

This work consists of removing the existing joint seals, modifying and cleaning the existing steel rails and joint armor, and installing new replacement seals in the bridge joints at the Danville Corner Road, Fisher Farm Road, and Center Road Bridges in accordance with the Plans and this Specification.

520.02 Materials

Replacement joints shall be Expansion Device - Gland Seal and shall meet the material requirements of Section 520 - Expansion Devices - Non-Modular Expansion Joints for Danville Corner Road and Center Road Bridges.

Materials for bonded silicone-and-foam hybrid seals (used on Center Road Bridge) shall meet the material requirements of Expansion Device - Compression Seal specified in this Subsection except the joint shall be an EMSEAL Bridge Expansion Joint System (BEJS) seal (bonded silicone and foam hybrid seals are not covered on the Maine Department of Transportation Prequalified List of Approved Products).

520.06 Installation

Existing steel shall be cleaned and sandblasted prior to the installation of the new joint steel. Any portions of the existing steel rails within the parapet joint opening that must be removed to fit the new joint rails shall be ground smooth prior to installation of the new joint steel rails.

The Contractor shall install the replacement joint seals according to the manufacturer's recommendations. Replacement bonded silicone and foam hybrid seals, and gland seals shall be installed full deck width (including turn-ups within parapets) in one piece after the existing seals are removed and the existing seal extrusions or joint armor are repaired, cleaned, sandblasted and primed (if priming is recommended by the seal manufacturer). Additionally, the EMSEAL manufacturer's technical representative shall be on site for the first day of installation of this seal and all costs associated with this shall be considered incidental to the appropriate pay item listed below.

Once the new gland seals are permanently installed, the Contractor shall thoroughly clean the abutment seats, bearings, and girder ends by pressure washing to remove any debris, salt, or other foreign contaminants. Payment for pressure washing shall be incidental to the Expansion Device Modifications item.

520.07 Method of Measurement

Expansion Device Modifications will be measured by each unit, complete in place and accepted.

520.08 Basis of Payment

The accepted quantity of expansion devices will be paid for at the contract unit price each, which shall be full compensation for removal and disposal of the existing joint seal, cleaning and partial removal of existing steel rails, installation of new joint armor, and all materials, coatings, equipment, labor and incidentals necessary for furnishing and installing the new seals.

Payment will be made under:

<u>Pay Item</u>		<u>Pay Unit</u>
520.2211	Expansion Device Modifications (Danville Corner Road)	Each
520.2211	Expansion Device Modifications (Fisher Farm Road)	Each
520.2211	Expansion Device Modifications (Center Road)	Each

SPECIAL PROVISIONSECTION 524TEMPORARY STRUCTURAL SUPPORTS

(Protective Shielding - Steel Girders)

524.01 Description

The following paragraph is added:

This work shall also consist of furnishing all labor, equipment and materials required to provide protection for the public during demolition and construction. This protection shall include, but not necessarily be limited to, protective shielding of existing structures during demolition work, concrete removal, and installation of temporary deck support over roadway lanes and shoulders on all existing and new bridge structures.

The following Subsections are added:

524.031 Protective Shielding Design

Prior to the start of work, the Contractor shall submit working drawings for review and comment indicating the sizes and dimensions of protective shielding. If the shielding is to be attached to prestressed concrete components the submittal shall be coordinated with the respective precast concrete shop drawings. The proposed methods of protective shielding, including connections and fasteners, shall be in accordance with the following criteria:

The protective shielding shall be designed for safely supporting all construction and dead loads, but not less than 100 pounds per square foot with a load duration of seven (7) days. Protective shielding shall be stiff enough to limit deflection to 1/2 inch under maximum loads and to be tightly sealed at all joints. The protective shielding shall be placed on the tops of the bottom flanges of the steel girders, or between the web or bottom flanges of the concrete I-girders, with edges and laps made tight to protect the turnpike motorists from dust, debris and falling objects.

524.041 Protective Shielding Erection and Removal

No portion of the protective shielding installed over a roadway shall project below a plane connecting the bottoms of the bottom flanges of the steel stringers or concrete I-girders. During demolition operations, the protective shielding shall be covered with sheet plastic made tight at edges and laps to prevent water used in the sawcutting operation from falling onto the facilities under the bridge.

The protective shielding on existing and new structures shall extend horizontally three feet beyond the fascia lines and vertically to a point one foot minimum above the top of parapet or railing. The shielding shall also extend 10 feet beyond the edge of pavement of the roadway below, unless otherwise noted on the Plans or as approved by the Resident.

Shielding shall be approved and installed prior to the start of any demolition work and shall remain in position during all demolition work. Shielding shall also be approved and installed prior to the start of any deck forming and shall remain in position during all deck work. The shielding shall be relocated or removed only as approved by the Resident.

Construction sequences may require protective shielding material to be removed, stored and then reinstalled by the Contractor. Any shielding which is damaged during this removal and reinstallation shall be replaced by the Contractor at no additional cost.

524.28 Method of Measurement

The following paragraph is added:

Protective Shielding will not be measured separately for payment, but shall be considered incidental to the related contract items under Section 518.

SPECIAL PROVISION

SECTION 526

CONCRETE BARRIER

(Temporary Concrete Barrier Type I - Supplied by Authority)

526.01 Description

The following paragraphs are added:

This work shall consist of loading, transporting, setting, resetting, removing, transporting and stacking Temporary Concrete Barrier Type I – Supplied by Authority. The barrier shall have attachments allowing individual sections to be connected into a continuous barrier.

The work also includes supplying connecting pins and furnishing and mounting retro-reflective delineators, per Subsection 526.02 and 526.03.

Concrete barriers supplied by Authority shall be available at the following location(s):

<u>Maintenance Area</u>	<u>Linear Feet of Barrier</u>
Crosby Maintenance Area Mile 46 Southbound	900

Upon substantial completion of work, the Contractor shall remove and transport the barrier back to its maintenance area of origin. All barrier shall be returned, sorted and stacked according to type in locations directed by the project Resident or maintenance area foreman.

526.02 Materials

The following paragraphs are added:

- e. Delineators shall be bi-directional with a minimum effective reflective area of eight square inches as approved by the Resident. The reflectors shall be methyl methacrylate and the housing of acrylonitrile butadiene styrene. Color shall be in accordance with the MUTCD.

526.021 Acceptance

The Resident shall have the authority to accept or reject all Temporary Concrete Barrier Type I – Supplied by Authority used on the Project that does not meet the requirements of this specification

526.03 Construction Requirements

The following paragraphs are added:

The Contractor shall notify the Resident prior to the scheduled pick-up and delivery of concrete barrier. No barrier shall be removed from or stacked at the Turnpike Maintenance Area without approval of the Resident.

The Contractor shall move and place barrier-utilizing methods that will not damage the barrier. Barrier that is damaged by the Contractor by failing to use proper methods shall be replaced by the Contractor at no additional cost to the Maine Turnpike Authority.

Concrete barrier supplied by the Authority consists of several different styles. Not all barriers may be compatible. The Contractor shall utilize caution when setting barrier to use identical barrier types as adjacent barrier. Non-compatible barrier that cannot be attached together shall be overlapped by a minimum of 10 feet with the blunt end on the non-traffic side of the barrier. This work will not be measured separately for payment, but shall be incidental to the concrete barrier.

Concrete barrier placed at roadway low points shall be shimmed on 1" by 2" by 2' long wood planks to allow drainage to pass under the barrier. In addition, the Resident may direct the Contractor to shim the concrete barrier at other locations to provide for proper roadway drainage. All labor, material, and equipment necessary to shim the barrier will not be measured separately for payment, but shall be incidental to the Concrete Barrier.

The removal of concrete barrier from adjacent to the travel lane may be conducted without a lane closure if it is accomplished in accordance with the following requirements:

1. Barrier is removed from the trailing end and the workmen and equipment involved in the operation are always behind the barrier. No workmen or equipment shall enter the travel lane.
2. Barrier shall be dragged away from the travel lane to at least a 30-degree angle by the use of a cable.
3. Barrier shall be lifted no more than six inches while within 10 feet of the travel lane.

Retro-Reflective Delineators shall be mounted as follows:

1. One on top of each barrier.
2. One on the traffic side of every barrier used in a taper.
3. One on the traffic side of every other barrier at regularly spaced intervals and locations.
4. Delineators shall be installed on both sides of the barrier if barrier is used to separate opposing traffic.
5. Delineators shall be physically adhered so as to withstand the force of throw from a snow plow.
6. If more than 25% of delineators in any 50 foot section of barrier fall off for any reason, the Contractor will be responsible for reinstalling all the delineators in that run at that their own cost.
7. Contractor is required to submit the installation method for review and approval to the Resident.

526.04 Method of Measurement

The following paragraphs are added:

Temporary Concrete Barrier Type I – Supplied by Authority shall be measured for payment by the lump sum.

The loading, transporting, setting, resetting, removing, transporting, sorting and stacking of the barrier, the furnishing, installation and maintenance of the barrier delineators, and furnishing and installing connector pins will not be measured separately for payment, but shall be incidental to the cost of the Barrier. Temporary storage of Concrete Barrier between construction phases, if required, will not be measured separately for payment, but shall be incidental to the cost of the Barrier. All equipment required to load, unload, transport and stack Concrete Barrier shall be supplied by the Contractor.

Any Barrier lost or damaged by the Contractor shall be replaced by the Contractor at no additional cost to the Authority.

526.05 Basis of Payment

The fifth paragraph is deleted and not replaced.

The following paragraphs are added:

Temporary Concrete Barrier Type I – Supplied by Authority will be paid for at the Contract lump sum price, complete in place. Such payment shall be full compensation for loading, transporting, setting, resetting, temporary storage, removing, transporting and stacking at the area designated, furnishing all materials, and all other incidentals necessary to complete the work. Temporary Concrete Barrier Type I – Supplied by Authority and all connecting pins shall remain the property of the Authority, and shall be returned to the Turnpike Maintenance Area as designated in Subsection 526.01.

Payment of Concrete Barrier shall be based on a percentage of the work accomplished during that pay period.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
526.306 Temporary Concrete Barrier, Type I – Supplied by Authority	Lump Sum

SPECIAL PROVISION

SECTION 527

ENERGY ABSORBING UNIT

(Work Zone Crash Cushion)

527.01 Description

The first paragraph is deleted in its entirety and replaced with the following:

The Contractor shall furnish and install work zone crash cushions where shown on the Plans, as specified herein, in Special Provision 652, or as approved by the Resident. Work zone crash cushions are required at each exposed end of temporary concrete barrier or guardrail.

The exposed end of the concrete barrier within 30 feet of the mainline travel lane shall be protected at all times. Barrier shall not be reset until after the work zone crash cushion(s) has been set to protect the exposed end of the barrier.

527.02 Materials

The following paragraph is added:

Only work zone crash cushions meeting the NCHRP Report 350 TL-3 crash test requirements may be used on the turnpike and local roadways with posted speeds of 45 MPH or greater. Work zone crash cushions meeting the NCHRP Report 350 TL-2 crash test requirements may be used on local roadways with posted speeds of 40 MPH or less. The Contractor shall provide the Resident with documentation of the proposed work zone crash cushion's NCHRP Report 350 Crash Test Results prior to installation at the jobsite.

527.03 Construction Requirements

The following is added to the end of the first paragraph:

The design speeds for work zone crash cushions shall be 45 mph for local road and 70 mph for turnpike roadways unless otherwise noted on the Plans.

527.04 Method of Measurement

Work Zone Crash Cushions used to protect exposed ends of guardrail for steel girder erection will not be measured separately for payment, but shall be included under the Maintenance of Traffic for Steel Girder Erection item.

527.05 Basis of Payment

Payment will be made under:

Pay Item

Pay Unit

527.341 Work Zone Crash Cushions – TL-3

Unit

SPECIAL PROVISION

SECTION 603

PIPE CULVERTS AND STORM DRAINS

(Pressure Treated Wood Drain Trough)

603.01 Description

The following paragraphs are added:

This work shall also consist of furnishing and installing pressure treated wood drain trough at the locations shown on the Plans or as directed by the Resident.

603.02 Materials

The following paragraphs are added:

Wood for pressure treated wood drainage trough shall be Yellow Pine, Number 2 or better, .40 CCA, D4 S. The pressure treated wood shall meet AWWA Standard P-5 or Federal Standard TT-W-550. The treating process shall meet Federal Specification TT-W-571, or AWWA Commodity Standards as applicable.

Assembly hardware shall be heavy zinc plated or stainless steel.

Caulking shall be Sikaflex 1a, or an approved equal.

Trough liner material shall be W.R. Grace Ice and Water Shield roofing underlayment, or approved equal.

603.03 General

The following paragraphs are added:

The pressure treated wood drainage trough shall be fabricated and installed in a workmanlike manner. Corners shall be mitered; adjacent boards and sections shall be butt jointed at a wide cleat, or spliced with a full dimensioned piece of pressure treated wood; and fastener holes shall be predrilled to prevent splitting.

The trough liner shall be installed prior to installation of the top cleats, and shall wrap the top edge and 2 inches down the exterior face of the trough sideboard; and shall be held in place with galvanized roofing nails.

The pressure treated wood drain trough shall be backfilled to the top of the side rail with materials available from on-site excavation, supplemented with common borrow, if required.

603.11 Method of Measurement

The following paragraphs are added:

Pressure treated wood drain trough will be measured by the length in linear feet along the centerline of the invert, laid as directed, complete in place and accepted.

Excavation, bedding and backfill will not be measured separately but shall be incidental to the Pressure Treated Wood Drain Trough pay item.

Common borrow will not be measured under this item but shall be measured under Item 203.25 Common Borrow.

603.12 Basis of Payment

The following paragraphs are added:

The accepted quantity of pressure treated wood drainage trough will be paid at the Contract unit price per linear foot.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
603.91 Pressure Treated Wood Drain Trough	Linear Foot

SPECIAL PROVISION

SECTION 607

FENCES

(Chain Link Fence - PVC Privacy Fence)
(Bracing Assembly Type I - Metal Post)

607.01 Description

The following sentence is added:

This work shall consist of the construction of chain link fence with PVC privacy slats in accordance with these Specifications and as shown on the Plans.

607.02 Materials

The following sentences are added:

Privacy slats shall be either a PVC material or PVC coated material that meets the following requirements:

- Tensile Strength: 3,700 psi
- Resistance to heat: 250°F
- Low temperature brittleness: -105°F
- Flexural stiffness: 120,000 psi

The color of the privacy slats, chain link fabric, posts, bracing, and all hardware shall be brown in color.

607.05 Chain Link Fence

Paragraph d. is deleted and replaced with the following:

d. Tension Wire: A seven gage tension wire shall be used.

The following sentence is added:

Privacy slats shall be installed in accordance with the manufacturer’s recommendations and to the satisfaction of the Resident.

607.07 Basis of Payment

Payment will be made under:

<u>Pay Item</u>		<u>Pay Unit</u>
607.171	Chain Link Fence – 6 foot PVC Privacy Fence	Linear Feet
607.32	Bracing Assembly Type I – Metal Posts	Each

SPECIAL PROVISION

SECTION 619

MULCH

(Mulch – Plan Quantity)
(Temporary Mulch)

619.01 Description

The first paragraph is modified by the addition of the following:

“as a temporary or permanent erosion control measure” after the word “mulch”.

Add the following sentence at the end of the first paragraph:

Refer to Section 656 Temporary Soil and Water Pollution Control, for more information on Temporary Mulch.

619.03 General

The first paragraph is deleted and replaced with the following:

Cellulose fiber mulch shall not be used within 200 feet of a wetland or stream. The limits shall be 200 feet up station and down station of the wetland or streams as well as the slopes adjacent to the stream. The application of hay or straw mulch with an approved binder shall be used at these locations to prevent erosion.

The use of cellulose fiber mulch will only be allowed at other areas with the approval of the Resident. The Contractor may be required to demonstrate that the material may be applied in a manner that will prevent erosion and will aid in the establishment of permanent vegetation. The Resident reserves the right to require the use of hay or straw mulch at all locations if he determines that the cellulose mulch is ineffective. Cellulose fiber mulch is not acceptable for winter stabilization.

610.06 Method of Measurement

The following sentence is added:

Temporary Mulch will be paid for by the lump sum.

656.10 Basis of Payment

Temporary Mulch will be paid for at the Contract price per lump sum which shall be full compensation for furnishing and spreading the Temporary Mulch as many times as necessary as determined by the Contractor’s operations and staging. The price shall also include the additional mulch netting and snow removal necessary during the winter months.

Payment will be made under:

Pay Item

619.1201 Mulch – Plan Quantity
619.1202 Temporary Mulch

Pay Unit

Unit
Lump Sum

SPECIAL PROVISION

SECTION 643

TRAFFIC SIGNALS

(Flashing Beacon – Solar Powered)

643.01 Description

The following paragraphs are added:

This special provision provides for the installation of two dual head flashing beacons at the locations shown on the plans and as directed by the Resident.

643.021 Materials

The following paragraphs are added:

The flashing beacon shall consist of the following list of major materials:

- 2 – P & K signal pole model SP-114 or approved equal.
- 2 – 12 inch amber flashing beacons powered by solar panel. Units shall be JSF Technologies FL Series -24 Hour Flashing Beacon FL -2400 or an approved equal.

643.03 General

The Contractor shall furnish twelve (12) inch amber flashing beacons powered by a solar panel with battery backup. Units shall have internal programmable timings for flash interval. The beacons shall be mounted immediately above the indicated merge signs and be clearly visible by oncoming traffic.

643.18 Method of Measurement

The following paragraphs are added:

Flashing Beacon – Solar Powered will be measured by each unit authorized and installed on the Project.

643.19 Basis of Payment

The following paragraphs are added:

The accepted quantity of Flashing Beacon – Solar Powered will be paid for at the Contract unit price per unit. This price shall be full compensation for all labor, materials and equipment necessary to furnish and install Flashing Beacons.

Payment will be made under:

Pay Item

Pay Unit

643.712 Flashing Beacon – Solar Powered

Each

SPECIAL PROVISION

SECTION 652

MAINTENANCE OF TRAFFIC

(Temporary Portable Rumble Strips)

652.01 Description:

This work consists of furnishing and placing temporary portable rumble strips RoadQuake 2F TPRS or an approved equal.

652.02 Materials:

Furnish a temporary portable rumble strip system, which includes a method to transport and move these to on-site locations where they will be used. The Contractor shall submit for approval, literature and all necessary certifications to the Maine Turnpike prior to procurement of the product.

652.03 General:

Placement:

Provide rumble strips where the plans show or as directed by the Resident as follows:

Prior to placing rumble strips, clean the roadway of sand and other materials, that may cause slippage.

Place one end of the rumble strips 6 inches from the roadway centerline. Extend the strips perpendicular to the direction of travel. Ensure strips lay flat on the roadway surface.

Only one series of rumble strips, placed before the first work zone, is required per direction of travel for multiple work zones spaced 1 mile or less apart. Work zones spaced greater than 1 mile apart require a separate series of rumble strips. Each lane shall use one group of temporary rumble strips.

Bracketed "Rumble Strip Ahead" and "Bump" signs shall be utilized and will be paid for under the respective construction sign pay items.

Maintenance:

Maintain rumble strips as follows:

If rumble strips slide, become out of alignment, or are no longer in the wheel path of approaching vehicles during the work period, thoroughly clean both sides of the rumble strips and reset on a clean roadway.

Repair or replace damaged rumble strips immediately.

652.04 Method of Measurement:

The accepted quantity of temporary portable rumble strips shall be measured by the unit complete in place, per lane closure application. A unit shall consist of 1 group of 3 full-lane width of rumble strips. As shown in the plans, a maximum of 3 units may be used at each lane closure. A unit shall be measured for each group of rumble strips, each time they are used for a lane closure.

652.05 Basis of Payment:

The accepted quantity of temporary portable rumble strips will be paid for at the contract unit price per unit which shall include the transport device. Payment is full compensation for providing, relocating, maintaining or replacing, and removing temporary portable rumble strips.

If the pay item is not included in the contract quantities, then the Authority does not anticipate the use of this item on the contract. If contractor wishes to utilize temporary portable rumble strips and the item is not in the contract, then the contractor may propose use of them to the Authority for consideration.

<u>Pay Item</u>	<u>Pay Unit</u>
652.46 Temporary Portable Rumble Strip	Unit

SPECIAL PROVISIONSECTION 652MAINTENANCE OF TRAFFIC(Specific Project Maintenance of Traffic Requirements)

This Specification describes the specific project maintenance of traffic requirements for this Project.

The following minimum traffic requirements shall be maintained. These requirements may be adjusted based on the traffic volume when authorized by the Authority. All road closures will require that portable-changeable message signs are installed each side of the closure and actively announcing the closure dates two weeks prior to closing.

Danville Corner Road Traffic Control Requirements

Danville Corner Road will be closed to through traffic between Washington Street and Old Danville Road. The Contractor shall coordinate directly with the Authority for acceptable road closure dates as outlined in Section 107.4.6. The Contractor shall notify the Resident/Authority two weeks prior to the closure. A temporary detour shall be established and maintained at all times in accordance with the detour plan shown in the Plans. The detour route begins at the Danville Corner Road bridge over the Maine Turnpike, proceeding south to Old Danville Road; following Old Danville Road to Moose Brook Road; following Moose Brook Road to Washington Street (US Rte 202) across the Turnpike back to Danville Corner Road on the west side of the Turnpike. The Resident/Inspector shall notify the City of Auburn prior to closing Danville Corner Road at the Turnpike.

Fisher Farm Road Traffic Control Requirements

Fisher Farm Road will be closed to through traffic between Marsh Road and Furbish Road. The Contractor shall coordinate directly with the Authority for acceptable road closure dates as outlined in Section 107.4.6. The Contractor shall notify the Resident/Authority two weeks prior to the closure. A temporary detour shall be established and maintained at all times in accordance with the detour plan shown in the Plans. The detour route begins at the Fisher Farm Road bridge over the Maine Turnpike, proceeding west to Marsh Road; following Marsh Road to Sabattus Road; following Sabattus Road to Pleasant Hill Road; following Pleasant Hill Road to Furbish road across the Turnpike back to Fisher Farm Road on the east side of the Turnpike. The Resident/Inspector shall notify the Town of Sabattus prior to closing Danville Corner Road at the Turnpike.

Center Road Traffic Control Requirements

Center Road will be closed to through traffic between Richmond Road (Route 197) and Dead River Road. The Contractor shall coordinate directly with the Authority for acceptable road closure dates as outlined in Section 107.4.6. The Contractor shall notify the Resident/Authority two weeks prior to the closure. A temporary detour shall be established and maintained at all times

in accordance with the detour plan shown in the Plans. The detour route begins at the Danville Corner Road bridge over the Maine Turnpike, proceeding north to Richmond Road; following Richmond Road to Hallowell-Litchfield Road (Academy Road); following Academy Road across the Turnpike to Dead River Road, following Dead River Road back to Center Road on the east side of the Turnpike. The Resident/Inspector shall notify the Town of Litchfield prior to closing Center Road at the Turnpike.

Maine Turnpike Traffic Control Requirements

This Section outlines the minimum requirements that shall be maintained for work on, over, or adjacent to the Maine Turnpike roadway. Operations are allowed as outlined below:

Bridge work directly over traffic or within six feet of a travel lane as measured from the painted pavement marking line or traffic control device will require a lane closure. This work includes but is not limited to the following:

1. Installing and removing shielding
2. Superstructure rehabilitation
3. Pier rehabilitation
4. Installing and removing deck and diaphragm forms
5. Erecting or moving sign panels on bridges
6. Bolting structural steel

When approved by the Resident, Items 4 and 6 may be performed over traffic if a temporary floor is provided between the bottom flanges of the beams.

A minimum of one lane shall be open to traffic in each direction at all times. Open lanes during periods of single lane closures shall have a minimum width of 14 feet. Permanent lane closures are not allowed. Lane closures are only allowed when the Contractor is working in the closure.

<u>Temporary Mainline Lane Closures</u>	<u>24 hours per day starting at 7:00 p.m. Sunday thru 6:00 p.m. Friday</u>
<u>Temporary Mainline Shoulder Closures</u>	<u>24 hours per day starting at 7:00 p.m. Sunday thru 6:00 p.m. Friday</u>

Exception: Lane Closures will NOT be allowed Northbound on Fridays from 3 p.m. to 5:30 p.m. from June 29 to August 31, inclusive, for the Danville Corner Road Bridge work.

SPECIAL PROVISIONSECTION 652MAINTENANCE OF TRAFFIC(Automated Speed Limit Sign)652.1 Description

This special provision provides for furnishing, operating, and maintaining an Automated Trailer Mounted Radar Speed Limit Sign for project use. The Contractor shall furnish, operate, and maintain the Automated Trailer Mounted Radar Speed Limit Signs during the project operations.

652.1.1 Instruction and maintenance manuals shall be provided.

652.2 MaterialsAutomated Trailer Mounted Speed Limit Sign

Trailer mounted speed limit signs shall be self-contained units including sign assembly, flashing lights, directional radar to measure speed limits, a regulatory speed limit sign, a construction sign stating “Work Zone Speed Limit When Flashing” and power supply specifically constructed to operate as a trailer-mounted sign. The preferred color of the unit shall be “construction orange”.

Signs

Base material for the regulatory speed limit signs shall be weather proof, rigid substrate specifically manufactured for highway signing and meet the retro-reflective sheeting application requirements of the sheeting manufacturer.

Sign text shall consist of the letters, digits and symbols either applied by stick-on or silk screen, to conform to the dimensions and designs indicated in the Contract, MUTCD and/or FHWA Standard Highway Signs. The materials and methods shall be in accordance with standard commercial processes.

The regulatory sign should have changeable speed limit numbers.

“Work Zone” construction signs shall be mounted on the trailer unit above and below the regulatory speed limit sign. (see Appendix). The “When Flashing” construction sign shall be added to the trailer.

Signs and secondary signs shall follow the MUTCD for minimum mounting heights.

Power supply

The power supply shall be either full battery power with solar panel charging (capable of maintaining a charged battery level) and 135 ampere, 12 volt deep cycle batteries, or diesel powered generator with a fuel capacity sufficient for 10 hours of continuous operation.

Flashing Lights

Each unit shall be equipped with two mono-directional flashing lights, placed in accordance with the MUTCD, with amber lenses and reflectors, which are visible through a range of 120 degrees when viewed facing the sign. The lights, either strobe, halogen, or incandescent lamps, shall be visible for a minimum distance of one mile under daylight conditions and shall have a minimum flash rate of 40 flashes per minute. An “On” indicator light shall be mounted on the back of the signs, which is visible for at least 500 feet to provide confirmation that the flashing lights are operating.

Radar

The directional radar shall monitor approaching traffic only. The radar shall be capable of measuring speeds from 5 to 70 MPH at a distance of up to 1500 feet and shall have a high speed cut off thresh hold.

CONSTRUCTION REQUIREMENTS652.3.2 Responsibility of the Contractor

The Contractor shall furnish the Automated Trailer Mounted Speed Limit Sign as described in this Special Provision for this project.

All existing speed limit signs, which conflict with the construction zone trailer mounted speed limit signs shall be covered completely during the operation of the flashing lights. These signs shall be immediately uncovered when the use of the flashing lights is discontinued.

Automated Trailer Mounted Speed Limit Signs shall be used only during the Contractor’s actual work hours, unless specifically authorized by the Engineer.

The Resident will record the actual time and location for the signs on a daily basis when the Automated Trailer Mounted Speed Limit Signs are in use.

Automated Trailer Mounted Speed Limit Signs shall be located as shown on the plans.

Automated Trailer Mounted Speed Limit Signs shall be delineated with retro-reflective temporary traffic control devices while in use and shall also be delineated by affixing a retro-reflective material directly on the trailer.

Upon delivery of the Automated Trailer Mounted Speed Limit Sign and before acceptance by the Authority, the Contractor shall have a representative of the manufacturer review the condition and notify the Resident in writing, of all deficiencies noted.

The Contractor shall arrange to have all necessary repairs performed at no cost to the Authority.

To avoid impairing driver vision, the Contractor shall dim the lighted speed limit readings by 50 percent during nighttime use, and restore full power lighting during daytime operation.

652.7 Method of Measurement

Automated Trailer Mounted Speed Limit Sign shall be measured for payment by the calendar day for each calendar day that the unit is used on a travel lane or shoulder on the project, as approved by the Resident, and shall include the Trailer, Radar Speed Limit Sign, flashing beacon amber lights, regulatory speed limit sign, “Work Zone Speed Limit When Flashing” construction sign, fuel, necessary maintenance, and all checking of Radar Speed Limit Signs by manufacturer. Also included are all project moves including the transporting and delivery of the unit.

652.8 Basis of Payment


The Automated Trailer Mounted Speed Limit Sign(s) will be paid for at the Contract unit price per calendar day. This price shall include all costs associated with the use of the Automated Trailer Mounted Speed Limit Sign.



Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
652.451 Automated Trailer Mounted Speed Limit Sign	Calendar Day


Appendix B

Automated Trailer Mounted Speed Limit Sign





- #1 - 1.25" BORDER; 0.75" INDENT. BLACK ON ORANGE; BB GRADE PLYWOOD SIGN
- #2 - 1.25" BORDER; 0.75" INDENT. BLACK ON WHITE; BB GRADE PLYWOOD SIGN
- #3 - 1.25" BORDER; 0.75" INDENT. BLACK ON WHITE; BB GRADE PLYWOOD SIGN



DIMENSIONS (inches)/LETTER FONTS

	A	B	C	D	E	F	G	H	I	J	K	L
#1	48	20	5D	18 ¹ / ₈	16 ⁵ / ₈	14 ⁷ / ₈	15 ⁵ / ₈	4	2	N/A	N/A	N/A
#2	48	20	5D	17 ¹ / ₄	31 ³ / ₈	15 ¹ / ₂	8 ¹ / ₄	4	2	N/A	N/A	N/A
#3	48	60	8E	16E	38 ¹ / ₄	29 ¹ / ₄	29 ¹ / ₂	4 ⁷ / ₈	9 ³ / ₈	9 ¹ / ₄	8	6

CONSTRUCTION SIGN/REGULATORY SIGNS

TRAILER MOUNTED CONSTRUCTION ZONE
SPEED LIMIT SIGN