



Maine Turnpike Authority *Schedule of Items*

Emergency Vehicle Ramps - Forest Avenue Overpass MM 50.0

Item No.	Description	Quantity	UOM
201.11	Clearing	0.75	AC
203.2	Common Excavation	2,000.00	CY
203.24	Common Borrow	14,200.00	CY
203.25	Granular Borrow	1,590.00	CY
304.1	Aggregate Subbase Course - Gravel	1,410.00	CY
304.14	Aggregate Base Course - Type A	360.00	CY
403.21	Hot Mix Asphalt - 19.0 MM Nom. Max. Size (Base)	390.00	Ton
403.208	Hot Mix Asphalt - 12.5 MM Nom. Max. Size (Surface)	240.00	Ton
409.15	Bituminous Tack Coat RS-1 or RS-1h - Applied	115.00	Gallo
419.3	Saw Cutting Bituminous Pavement	1,190.00	LF
603.155	12" RCP Class III	40.00	LF
603.159	12" Culvert Pipe Opt III	20.00	LF
603.179	18" Culvert Pipe Opt III	88.00	LF
603.199	24" Culvert Pipe Opt III	168.00	LF
603.28	Concrete Collar	3.00	LF
606.1301	31" W-Beam Guardrail, Mid-Way Splice	1,588.00	LF
606.1304	31" W-Beam Guardrail, Mid-Way Splice - Over 15' Radius	463.00	LF
606.1351	Terminal End - Anchored End	12.00	EA
606.353	Reflectorized Flexible Guardrail Markers	11.00	EA
606.3561	Delineator Post - Remove and Stack	5.00	EA
606.369	Guardrail Remove and Stack	1,025.00	LF
606.611	Remove and Reset Timber Guardrail	80.00	LF
607.17	Chain Link Fence - 6 Ft	160.00	LF
607.2325	Pipe Entry Gate	2.00	EA
607.32	Bracing Assembly Type I - Metal Posts	8.00	EA
607.33	Bracing Assembly Type II - Metal Posts	4.00	EA
610.08	Plain Riprap	177.00	CY
610.18	Stone Ditch Protection	100.00	CY
610.181	Temporary Stone Check Dam	8.00	CY
613.319	Erosion Control Blanket	4,910.00	SY
615.07	Loam	660.00	CY
618.14	Seeding Method Number 2	51.00	Unit
619.1201	Mulch - Plan Quantity	51.00	Unit
620.58	Erosion Control Geotextile	681.00	SY
629.05	Hand Labor Straight Time	30.00	HR
631.12	All Purpose Excavator (including operator)	30.00	HR
631.171	Truck - Small (including operator)	30.00	HR



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
631.32	Culvert Cleaner (Including Operator)	10.00	HR
631.36	Foreman	15.00	HR
645.271	Regulatory, Warning, Confirmation and Route Marker Assembly Sign, Type 1	67.00	SF
652.39	Work Zone Traffic Control	1.00	LUMP
652.45	Truck Mounted Attenuator	10.00	CD
656.5	Baled Hay, in Place	35.00	EA
656.632	30" Temporary Silt Fence	2,170.00	LF
659.1	Mobilization	1.00	LS