



# Maine Turnpike Authority *Schedule of Items*

## Bridge Repairs - Eagles Nest Road Southbound Overpass Mile 60.81 & Superstructure Replacement Route 122 Underpass Mile 74.00

Item No.	Description	Quantity	UOM
202.1	Removing Existing Superstructure Property of Contractor (362 CY)	1.00	LS
202.17	Removing Existing Structural Concrete	95.00	CY
202.191	Removing Existing Drain Troughs	1.00	LS
202.202	Removing Pavement Surface	680.00	SY
203.2	Common Excavation	345.00	CY
203.25	Granular Borrow	160.00	CY
206.082	Structural Earth Excavation - Major Structures, Plan Quantity	160.00	CY
304.14	Aggregate Base Course - Type A	150.00	CY
403.207	Hot Mix Asphalt - 19 mm	107.00	TON
403.208	Hot Mix Asphalt - 12.5 mm	200.00	TON
403.213	Hot Mix Asphalt - 12.5 mm (base and intermediate course)	140.00	TON
409.15	Bituminous Tack Coat RS-1 or RS1h- Applied	120.00	GAL
411.1	Untreated Aggregate Surface Course, Truck Measure	2.00	CY
419.3	Sawing Bituminous Pavement	250.00	LF
502.21	Structural Concrete, Abutments and Retaining Walls	83.00	CY
502.23	Structural Concrete Piers	15.00	CY
502.26	Structural Concrete Roadway and Sidewalk Slab on Steel Bridges (290 CY)	1.00	LS
502.49	Structural Concrete Curbs and Sidewalks (54 CY)	1.00	LS
502.602	Pier Pedestal Concrete	16.00	CF
503.12	Reinforcing Steel, Fabricated and Delivered	2,150.00	LB
503.13	Reinforcing Steel, Placing	2,150.00	LB
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	128,250.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	128,250.00	LB
504.7	Structural Steel Fabricated and Delivered (217,600 LB)	1.00	LS
504.71	Structural Steel Erection (217,600 LB)	1.00	LS
504.8	Eagles Nest Road Southbound Overpass Steel Repair	1.00	LS
505.08	Shear Connectors (4,730 EA)	1.00	LS
506.9104	Thermal Spray Coating (Shop Applied)	1.00	LS
507.0821	Steel Bridge Railing, 3 Bar (720 LF)	1.00	LS
508.14	High Performance Waterproofing Membrane (1,050 SY)	1.00	LS
508.15	Membrane Waterproofing (170 SY)	1.00	LS
514.06	Curing Box for Concrete Cylinders	1.00	EA
515.201	Pigmented Protective Coating for Concrete Surfaces	790.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	510.00	SY
518.2	Pier Repairs	185.00	SF
520.21	Expansion Device - Gland Seal (68 LF)	2.00	EA
523.52	Bearing Installation	35.00	EA



# Maine Turnpike Authority

## *Schedule of Items*

Item No.	Description	Quantity	UOM
523.5401	Laminated Elastomeric Bearings, Fixed	5.00	EA
523.54021	PTFE Elastomeric Bearings, Expansion	30.00	EA
524.4	Protective Shielding - Steel Girders	1,470.00	SY
526.306	Temporary Concrete Barrier, Type 1 - Supplied by the Authority (600 LF)	1.00	LS
527.341	Work Zone Crash Cushions - TL-3	2.00	UNIT
606.1301	31" W-Beam Guardrail – Mid-way Splice	125.00	LF
606.1305	31" W-Beam Guardrail – Mid-way Splice Flared Terminal	2.00	EA
606.1721	Bridge Transition - Type 1	4.00	EA
606.178	Guardrail Beam	25.00	LF
606.23	Guardrail Type 3c - Single Rail	25.00	LF
606.352	Reflectorized Beam Guardrail Delineator	10.00	EA
606.353	Reflectorized Flexible Guardrail Marker	4.00	EA
607.17	Chain Link Fence - 6 Foot	180.00	LF
607.23	Chain Link Fence Gate	2.00	EA
607.32	Bracing Assembly Type I - Metal Posts	16.00	EA
607.33	Bracing Assembly Type II - Metal Posts	2.00	EA
607.431	Snow Fence	221.00	LF
609.11	Vertical Curb Type 1	36.00	LF
609.23	Terminal Curb Type 1	32.00	LF
610.08	Plain Riprap	440.00	CY
610.18	Stone Ditch Protection	75.00	CY
610.181	Temporary Stone Check Dam	10.00	CY
613.319	Erosion Control Blanket	39.00	SY
615.07	Loam	111.00	CY
618.14	Seeding Method Number 2	9.00	UN
619.1201	Mulch - Plan Quantity	9.00	UN
619.1202	Temporary Mulch	1.00	LS
619.1401	Erosion Control Mix	35.00	CY
620.58	Erosion Control Geotextile	695.00	SY
627.712	White or Yellow Pavement Marking Line	2,100.00	LF
629.05	Hand Labor, Straight Time	20.00	HR
631.1	Air Compressor (Including Operator)	20.00	HR
631.11	Air Tool (Including Operator)	20.00	HR
631.12	All Purpose Excavator (Including Operator)	20.00	HR
631.172	Truck - Large (Including Operator)	40.00	HR
631.36	Foreperson	20.00	HR
639.18	Field Office, Type A	1.00	EA



## Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
652.3	Flashing Arrow	2.00	EA
652.312	Type III Barricades	11.00	EA
652.33	Drum	115.00	EA
652.34	Cone	50.00	EA
652.35	Construction Signs	1,277.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	110.00	HR
652.41	Portable-Changeable Message Sign	3.00	EA
652.45	Truck Mounted Attenuator	160.00	CD
652.452	Automated Trailer Mounted Speed Limit Sign	2.00	EA
656.5	Baled Hay, in place	10.00	EA
656.632	30 inch Temporary Silt Fence	1,060.00	LF
659.1	Mobilization	1.00	LS