



Maine Turnpike Authority

Schedule of Items

Pavement Rehabilitation MM 42.0 to MM 44.3

Item No.	Description	Quantity	UOM
202.202	Removing Pavement Surface - Mainline	37,600.00	SY
202.2026	Removing Pavement Surface – Drainage Paths	780.00	SF
202.206	Fill Existing Rumble Strips	4,800.00	LF
403.21	Hot Mix Asphalt, 9.5mm, 20% RAP Max.	4,600.00	Ton
409.152	Bituminous Tack Coat Trackless - Applied	5,800.00	GAL
470.08	Berm Dropoff Correction – Grindings	100.00	Ton
470.081	Berm Correction	1,000.00	LF
615.07	Loam	10.00	CY
618.14	Seeding Method 2	2.00	Un
619.12	Mulch	2.00	Un
627.681	Temporary Pavement Marking Line, White or Yellow	51,200.00	LF
627.73	Temporary 6" Pavement Marking Tape	3,300.00	LF
627.75	White or Yellow Pavement and Curb Markings	120.00	SF
627.772	Removing Existing Pavement Markings - Tape	120.00	SF
627.812	Temporary Raised Pavement Markers	5,120.00	EA
629.05	Hand Labor, Straight Time	10.00	HR
631.12	All Purpose Excavator (including Operator)	10.00	HR
631.172	Truck - Large (including Operator)	10.00	HR
652.361	Maintenance of Traffic Control Devices	1.00	LS
659.1	Mobilization	1.00	LS