

MAINE TURNPIKE AUTHORITY

ADDENDUM NO. 3

CONTRACT 2019.04

INTERCHANGE 103 BARRIER TOLL PLAZA
OPEN ROAD TOLLING CONVERSION
MILE 103

The bid opening date is Thursday, 4/18/2019 at 11 am.

The following changes are made to the Proposal, Specification's, and Plans.

SPECIAL PROVISIONS

Page SP-226 Section 652.1 Description shall be replaced with the following:

652.1 Description

The following paragraph is added:

When a pay item for a Truck Mounted Attenuator (TMA) is included in the contract TMA(s) will be required on the project and its use will be required. Truck Mounted Attenuator(s) should be utilized in lane closures and other construction operations where workers are exposed to traffic and not protected by other positive means. The Contractor shall manage the utilization and operation of the TMA(s) and if not used as described above then it will be considered a Traffic Control Plan violation and result in a reduction of payment as outlined in Section 652.

Page SP-227 Section 652.7 Method of Measurement shall be replaced with the following:

652.7 Method of Measurement

The last Paragraph is deleted and replaced with:

Truck Mounted Attenuator(s) will be paid for at the contract unit price per each for the continued use for the duration of the project.