



# Maine Turnpike Authority *Schedule of Items*

## Emergency Vehicle Ramps - Various Locations MM 6.2, 10.6 & 19.9

| Item No. | Description  | Quantity | UOM  |
|----------|--|----------|------|
| 201.11   | Clearing   | 1.70     | AC   |
| 201.23   | Remove Single Tree Top Only                        | 1.00     | EA   |
| 201.24   | Remove Stump                                       | 1.00     | EA   |
| 203.2    | Common Excavation                                  | 2,350.00 | CY   |
| 203.24   | Common Borrow                                      | 5,710.00 | CY   |
| 203.25   | Granular Borrow                                    | 110.00   | CY   |
| 304.1    | Aggregate Subbase Course - Gravel                  | 2,165.00 | CY   |
| 304.14   | Aggregate Base Course - Type A                     | 560.00   | CY   |
| 403.21   | Hot Mix Asphalt - 19.0 MM Nom. Max. Size (Base)    | 500.00   | Ton  |
| 403.208  | Hot Mix Asphalt - 12.5 MM Nom. Max. Size (Surface) | 310.00   | Ton  |
| 409.15   | Bituminous Tack Coat RS-1 or RS-1h - Applied       | 150.00   | GA   |
| 419.3    | Saw Cutting Bituminous Pavement                    | 1,080.00 | LF   |
| 603.155  | 12" RCP Class III                                  | 48.00    | LF   |
| 603.175  | 18" RCP Class III                                  | 68.00    | LF   |
| 603.179  | 18" Culvert Pipe Opt III                           | 260.00   | LF   |
| 603.209  | 30" Culvert Pipe Opt III                           | 44.00    | LF   |
| 604.09   | Catch Basin Type B1                                | 1.50     | EA   |
| 606.242  | Guardrail Type 3D - Over 15 ft Radius              | 150.00   | LF   |
| 606.265  | Terminal End - Single Rail - Galvanized Steel      | 5.00     | EA   |
| 606.278  | Terminal End - Anchored End                        | 5.00     | EA   |
| 606.353  | Reflectorized Flexible Guardrail Markers           | 10.00    | EA   |
| 606.3561 | Delineator Post - Remove and Stack                 | 12.00    | EA   |
| 606.369  | Guardrail Remove and Stack                         | 212.50   | LF   |
| 607.17   | Chain Link Fence - 6 Ft                            | 443.00   | LF   |
| 607.2325 | Pipe Entry Gate                                    | 6.00     | EA   |
| 607.32   | Bracing Assembly Type I - Metal Posts              | 21.00    | EA   |
| 607.33   | Bracing Assembly Type II - Metal Posts             | 10.00    | EA   |
| 610.08   | Plain Riprap                                       | 29.00    | CY   |
| 610.18   | Stone Ditch Protection                             | 14.00    | CY   |
| 610.181  | Temporary Stone Check Dam                          | 4.00     | CY   |
| 613.319  | Erosion Control Blanket                            | 230.00   | SY   |
| 615.07   | Loam   | 530.00   | CY   |
| 618.14   | Seeding Method Number 2                            | 44.00    | Unit |
| 619.1201 | Mulch - Plan Quantity                              | 44.00    | Unit |
| 620.58   | Erosion Control Geotextile                         | 176.00   | SY   |
| 621.045  | Evergreen Trees 6' - 8' Gr. C                      | 5.00     | EA   |
| 626.33   | 30 Inch Foundation, 8-Foot or less Foundation      | 2.00     | EA   |



## Maine Turnpike Authority *Schedule of Items*

| Item No. | Description  | Quantity | UOM |
|----------|--|----------|-----|
| 629.05   | Hand Labor, Straight Time  | 30.00    | HR  |
| 631.12   | All Purpose Excavator (including operator)                               | 30.00    | HR  |
| 631.171  | Truck - Small (including operator)                                       | 30.00    | HR  |
| 631.36   | Foreman  | 30.00    | HR  |
| 645.109  | Remove and Reset Sign  | 2.00     | EA  |
| 645.162  | Breakaway Device Multi Pole  | 2.00     | EA  |
| 645.271  | Regulatory, Warning, Confirmation and Route Marker Assembly Sign, Type 1 | 216.00   | SF  |
| 645.289  | Steel H-Beam Poles   | 365.00   | LBS |
| 652.39   | Work Zone Traffic Control  | 1.00     | LS  |
| 652.45   | Truck Mounted Attenuator   | 25.00    | CD  |
| 656.5    | Baled Hay, in Place  | 90.00    | EA  |
| 656.632  | 30" Temporary Silt Fence   | 2,700.00 | LF  |
| 659.1    | Mobilization (10% of above items)  | 1.00     | LS  |