



Maine Turnpike Authority *Schedule of Items*

Pavement Rehabilitation and Drainage Improvements MM 102.6 TO MM 109.1

Item No.	Description	Quantity	UOM
202.202	Removing Pavement Surface - Mainline	280,700.00	SY
202.2026	Remove Pavement Surface - Drainage Paths	385.00	SF
202.205	Rumble Strips	122,400.00	EA
403.2081	Hot Mix Asphalt, 12.5mm (Polymer Modified)- RAP	24,500.00	Ton
403.2084	Hot Mix Asphalt, 12.5mm Nominal Maximum Size (sidewalks, drives, islands & incidentals)	180.00	Ton
403.211	Hot Mix Asphalt (shimming)	150.00	Ton
409.15	Bituminous Tack Coat - Applied	17,590.00	GAL
419.3	Full Depth Bituminous Sawcut	900.00	LF
419.301	Saw Cutting and Sealing Bituminous Pavement	156.00	LF
424.323	Asphalt Rubber Mastic Crack Sealant	39,700.00	LB
459.06	Bituminous Concrete Waterway - Type I	12.00	EA
470.08	Berm Dropoff Correction - Grindings	1,200.00	Ton
470.081	Berm Correction	21,000.00	LF
520.23	Asphaltic Plug Joint	136.00	LF
603.199	24 inch Culvert Pipe - Option III	58.00	LF
603.28	Concrete Collar	3.00	EA
604.182	Clean Existing Catch Basin And Manhole	60.00	EA
604.186	Rebuild Catch Basin to Grade - Type IV	10.00	EA
610.08	Plain Rip Rap	15.00	CY
613.319	Erosion Control Blanket	1,150.00	SY
615.07	Loam	90.00	CY
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	75.00	SY
627.73	Temporary Pavement Marking Line Tape	5,200.00	LF
627.78	Temporary Pavement Marking Line	203,400.00	LF
627.812	Temporary Raised Pavement Markers	13,500.00	EA
627.94	Pavement Marking Tape	2,650.00	LF
627.941	Pavement Marking Tape - Dotted White Lane Line, 6-inch width	300.00	LF
627.942	Pavement Marking Tape - Dotted White Lane Line, 12-inch width	160.00	LF
629.05	Hand Labor, Straight Time	20.00	HR
631.1	Air Compressor (including operator)	20.00	HR
631.11	Air Tool (including operator)	20.00	HR
631.12	All Purpose Excavator (including operator)	30.00	HR
631.172	Truck - Large (including operator)	30.00	HR
631.36	Foreman	20.00	HR
652.3	Flashing Arrow	4.00	EA



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
652.35	Construction Signs	4,550.00	SF
652.3611	Maintenance of Traffic Control Devices	1.00	LS
652.411	Portable - Changeable Message Sign	4.00	EA
652.45	Truck Mounted Attenuator	75.00	CD
652.452	Automated Trailer Mounted Speed Limit Sign	2.00	EA
656.5	Baled Hay, in place	70.00	EA
656.632	30 inch Temporary Silt Fence	400.00	LF
659.1	Mobilization	1.00	LS