



# Maine Turnpike Authority *Schedule of Items*

## York Toll Plaza Demolition and Mainline Reconstruction, Mile 7.3

Item No.	Description	Quantity	UOM
201.11	Clearing	1.00	AC
202.071	Removing Asbestos Containing Materials	1.00	LS
202.15	Removing Manhole or Catch Basin	11.00	EA
202.151	Abandoning Existing Manhole or Catch Basin	7.00	EA
202.16	Removing Existing Pipe	310.00	LF
202.161	Abandoning Existing Pipe	650.00	LF
202.202	Removing Pavement Surface	52,000.00	SY
202.205	Rumble Strips - Shoulder	53,000.00	LF
202.206	Remove Rumble Strips	1,330.00	LF
203.2	Common Excavation	44,000.00	CY
203.21	Rock Excavation	400.00	CY
203.24	Common Borrow	5,997.00	CY
203.245	Clay Borrow	45.00	CY
203.25	Granular Borrow	409.00	CY
203.35	Crushed Stone Fill 3/4-Inch	550.00	CY
206.071	Structural Rock Excavation - Pavement	800.00	CY
304.1	Aggregate Subbase Course – Gravel	18,750.00	CY
304.14	Aggregate Base Course - Type A	5,950.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	13,500.00	T
403.2081	Hot Mix Asphalt - 12.5 mm Nominal Maximum Size (Polymer Modified)	6,100.00	T
403.211	Hot Mix Asphalt (Shim)	4,500.00	T
403.213	Hot Mix Asphalt 12.5 mm Nominal Maximum Size (Binder)	4,500.00	T
409.15	Bituminous Tack Coat - Applied	4,350.00	G
409.152	Bituminous Tack Coat NTSS-1HM Trackless - Applied	4,200.00	G
419.3	Saw Cutting Bituminous Pavement	17,700.00	LF
502.234	Structural Concrete. Basement Closure Wall	2.00	CY
503.12	Reinforcing Steel, Fabricated and Delivered	400.00	LB
503.121	Reinforcing Steel, Placing	400.00	LB
508.14	High Performance Membrane Waterproofing	10.00	SY
511.091	Temporary Earth Support Systems	1.00	LS
526.306	Temporary Concrete Barrier Type I - Supplied by the Authority	1.00	LS
526.351	Median Barrier Type I -Precast	2,700.00	LF
526.352	Median Barrier Type I - Supplied By MTA	240.00	LF
526.361	Median Barrier Transition Type I - Precast	2.00	EA
526.362	Median Barrier Transition Type I - Supplied By MTA	1.00	EA
527.307	Center Barrier Crash Attenuator (Smart Cushion)	3.00	EA
527.34	Work Zone Crash Cushions	1.00	UNIT



## Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
527.341	Work Zone Crash Cushions - TL-3	4.00	UNIT
602.4	Pumped Grout Fill	30.00	CY
603.159	12 Inch Culvert Pipe Option III	150.00	LF
603.165	15 Inch Reinforced Concrete Pipe Class III	680.00	LF
603.169	15 Inch Culvert Pipe Option III	340.00	LF
603.175	18 Inch Reinforced Concrete Pipe Class III	100.00	LF
604.09	Catch Basin Type B1	9.00	EA
604.0901	Catch Basin Type B1 with Flat Top	12.00	EA
604.1521	48 Inch Manhole Type 6 with Flat Top	2.00	EA
604.1542	72 Inch Outlet Control Structure	4.00	EA
604.1561	96 Inch Doghouse Manhole	1.00	EA
604.161	Altering Catch Basin	1.00	EA
604.182	Cleaning Existing Catch Basin and Manhole	3.00	EA
605.09	6 Inch Underdrain Type B	720.00	LF
605.105	8 Inch Underdrain Outlet	800.00	LF
606.1301	31" W-Bm Gr, Mid-Way Splice-Sgl Faced	1,450.00	LF
606.1305	31" W-Bm Gr, Md-Wy Splic Flared Term	1.00	EA
606.1351	31" W-Bm Gr, Mid-Way Splice Terminal End-Anchored End	1.00	EA
606.1724	Bridge Transition - Type III Modified	2.00	EA
606.352	Reflectorized Beam Guardrail Delineator	2.00	EA
606.353	Reflectorized Flexible Guardrail Marker	3.00	EA
606.356	Underdrain Delineator Post	43.00	EA
606.3561	Delineator Post - Remove and Reset	50.00	EA
606.3562	Delineator Post - Remove and Stack	31.00	EA
606.3611	Guardrail - Remove, Modify, and Reset Thrie Beam, Double Rail	25.00	LF
606.3631	Guardrail - Remove and Stack or Dispose	4,810.00	LF
606.48	Single Galvanized Steel Post	2.00	EA
606.64	Gr - Thrie Beam - Dbl Rail	638.00	LF
606.65	Gr - Thrie Beam - Sgl Rail	525.00	LF
606.754	Widen Shoulder for Energy Absorbing End Terminal	1.00	EA
610.08	Plain Riprap	200.00	CY
610.181	Temporary Stone Check Dam	150.00	CY
610.182	Permanent Stone Check Dam	8.00	CY
615.07	Loam	7,700.00	CY
618.14	Seeding Method Number 2	420.00	UN
619.1201	Mulch	420.00	UN
619.1202	Temporary Mulch	1.00	LS



## Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
620.56	Drainage Geotextile	300.00	SY
620.58	Erosion Control Geotextile	10,500.00	SY
626.122	Quazite Junction Box (18"x11")	14.00	EA
626.22	Non-Metallic Conduit	3,100.00	LF
626.341	Light Standard Foundation	11.00	EA
627.18	12" Solid White Pavement Marking	1,200.00	LF
627.4072	Pref Pave Mark Tape Line, Groove Install	725.00	SF
627.681	Temporary 6 Inch Painted Pavement Marking Line -Yellow or White	145,000.00	LF
627.73	Temporary 6 Inch Pavement Marking Tape	1,800.00	LF
627.731	Temporary 6 Inch Black Pavement Marking Tape	2,000.00	LF
627.744	6" White or Yellow Painted Pavement Marking Line	26,600.00	LF
627.745	6" White Or Yellow Polyurea Pavement Mrl Line	5,000.00	LF
627.77	Remove Existing Pavement Marking	3,400.00	SF
627.812	Temporary Raised Pavement Markers	300.00	EA
627.94	Pavement Marking Tape	1,250.00	LF
627.941	Pavement Marking Tape - Dotted White Lane Line, 6-Inch Width	110.00	LF
629.05	Hand Labor, Straight Time	40.00	HR
631.1	Air Compressor (Inc Operator)	20.00	HR
631.11	Air Tool (Inc Operator)	20.00	HR
631.115	Jackhammer (Inc Operator)	20.00	HR
631.12	All Purpose Excavator (Inc Operator)	40.00	HR
631.171	Truck - Small (Including Operator)	20.00	HR
631.18	Chain Saw Rental (Inc Operator)	20.00	HR
631.32	Culvert Cleaner (Inc Operator)	20.00	HR
631.36	Foreperson	40.00	HR
631.51	Bucket Truck	20.00	HR
631.52	Scissor Lift	20.00	HR
631.53	Electrician	20.00	HR
631.54	Electrician's Apprentice	20.00	HR
634.16	Highway Lighting	1.00	LS
634.2042	LED Luminaries	2.00	EA
634.2082	Remove Existing Light Standard	31.00	EA
634.21	Conventional Light Standard	2.00	EA
643.63	Flashing Beacon - Solar Powered	5.00	EA
645.1051	Remove and Stack Ground Mount Guide Sign and Structure	18.00	EA
645.1052	Remove and Stack Overhead or Cantilever Guide Sign and Structure	2.00	EA
645.107	Remove and Discard Canopy Mounted Sign	12.00	EA



## Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
645.1071	Remove and Discard Canopy Mounted Dynamic Message Sign	1.00	EA
645.109	Remove and Reset Highway Signs	5.00	EA
645.1099	Remove and Dispose Sign	70.00	EA
645.251	Roadside Guide Signs, Type I	650.00	SF
645.271	Regulatory, Warning, Confirmation and Route Assembly Sign, Type I	102.00	SF
645.28	Wood Post	5.00	EA
645.289	Steel H-Beam Poles	6,150.00	LB
652.3	Flashing Arrow Board	6.00	EA
652.312	Type III Barricade	10.00	EA
652.33	Drum	400.00	EA
652.34	Cone	200.00	EA
652.35	Construction Signs	1,700.00	SF
652.351	Construction Signs - Supplied By Authority	1.00	LS
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.39	Portable Light Tower	2.00	EA
652.41	Portable-Changeable Message Sign	3.00	EA
652.45	Truck Mounted Attenuator	200.00	CD
652.451	Automated Trailer Mounted Speed Limit Sign	2.00	EA
652.47	Sequential Flashing Warning Light	30.00	EA
656.5	Baled Hay, In Place	50.00	EA
656.632	30" Temporary Silt Fence	12,000.00	LF
659.1	Mobilization	1.00	LS
800.311	Toll Plaza and Tunnel Demolition	1.00	LS
801.03	Test Pits	8.00	EA
802.02	Construct Underdrained Soil Filters	1.00	LS