



# Maine Turnpike Authority *Schedule of Items*

## Pavement Rehabilitation, Guardrail, Drainage, & Clear Zone Improvements

MM 71.9 TO MM 80.7

Item No.	Description	Quantity	UOM
202.202	REMOVING PAVEMENT SURFACE - MAINLINE	153,000.00	SY
202.2026	REMOVING PAVEMENT SURFACE - DRAINAGE PATHS	6,350.00	SF
202.205	RUMBLE STRIPS	59,000.00	EA
203.24	COMMON BORROW	170.00	CY
205.511	WIDENING OF EXISTING SHOULDER	75.00	LF
211.3	DITCH EXCAVATION	3,050.00	LF
403.208	HOT MIX ASPHALT, 12.5 mm NOMINAL MAXIMUM SIZE	860.00	T
403.2081	HOT MIX ASPHALT, 12.5 mm NOMINAL MAXIMUM SIZE (POLYMER MODIFIED)	12,400.00	T
403.211	HOT MIX ASPHALT, 9.5 mm NOMINAL MAXIMUM SIZE (SHIMMING)	4,100.00	T
409.15	BITUMINOUS TACK COAT, APPLIED	12,500.00	G
424.323	ASPHALT RUBBER MASTIC CRACK SEALER - APPLIED	20,000.00	LB
427.09	PAVEMENT CRACK REPAIR	7,150.00	LF
429.341	GRID/PAVING FABRIC COMPOSITE INTERLAYER	33,600.00	SF
470.08	BERM DROP OFF CORRECTION - GRINDINGS	2,000.00	T
527.304	ENERGY ABSORBING SYSTEM (C-A-T) - REMOVE & STACK	4.00	EA
603.155	12" RCP CLASS III	32.00	LF
603.159	12" CULVERT PIPE OPTION III	91.00	LF
603.179	18" CULVERT PIPE OPTION III	40.00	LF
603.199	24" CULVERT PIPE OPTION III	32.00	LF
603.209	30" CULVERT PIPE OPTION III	16.00	LF
603.28	CONCRETE COLLAR	11.00	EA
604.184	REBUILD CATCH BASIN TO GRADE - TYPE II	1.00	EA
606.178	GUARDRAIL BEAM	1,500.00	LF
606.24	GUARDRAIL TYPE 3D - SINGLE RAIL	75.00	LF
606.2401	GUARDRAIL TYPE 3D - DOUBLE RAIL	300.00	LF
606.2652	TERMINAL END - REMOVE AND STACK	19.00	EA
606.278	TERMINAL END - ANCHORED END	19.00	EA
606.356	UNDERDRAIN DELINEATOR POST	35.00	EA
606.3562	UNDERDRAIN DELINEATOR POST - REMOVE AND STACK	28.00	EA
606.3606	GUARDRAIL - REMOVE, MODIFY, AND RESET DOUBLE RAIL	890.00	LF
606.3621	GUARDRAIL ADJUST, SINGLE RAIL	20,900.00	LF
606.3622	GUARDRAIL ADJUST, DOUBLE RAIL	22,100.00	LF
606.471	SINGLE OFFSET BLOCK - W-BEAM	20.00	EA
606.48	SINGLE GALVANIZED STEEL POST	30.00	EA
606.754	WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	4.00	EA
606.755	MODIFY WIDENED SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	19.00	EA
606.79	GUARDRAIL 350 FLARED TERMINAL	5.00	EA



## Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
610.08	PLAIN RIPRAP	57.00	CY
613.319	EROSION CONTROL BLANKET	2,400.00	SY
615.07	LOAM	290.00	CY
618.14	SEEDING METHOD #2	24.00	UNIT
619.1201	MULCH - PLAN QUANTITY	24.00	UNIT
619.1202	TEMPORARY MULCH	1.00	LS
620.58	EROSION CONTROL GEOTEXTILE	150.00	SY
627.18	12" SOLID WHITE PAVEMENT MARKING LINE	2,550.00	LF
627.712	WHITE OR YELLOW PAVEMENT MARKING LINE	103,000.00	LF
627.78	TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	142,000.00	LF
627.812	TEMPORARY RAISED PAVEMENT MARKERS	26,000.00	EA
627.94	PAVEMENT MARKING TAPE	1,800.00	LF
627.941	PAVEMENT MARKING TAPE - DOTTED WHITE LANE LINE, 6-INCH WIDTH	550.00	LF
629.05	HAND LABOR, STRAIGHT TIME	40.00	HR
631.1	AIR COMPRESSOR (INCLUDING OPERATOR)	10.00	HR
631.11	AIR TOOL (INCLUDING OPERATOR)	10.00	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.00	HR
631.172	TRUCK - LARGE (INCLUDING OPERATOR)	40.00	HR
631.32	CULVERT CLEANER (INCLUDING OPERATOR)	10.00	HR
631.36	FOREMAN	40.00	HR
652.3	FLASHING ARROW BOARD	2.00	EA
652.331	DRUM	1.00	LS
652.34	CONE	10.00	EA
652.35	CONSTRUCTION SIGNS	3,400.00	SF
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS
652.41	PORTABLE - CHANGEABLE MESSAGE SIGN	3.00	EA
652.45	TRUCK MOUNTED ATTENUATOR	100.00	CD
652.452	AUTOMATED TRAILER MOUNTED SPEED LIMIT SIGN	2.00	EA
652.46	TEMPORARY PORTABLE RUMBLE STRIP	300.00	UNIT
656.632	30 INCH TEMPORARY SILT FENCE	830.00	LF
659.1	MOBILIZATION	1.00	LS