



Maine Turnpike Authority

Schedule of Items

Litchfield 8-Bay Garage Replacement Mile 92.7

Item No.	Description	Quantity	UOM
202.081	Removing Buildings	1.00	LS
202.202	Removing Pavement Surface	55.00	SY
203.2	Common Excavation	2,500.00	CY
203.2312	Health and Safety Plan	1.00	LS
203.2333	Disposal/Treatment of Special Excavation	50.00	TON
203.2334	Disposal/Treatment of Groundwater	500.00	GAL
203.25	Granular Borrow	765.00	CY
203.35	Crushed Stone 3/4-Inch	60.00	CY
304.1	Aggregate Subbase Course - Gravel	750.00	CY
304.105	Structural Fill	325.00	CY
304.14	Aggregate Base Course - Type A	350.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	550.00	TON
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size	340.00	TON
409.15	Bituminous Tack Coat RS-1 or RS1h - Applied	130.00	GAL
419.3	Sawing Bituminous Pavement	1,250.00	LF
502.205	Replacement of Oil/Water Separator Tank Slab	1.00	LS
502.701	Concrete Generator Pad	1.00	EA
502.702	Concrete Propane Tank Pad	3.00	EA
602.4	Filling of Abandoned Tanks	30.00	CY
603.04	4 Inch PVC Pipe	460.00	LF
603.05	6 inch PVC Pipe	10.00	LF
604.158	6000 Gallon Holding Tank	1.00	EA
604.4	Oil / Water Separator	1.00	EA
605.072	4 Inch Perforated SDR-35 Underdrain	450.00	LF
606.356	Underdrain Delineator Post	1.00	EA
610.18	Stone Ditch Protection	1.00	CY
615.07	Loam	250.00	CY
618.14	Seeding Method Number 2	21.00	UNIT
620.58	Erosion Control Geotextile	170.00	SY
626.112	Heavy Duty Precast Concrete Junction Box	4.00	EA
629.05	Hand Labor, Straight Time	40.00	HR
631.12	All Purpose Excavator (including operator)	40.00	HR
631.172	Truck-large (including operator)	40.00	HR
631.221	Small Front End Loader (including operator)	20.00	HR
631.36	Foreman	20.00	HR
633.031	Propane Service	1.00	LS
639.19	Field Office, Type B	1.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
655.097	#4/0 AWG Wire	350.00	LF
655.099	#2 AWG Wire	1,950.00	LF
655.1	#4 AWG Wire	120.00	LF
655.106	#6 AWG Wire	1,200.00	LF
655.108	#8 AWG Wire	650.00	LF
655.11	#10 AWG Wire	530.00	LF
655.125	350 KCMIL Wire	2,250.00	LF
655.2002	1" Schedule 80 PVC Conduit	1,400.00	LF
655.2003	1.5" Schedule 80 PVC Conduit	720.00	LF
655.2031	2" Schedule 80 PVC Conduit	800.00	LF
655.204	3" Schedule 80 PVC Conduit	750.00	LF
656.632	30 Inch Temporary Silt Fence	850.00	LF
659.1	Mobilization	1.00	LS
800.01	Litchfield Vehicle Storage Garage	1.00	LS
825.4231	2.5 inch HDPE Plastic Service	500.00	LF
825.4311	1.5 inch HDPE Plastic Service	650.00	LF
832.41	Type A Steel Site Bollard	23.00	EA