



Maine Turnpike Authority

Schedule of Items

Pavement Rehabilitation and Safety Improvements MM 68.5 to MM 74.9 Bridge Repairs Royal - River (MM 71.1) Washington St/MCRR (MM 75.6) Lisbon St/Rt (MM 81.4)

Item No.	Description	Quantity	UOM
202.202	REMOVING PAVEMENT SURFACE	270,000.00	SY
202.205	RUMBLE STRIPS	112,600.00	EA
211.5	MEDIAN RESTORATION	29,900.00	LF
401.03	BALANCED MIX DESIGN DATA COLLECTION	1.00	LS
403.2081	HOT MIX ASPHALT - 12.5 MM (POLYMER MODIFIED)	26,100.00	T
403.2084	HOT MIX ASPHALT - 12.5 MM NOMINAL MAXIMUM SIZE (SIDEWALKS, DRIVES, ISLANDS & INCIDENTALS)	100.00	T
403.211	HOT MIX ASPHALT (SHIMMING)	100.00	T
409.152	BITUMINOUS TACK COAT TRACKLESS, APPLIED	16,300.00	G
419.3	SAW CUTTING BITUMINOUS PAVEMENT	1,000.00	LF
424.3231	ASPHALT RUBBER MASTIC CRACK SEALER	20,800.00	LB
424.324	ASPHALT RUBBER MASTIC CRACK SEALER WITH AGGREGATE	5,200.00	LB
427.09	CRACK REPAIR	27,400.00	LF
459.06	BITUMINOUS CONCRETE WATERWAY, TYPE I	5.00	EA
459.061	BITUMINOUS CONCRETE WATERWAY, TYPE II	5.00	EA
470.08	BERM DROP OFF CORRECTION - GRINDINGS	30,700.00	LF
470.081	BERM CORRECTION	22,000.00	LF
515.202	CLEAR PROTECTIVE COATING FOR CONCRETE SURFACE	915.00	SY
518.865	ELASTOMERIC CONCRETE	50.00	CF
520.231	EXPANSION DEVICE - ASPHALTIC PLUG JOINT FOR CRACK CONTROL	76.00	LF
520.234	EXPANSION DEVICE - SILICONE COATED AND PRE-COMPRESSED SEAL	76.00	LF
603.199	24 IN CULVERT PIPE OPTION III	16.00	LF
603.209	30 IN CULVERT PIPE OPTION III	8.00	LF
603.28	CONCRETE COLLAR	3.00	EA
604.182	CLEAN EXISTING CATCH BASIN AND MANHOLE	42.00	EA
604.184	REBUILD CATCH BASIN TO GRADE - TYPE II	24.00	EA
604.185	REBUILD CATCH BASIN TO GRADE - TYPE IV	10.00	EA
606.1307	31" W-BEAM GUARDRAIL - MID-WAY SPLICE FLARED TERMINAL	1.00	EA
606.178	GUARDRAIL BEAM	630.00	LF
606.352	REFLECTORIZED BEAM GUARDRAIL DELINEATORS	850.00	EA
606.3621	GUARDRAIL ADJUST, SINGLE RAIL	3,200.00	LF
606.3622	GUARDRAIL ADJUST, DOUBLE RAIL	4,900.00	LF
606.47	SINGLE WOOD POST	5.00	EA
606.471	SINGLE OFFSET BLOCK - W-BEAM	30.00	EA
606.48	SINGLE GALVANIZED STEEL POST	30.00	EA
606.755	PAVING OF EXISTING GUARDRAIL WIDENINGS	34.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
610.08	PLAIN RIPRAP	35.00	CY
610.213	VOID-FILLED RIPRAP TYPE A OR B	30.00	CY
613.319	EROSION CONTROL BLANKET	26,500.00	SY
618.14	SEEDING METHOD NUMBER 2	540.00	UN
619.12	MULCH	540.00	UN
619.1202	TEMPORARY MULCH	50.00	UN
620.58	EROSION CONTROL GEOTEXTILE	85.00	SY
627.73	TEMPORARY PAVEMENT MARKING TAPE	27,500.00	LF
627.75	WHITE OR YELLOW PAVEMENT & CURB MARKING	40.00	SF
627.78	TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	140,100.00	LF
627.94	PAVEMENT MARKING TAPE	2,500.00	LF
629.05	HAND LABOR, STRAIGHT TIME	100.00	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.00	HR
631.172	TRUCK - LARGE (INCLUDING OPERATOR)	80.00	HR
631.32	CULVERT CLEANER (INCLUDING OPERATOR)	10.00	HR
631.36	FOREMAN	80.00	HR
652.3	FLASHING ARROW BOARD	4.00	EA
652.35	CONSTRUCTION SIGNS	4,200.00	SF
652.3611	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS
652.3612	MAINTENANCE OF TRAFFIC CONTROL DEVICES (WASHINGTON STREET)	1.00	LS
652.3613	MAINTENANCE OF TRAFFIC CONTROL DEVICES (LISBON STREET)	1.00	LS
652.41	PORTABLE - CHANGEABLE MESSAGE SIGN	6.00	EA
652.4502	TRUCK MOUNTED ATTENUATOR	2.00	EA
652.4503	TRUCK MOUNTED ATTENUATOR	8.00	WK
656.5	BALED HAY, IN-PLACE	50.00	EA
659.1	MOBILIZATION	1.00	LS