



Maine Turnpike Authority *Schedule of Items*

Pavement Rehabilitation Safety Improvements & Pipe End Repairs MM 51.2 to MM 51.5

Item No.	Description	Quantity	UOM
202.202	REMOVING PAVEMENT SURFACE	160,200.00	SY
202.205	RUMBLE STRIPS	51,800.00	EA
211.5	MEDIAN RESTORATION	15,300.00	LF
401.03	BALANCED MIX DESIGN DATA COLLECTION	1.00	LS
403.2081	HOT MIX ASPHALT - 12.5 MM (POLYMER MODIFIED)	15,500.00	T
409.152	BITUMINOUS TACK COAT TRACKLESS, APPLIED	9,700.00	G
419.3	SAW CUTTING BITUMINOUS PAVEMENT	1,000.00	LF
424.3231	ASPHALT RUBBER MASTIC CRACK SEALER	11,100.00	LB
424.324	ASPHALT RUBBER MASTIC CRACK SEALER WITH AGGREGATE	2,800.00	LB
427.09	CRACK REPAIR	15,000.00	LF
459.06	BITUMINOUS CONCRETE WATERWAY, TYPE I	18.00	EA
470.08	BERM DROP OFF CORRECTION - GRINDINGS	17,100.00	LF
470.081	BERM CORRECTION	2,190.00	LF
502.248	UNDERWATER GROUT BAGS	4.00	CY
603.155	12 IN REINFORCED CONCRETE PIPE CLASS III	32.00	LF
603.225	42 IN REINFORCED CONCRETE PIPE CLASS III	16.00	LF
603.235	48 IN REINFORCED CONCRETE PIPE CLASS III	32.00	LF
603.28	CONCRETE COLLAR	3.00	EA
604.182	CLEAN EXISTING CATCH BASIN AND MANHOLE	32.00	EA
604.184	REBUILD CATCH BASIN TO GRADE - TYPE II	8.00	EA
604.186	REBUILD CATCH BASIN TO GRADE - TYPE IV	9.00	EA
606.1351	31" W-BEAM GUARDRAIL - MID-WAY SPLICE TERMINAL END - ANCHORED END	1.00	EA
606.178	GUARDRAIL BEAM	1,100.00	LF
606.265	TERMINAL END-SINGLE RAIL - GALVANIZED STEEL	5.00	EA
606.352	REFLECTORIZED BEAM GUARDRAIL DELINEATORS	510.00	EA
606.3621	GUARDRAIL ADJUST, SINGLE RAIL	2,300.00	LF
606.3622	GUARDRAIL ADJUST, DOUBLE RAIL	2,600.00	LF
606.47	SINGLE WOOD POST	7.00	EA
606.471	SINGLE OFFSET BLOCK - W-BEAM	180.00	EA
610.08	PLAIN RIPRAP	120.00	CY
613.319	EROSION CONTROL BLANKET	14,300.00	SY
618.14	SEEDING METHOD NUMBER 2	300.00	UN
619.12	MULCH	300.00	UN
620.58	EROSION CONTROL GEOTEXTILE	220.00	SY
627.73	TEMPORARY PAVEMENT MARKING TAPE	5,150.00	LF
627.78	TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	104,600.00	LF
627.812	TEMPORARY RAISED PAVEMENT MARKERS	7,000.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
627.94	PAVEMENT MARKING TAPE	1,350.00	LF
627.941	PAVEMENT MARKING TAPE DOTTED WHITE LINE 6-INCH WIDTH	3,200.00	LF
629.05	HAND LABOR, STRAIGHT TIME	80.00	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.00	HR
631.172	TRUCK - LARGE (INCLUDING OPERATOR)	80.00	HR
631.32	CULVERT CLEANER (INCLUDING OPERATOR)	10.00	HR
631.36	FOREMAN	80.00	HR
652.3	FLASHING ARROW BOARD	4.00	EA
652.35	CONSTRUCTION SIGNS	3,050.00	SF
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS
652.41	PORTABLE - CHANGEABLE MESSAGE SIGN	4.00	EA
652.4502	TRUCK MOUNTED ATTENUATOR	2.00	EA
652.4503	TRUCK MOUNTED ATTENUATOR	4.00	WK
656.5	BALED HAY, IN-PLACE	40.00	EA
659.1	MOBILIZATION	1.00	LS