



Maine Turnpike Authority

Schedule of Items

Portland Area Widening & Safety Improvements MM 46.4 TO MM 49.3

Item No.	Description	Quantity	UOM
201.11	Clearing	2.90	AC
201.23	Removing Single Tree Top Only	1.00	EA
201.24	Removing Stump	1.00	EA
202.12	Removing Existing Structural Concrete	10.00	CY
202.15	Removing Existing Manhole or Catch Basin	25.00	EA
202.202	Removing Pavement Surface	15,790.00	SY
202.206	Removing Rumble Strips	2,000.00	LF
203.2	Common Excavation	129,500.00	CY
203.21	Rock Excavation	13,550.00	CY
203.25	Granular Borrow	22,550.00	CY
203.34	Lightweight Fill	470.00	CY
304.1	Aggregate Subbase Course - Gravel	29,800.00	CY
304.14	Aggregate Base Course - Type A	16,450.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	13,400.00	TON
403.2072	19.0mm Asphalt Rich Base HMA	12,850.00	TON
403.2081	Hot Mix Asphalt, 12.5 mm (Polymer Modified) – RAP	6,750.00	TON
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate Base Course)	4,510.00	TON
409.15	Bituminous Tack Coat RS1 or RS1h - Applied	9,800.00	GAL
419.3	Sawing Bituminous Pavement	49,625.00	LF
470.08	Berm Dropoff Correction - Grindings	500.00	TON
502.5651	Flowable Concrete Fill	135.00	CY
502.57	Concrete Cap	15.00	CY
513.09	Slope Protection - Portland Cement Concrete	200.00	SY
514.06	Curing Box for Concrete Cylinders	1.00	EA
526.301	Temporary Concrete Barrier, Type I	19,250.00	LF
526.306	Temporary Concrete Barrier, Type 1 - Supplied by Authority (8,000 LF)	1.00	LS
526.352	Median Barrier - Type B (11,600 LF)	1.00	LS
526.353	Median Barrier - Type C (400 LF)	1.00	LS
526.354	Median Barrier - Type D (1,700 LF)	1.00	LS
526.361	Bridge End Post Transition Barrier	4.00	EA
526.362	Type C Transition Barrier	2.00	EA
526.363	Type D Transition Barrier	12.00	EA
526.364	OHSS Foundation Transition Barrier	2.00	EA
527.341	Work Zone Crash Cushions - TL-3	27.00	UNIT
602.4	Pumped Grout Fill	11.00	CY
603.155	12 inch Reinforced Concrete Pipe - Class III	160.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
603.159	12 Inch Culvert Pipe Option III	270.00	LF
603.165	15 inch Reinforced Concrete Pipe - Class III	320.00	LF
603.175	18 inch Reinforced Concrete Pipe - Class III	770.00	LF
603.195	24 inch Reinforced Concrete Pipe - Class III	580.00	LF
603.205	30 inch Reinforced Concrete Pipe - Class III	410.00	LF
603.215	36 inch Reinforced Concrete Pipe - Class III	30.00	LF
603.28	Concrete Collar	8.00	EA
603.47	60 inch Reinforced Concrete Pipe - Class IV	55.00	LF
604.09	Catch Basin Type B1	9.00	EA
604.0961	60" Catch Basin Type B1	5.00	EA
604.0971	72" Catch Basin Type B1	1.00	EA
604.18	Adjusting Manhole or Catch Basin to Grade	10.00	EA
604.182	Cleaning Existing Catch Basin and Manhole	12.00	EA
604.248	Catch Basin Type F6	74.00	EA
604.26	Catch Basin Type B5	12.00	EA
604.266	60" Catch Basin Type B5	2.00	EA
604.4	Secure Catch Basin Grate	6.00	EA
605.09	6 Inch Underdrain Type B	6,700.00	LF
605.11	12 Inch Underdrain Type C	5,300.00	LF
605.12	15 Inch Underdrain Type C	1,300.00	LF
606.1301	31" W Beam Guardrail - Mid-way Splice (7' Steel Post, 8" Offset Blocks, Single Faced)	5,200.00	LF
606.1307	31" W-Beam Guardrail - Mid-way Splice Flared Terminal	8.00	EA
606.1351	31" W-Beam Guardrail - Mid-way Splice Terminal End - Anchored End	4.00	EA
606.353	Reflectorized Flexible Guardrail Marker	12.00	EA
606.356	Underdrain Delineator Post	31.00	EA
606.3561	Delineator Post-Remove and Reset	117.00	EA
606.3631	Guardrail - Remove and Dispose	21,050.00	LF
607.17	Chain Link Fence - 6 Foot	100.00	LF
607.183	Chain Link Snow Fence	192.00	LF
610.071	Stone Fill	470.00	CY
610.08	Plain Riprap	490.00	CY
610.18	Stone Ditch Protection	600.00	CY
610.181	Temporary Stone Check Dam	420.00	CY
613.319	Erosion Control Blanket	47,500.00	SY
615.07	Loam	10,300.00	CY
618.14	Seeding Method Number 2	850.00	UNIT



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
619.1201	Mulch - Plan Quantity	850.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	1,800.00	SY
626.122	Quazite Junction Box (18x11)	65.00	EA
626.22	Non-metallic Conduit	10,700.00	LF
626.31	18 Inch Diameter Foundation	7.00	EA
626.32	24 Inch Diameter Foundation	54.00	EA
626.33	30 Inch Diameter, 8 Feet or Less Foundation	3.00	EA
626.332	30-Inch Diameter, Greater than 8-Feet Long, All 36 Inch and 42 Inch Diameter Foundations	51.00	CY
626.34	Overhead Sign Structure Foundation	1.00	LS
626.38	Ground Mounted Cabinet Foundation	1.00	EA
627.712	White or Yellow Pavement Marking Line	128,600.00	LF
627.73	Temporary 6 Inch Pavement Marking Tape	2,000.00	LF
627.731	Temporary 6 Inch Black Pavement Marking Tape	2,000.00	LF
627.77	Removing Existing Pavement Marking	35,100.00	SF
627.78	Temporary Pavement Marking Line, White or Yellow	168,000.00	LF
629.05	Hand Labor, Straight Time	200.00	HR
631.12	All Purpose Excavator (Including Operator)	200.00	HR
631.13	Bulldozer (Including Operator)	200.00	HR
631.172	Truck-Large (Including Operator)	200.00	HR
631.22	Front End Loader (Including Operator)	200.00	HR
631.32	Culvert Cleaner (Including Operators)	74.00	HR
631.36	Foreman	200.00	HR
634.16	Highway Lighting	1.00	LS
634.208	Remove and Reset Light Standard	41.00	EA
634.231	Conventional Light Standard With LED Fixture	16.00	EA
645.1099	Remove and Dispose Sign	58.00	EA
645.124	Removal, Disassembly and Relocation of VMS and Supporting Structure	1.00	LS
645.161	Breakaway Device Single Pole	12.00	EA
645.162	Breakaway Device Multi Pole	29.00	EA
645.251	Roadside Guide Sign, Type I	3,390.00	SF
645.271	Regulatory, Warning, Confirmation and Route Assembly Sign, Type I	290.00	SF
645.289	Steel H-Beam Poles	20,150.00	LB
645.501	Remove and Reset Mainline Sign No. 1	1.00	EA
645.502	Remove and Reset Mainline Sign No. 2	1.00	EA
645.503	Remove and Reset Mainline Sign No. 3	1.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
645.504	Remove and Reset Mainline Sign No. 4	1.00	EA
645.505	Remove and Reset Mainline Sign No. 5	1.00	EA
645.506	Remove and Reset Mainline Sign No. 6	1.00	EA
645.507	Remove and Reset Mainline Sign No. 7	1.00	EA
645.509	Remove and Reset Mainline Sign No. 9	1.00	EA
645.51	Remove and Reset Mainline Sign No. 10	1.00	EA
645.511	Remove and Reset Mainline Sign No. 11	1.00	EA
645.512	Remove and Reset Mainline Sign No. 12	1.00	EA
645.513	Remove and Reset Mainline Sign No. 13	1.00	EA
645.514	Remove and Reset Mainline Sign No. 14	1.00	EA
645.515	Remove and Reset Mainline Sign No. 15	1.00	EA
645.516	Remove and Reset Mainline Sign No. 16	1.00	EA
645.517	Remove and Reset Mainline Sign No. 17	1.00	EA
645.518	Remove and Reset Mainline Sign No. 18	1.00	EA
645.519	Remove and Reset Mainline Sign No. 19	1.00	EA
645.52	Remove and Reset Mainline Sign No. 20	1.00	EA
645.521	Remove and Reset Mainline Sign No. 21	1.00	EA
645.522	Remove and Reset Mainline Sign No. 22	1.00	EA
645.523	Remove and Reset Mainline Sign No. 23	1.00	EA
645.524	Remove and Reset Mainline Sign No. 24	1.00	EA
652.3	Flashing Arrow	4.00	EA
652.312	Type III Barricades	18.00	EA
652.33	Drum	500.00	EA
652.34	Cone	200.00	EA
652.35	Construction Signs	4,300.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.41	Portable-Changeable Message Sign	6.00	EA
652.45	Truck Mounted Attenuator	2,920.00	CD
652.452	Automated Trailer Mounted Speed Limit Sign	5.00	EA
652.46	Temporary Portable Rumble Strip	36.00	UNIT
652.47	Sequential Flashing Warning Lights	100.00	EA
656.5	Baled Hay, In Place	20.00	EA
656.6	Temporary Berms	200.00	LF
656.632	30 Inch Temporary Silt Fence	23,400.00	LF
659.1	Mobilization	1.00	LS