



Maine Turnpike Authority

Schedule of Items

Exit 44 Southbound On Ramp Improvements Mile 44.3

Item No.	Description	Quantity	UOM
202.15	REMOVING MANHOLE OR CATCH BASIN	2.00	EA
202.202	REMOVING PAVEMENT SURFACE	2,700.00	SY
202.206	REMOVING RUMBLE STRIPS	3,800.00	LF
203.2	COMMON EXCAVATION	7,600.00	CY
203.24	COMMON BORROW	300.00	CY
203.25	GRANULAR BORROW	3,275.00	CY
304.1	AGGREGATE SUBBASE COURSE - GRAVEL	1,125.00	CY
304.14	AGGREGATE BASE COURSE - TYPE A	1,050.00	CY
403.207	HOT MIX ASPHALT, 19.0 MM NOMINAL MAXIMUM SIZE	2,225.00	TON
403.2081	HOT MIX ASPHALT, 12.5 MM (POLYMER MODIFIED)	950.00	TON
403.213	HOT MIX ASPHALT, 12.5 MM NOMINAL MAXIMUM SIZE, BASE	850.00	TON
409.15	BITUMINOUS TACK COAT, APPLIED	740.00	GAL
419.3	SAWING BITUMINOUS PAVEMENT	3,200.00	LF
470.08	BERM DROPOFF CORRECTION - GRINDINGS	150.00	TON
526.306	TEMPORARY CONCRETE BARRIER TYPE I - SUPPLIED BY AUTHORITY (2,900 LF)	1.00	LS
527.343	WORK ZONE CRASH CUSHIONS - TL-3	2.00	UNIT
603.175	18 INCH REINFORCED CONCRETE PIPE - CLASS III	24.00	LF
604.09	CATCH BASIN TYPE B1	2.00	EA
606.13	31" W-BEAM GUARDRAIL - MID-WAY SPLICE (7' STEEL POSTS, 8" OFFSET BLOCKS, SINGLE FACED)	825.00	LF
606.131	31" W-BEAM GUARDRAIL - MID-WAY SPLICE (8' STEEL POSTS, 8" OFFSET BLOCKS, SINGLE FACED)	200.00	LF
606.1351	TERMINAL END - ANCHORED END - 31" W-BEAM GUARDRAIL	1.00	EA
606.2652	TERMINAL END - REMOVE AND STACK	1.00	EA
606.352	REFLECTORIZED BEAM GUARDRAIL DELINEATOR	17.00	EA
606.353	REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.00	EA
606.356	UNDERDRAIN DELINEATOR POST	25.00	EA
606.3561	DELINEATOR POST - REMOVE AND RESET	10.00	EA
606.791	GUARDRAIL - 350 FLARED TERMINAL - 31" W-BEAM GUARDRAIL	1.00	EA
606.82	GUARDRAIL - REMOVE AND STACK EXISTING CRASH END	1.00	EA
610.08	PLAIN RIPRAP	5.00	CY
610.16	HEAVY RIP RAP	385.00	CY
610.18	STONE DITCH PROTECTION	10.00	CY
610.181	TEMPORARY STONE CHECK DAM	100.00	CY
613.319	EROSION CONTROL BLANKET	2,550.00	SY
615.07	LOAM	1,100.00	CY
618.14	SEEDING METHOD NUMBER 2	54.00	UNIT
618.141	SEEDING METHOD NUMBER 3	30.00	UNIT



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
619.1201	MULCH - PLAN QUANTITY	84.00	UNIT
619.1202	TEMPORARY MULCH	1.00	LS
620.58	EROSION CONTROL GEOTEXTILE	330.00	SY
626.122	QUAZITE JUNCTION BOX (18X11)	14.00	EA
626.22	NON-METALLIC CONDUIT	2,700.00	LF
626.31	18 INCH DIAMETER FOUNDATION	6.00	EA
626.32	24 INCH DIAMETER FOUNDATION	16.00	EA
626.33	30 INCH DIAMETER FOUNDATION	2.00	EA
626.36	REMOVE OR MODIFY CONCRETE FOUNDATION	11.00	EA
627.681	TEMPORARY 6 INCH PAINTED PAVEMENT MARKING LINE - YELLOW OR WHITE	4,950.00	LF
627.73	TEMPORARY 6 INCH PAVEMENT MARKING TAPE	18,050.00	LF
627.731	TEMPORARY 6 INCH BLACK PAVEMENT MARKING TAPE	14,100.00	LF
627.744	6" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	14,900.00	LF
627.77	REMOVING EXISTING PAVEMENT MARKING	500.00	SF
627.812	TEMPORARY RAISED PAVEMENT MARKERS	500.00	EA
627.94	PAVEMENT MARKING TAPE	200.00	LF
627.941	PAVEMENT MARKING TAPE – DOTTED WHITE LANE LINE, 6-INCH WIDTH	600.00	LF
627.944	PAVEMENT MARKINGS - RECESSED TAPE - WORDS, ARROWS AND STOP BARS	160.00	SF
629.05	HAND LABOR, STRAIGHT TIME	30.00	HR
631.1	AIR COMPRESSOR (INCLUDING OPERATOR)	20.00	HR
631.11	AIR TOOL (INCLUDING OPERATOR)	20.00	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	30.00	HR
631.14	GRADER (INCLUDING OPERATOR)	30.00	HR
631.171	TRUCK - SMALL (INCLUDING OPERATOR)	30.00	HR
631.22	FRONT END LOADER (INCLUDING OPERATOR)	30.00	HR
631.36	FOREPERSON	30.00	HR
631.51	BUCKET TRUCK	20.00	HR
631.52	SCISSOR LIFT	20.00	HR
634.051	REMOVE AND STACK LIGHT STANDARD	3.00	EA
634.16	HIGHWAY LIGHTING	1.00	LS
634.175	REPLACEMENT LED FIXTURE, INSTALLED	3.00	EA
634.208	REMOVE AND RESET LIGHT STANDARD	4.00	EA
634.231	CONVENTIONAL LIGHT STANDARD WITH LED FIXTURE	10.00	EA
645.105	REMOVE AND STACK SIGN	4.00	EA
645.161	BREAKAWAY DEVICE SINGLE POLE	4.00	EA
645.271	REGULATORY, WARNING, CONFIRMATION AND ROUTE ASSEMBLY SIGNS, TYPE I	102.00	SF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
645.289	STEEL H-BEAM POLES	792.00	LB
645.501	REMOVE AND RESET MAINLINE SIGN NO. 1	1.00	EA
645.502	REMOVE AND RESET MAINLINE SIGN NO. 2	1.00	EA
652.3	FLASHING ARROW	2.00	EA
652.312	TYPE III BARRICADES	5.00	EA
652.33	DRUM	150.00	EA
652.34	CONE	50.00	EA
652.35	CONSTRUCTION SIGNS	910.00	SF
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS
652.39	PORTABLE LIGHT TOWER	2.00	EA
652.41	PORTABLE-CHANGEABLE MESSAGE SIGN	2.00	EA
652.45	TRUCK MOUNTED ATTENUATOR	90.00	CD
652.451	AUTOMATED TRAILER MOUNTED SPEED LIMIT SIGN	90.00	CD
656.632	30" TEMPORARY SILT FENCE	5,800.00	LF
656.6	TEMPORARY BERMS	100.00	LF
656.62	TEMPORARY SLOPE DRAINS	100.00	LF
659.1	MOBILIZATION	1.00	LS