



# Maine Turnpike Authority *Schedule of Items*

## Water Line and Utility Vaults MM 47.1, MM 47.6, & MM 48.5

Item No.	Description	Quantity	UOM
202.12	Remove Existing Structural Concrete	30.00	CY
203.2	Common Excavation	980.00	CY
203.25	Granular Borrow	280.00	CY
304.14	Aggregate Base Course - Type A	850.00	CY
403.213	Hot Mix Asphalt, 12.50 mm Nominal Maximum Size (Base and Intermediate Base Course)	80.00	TON
409.15	Bituminous Tack Coat RS1 or RS1h - Applied	15.00	GAL
419.3	Sawing Bituminous Pavement	450.00	LF
501.231	Dynamic Load Test	2.00	EA
501.4	Steel H-beam Piles, 53 lb/ft, delivered	865.00	LF
501.401	Steel H-beam Piles, 53 lb/ft, in place	865.00	LF
501.9	Pile Tips	10.00	EA
501.91	Pile Splices	10.00	EA
501.92	Pile Driving Equipment Mobilization	1.00	LS
511.091	Temporary Earth Support Systems	1.00	LS
514.06	Curing Box for Concrete Cylinders	1.00	EA
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority (1,760 LF)	1.00	LS
527.341	Work Zone Crash Cushions - TL-3	5.00	UNIT
603.195	24 inch Reinforced Concrete Pipe - Class III	20.00	LF
603.28	Concrete Collar	1.00	EA
603.281	Concrete Collar for Watermain	1.00	EA
603.7424	Remove and Relay 24 inch Concrete Pipe	54.00	LF
604.1581	Utility Vault Extension - STA 2360+02.55 NB	1.00	LS
604.1582	Utility Vault Extension - STA 2340+52.81 NB	1.00	LS
604.1583	Utility Vault Extension - STA 2340+52.81 SB	1.00	LS
606.366	Guardrail, Removed and Reset, Type 3c	540.00	LF
610.08	Plain Riprap	11.00	CY
610.18	Stone Ditch Protection	5.00	CY
613.319	Erosion Control Blanket	200.00	SY
615.07	Loam	170.00	CY
618.14	Seeding Method Number 2	15.00	UNIT
619.1201	Mulch - Plan Quantity	15.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	54.00	SY
627.712	White or Yellow Pavement Marking Line	300.00	LF
627.73	Temporary 6 inch Pavement Marking Tape	600.00	LF
629.05	Hand Labor, Straight Time	15.00	HR



## Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
631.12	All Purpose Excavator (Including Operator)	15.00	HR
631.172	Truck-Large (Including Operator)	15.00	HR
631.22	Front End Loader (Including Operator)	15.00	HR
631.36	Foreman	15.00	HR
652.3	Flashing Arrow	1.00	EA
652.312	Type III Barricades	2.00	EA
652.33	Drum	110.00	EA
652.35	Construction Signs	660.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.41	Portable-Changeable Message Sign	2.00	EA
652.45	Truck Mounted Attenuator	15.00	CD
656.5	Bailed Hay, In Place	15.00	EA
656.632	30 Inch Temporary Silt Fence	900.00	LF
659.1	Mobilization (Utility Vaults)	1.00	LS
659.11	Mobilization (Waterline)	1.00	LS
822.3405	8" Class 52 DI Pipe Push On Joint	10.00	LF
822.3605	12" Class 52 DI Pipe Push on Joint	160.00	LF
823.311	12" Gate Valve	2.00	EA
823.333	1" Air Release Valve	2.00	EA
825.6	12" DR 11 HDPE Pipe	390.00	LF
827.303	Unsuitable Material Below Trench Grade	50.00	CY
845.211	Stone Pipe Support in Casing - NB, SB, & SB On Ramp	1.00	LS
845.212	Stone Pipe Support in Casing - NB Off Ramp	1.00	LS