



Maine Turnpike Authority *Schedule of Items*

KENNEBUNK TRAVEL PLAZAS PARKING EXPANSION MILE 25.5 SB & NB AND ROUTE 25 TRAFFIC SIGNALS

Item No.	Description	Quantity	UOM
201.11	Clearing	7.00	AC
201.23	Removing Single Tree Top Only	27.00	EA
201.24	Removing Stump	27.00	EA
202.15	Removing Existing Manhole or Catch Basin	6.00	EA
202.202	Removing Pavement Surface	13,600.00	SY
202.203	Pavement Butt Joints	2,400.00	SY
202.22	Removing and Stockpiling Boulders	41.00	EA
203.2	Common Excavation	55,300.00	CY
203.2312	Health and Safety Plan	1.00	LS
203.2333	Disposal/Treatment of Special Excavation	250.00	TON
203.2334	Disposal/Treatment of Contaminated Groundwater	100,000.00	GAL
203.25	Granular Borrow	4,450.00	CY
203.43	Foamed Glass Aggregate Lightweight Fill	1,200.00	CY
203.45	Clay Borrow	200.00	CY
304.1	Aggregate Subbase Course - Gravel	29,400.00	CY
304.14	Aggregate Base Course - Type A	7,700.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	9,000.00	TON
403.208	Hot Mix Asphalt, 12.5 mm - RAP	4,300.00	TON
403.2081	Hot Mix Asphalt, 12.5 mm (Polymer Modified) - RAP	2,900.00	TON
403.2084	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (sidewalks, drives, islands & incidentals)	290.00	TON
403.212	Hot Mix Asphalt, 4.75 mm Nominal Maximum Size	795.00	TON
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate Base Course)	5,050.00	TON
409.15	Bituminous Tack Coat RS-1 or RS1H - Applied	7,200.00	GAL
411.12	Crushed Stone Surface	54.00	TON
419.3	Sawing Bituminous Pavement	10,800.00	LF
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority (3520 LF)	1.00	LS
526.307	Concrete Barrier Type I - Stormwater Filter	100.00	LF
527.341	Work Zone Crash Cushions - TL-3	5.00	UNIT
527.342	Work Zone Crash Cushions - TL-2	1.00	UNIT
602.3	Flowable Concrete Fill	110.00	CY
603.05	6" PVC Pipe	52.00	LF
603.155	12 inch Reinforced Concrete Pipe - Class III	1,050.00	LF
603.1552	12 inch Reinforced Concrete Pipe - Class IV	200.00	LF
603.165	15 inch Reinforced Concrete Pipe - Class III	130.00	LF
603.175	18 inch Reinforced Concrete Pipe - Class III	770.00	LF
603.179	18 Inch Culvert Pipe Option III	50.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
603.195	24 inch Reinforced Concrete Pipe - Class III	520.00	LF
603.205	30 inch Reinforced Concrete Pipe - Class III	440.00	LF
603.215	36 inch Reinforced Concrete Pipe - Class III	300.00	LF
603.225	42 inch Reinforced Concrete Pipe - Class III	120.00	LF
603.28	Concrete Collar	4.00	EA
604.09	Catch Basin Type B1	21.00	EA
604.093	60" Catch Basin Type B1	3.00	EA
604.094	72" Catch Basin Type B1	1.50	EA
604.11	Catch Basin Type C1	1.00	EA
604.16	Altering Catch Basin to Manhole	1.00	EA
604.164	Rebuilding Catch Basin	1.00	EA
604.18	Adjusting Manhole or Catch Basin To Grade	3.00	EA
604.182	Cleaning Existing Catch Basin and Manhole	4.00	EA
604.244	Catch Basin Type F4	2.00	EA
604.248	Catch Basin Type F6	2.00	EA
604.3	Oil-Water Separator System	1.00	EA
605.016	6 Inch PVC Underdrain	1,550.00	LF
605.018	8 Inch PVC Underdrain	600.00	LF
605.09	6 Inch Underdrain Type B	810.00	LF
605.1	6 Inch Underdrain Outlet	23.00	LF
605.13	18 Inch Underdrain Type C	140.00	LF
606.1301	31" W-Beam Guardrail - Mid-Way Splice (7' Steel Posts, 8" Offset Blocks, Single Faced)	1,850.00	LF
606.1307	31" W-Beam Guardrail - Mid-Way Splice Flared Terminal	2.00	EA
606.1351	Terminal End - Anchored End - 31" W-Beam Guardrail	2.00	EA
606.356	Underdrain Delineator Post	230.00	EA
606.3561	Delineator Post – Remove and Reset	58.00	EA
606.3605	Guardrail - Remove, Modify and Reset Single Rail	190.00	LF
606.3606	Guardrail - Remove, Modify and Reset Double Rail	25.00	LF
606.79	Guardrail 350 Flared Terminal	2.00	EA
607.24	Remove and Reset Fence	220.00	LF
607.44	Safety Fence	4,470.00	LF
608.08	Reinforced Concrete Sidewalk	220.00	SY
608.26	Curb Ramp Detectable Warning Field	48.00	SF
609.12	Vertical Curb Type 1 - Circular	85.00	LF
609.234	Terminal Curb Type 1 - 4 foot	2.00	EA
609.238	Terminal Curb Type 1 - 8 foot	1.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
609.31	Curb Type 3	150.00	LF
609.34	Curb Type 5	2,350.00	LF
609.35	Curb - Type 5 - Circular	140.00	LF
609.38	Reset Curb Type 1	790.00	LF
610.08	Plain Riprap	180.00	CY
610.18	Stone Ditch Protection	120.00	CY
610.181	Temporary Stone Check Dam	47.00	CY
613.319	Erosion Control Blanket	13,800.00	SY
615.07	Loam	5,400.00	CY
618.13	Seeding Method Number 1	15.00	UNIT
618.14	Seeding Method Number 2	380.00	UNIT
618.143	Special Seeding	38.00	UNIT
619.1201	Mulch - Plan Quantity	420.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.56	Drainage Geotextile	4,100.00	SY
620.58	Erosion Control Geotextile	950.00	SY
620.6	Separation Geotextile	2,700.00	SY
621.037	Evergreen Trees (5'-6'), GP A - Pinus Resinosa (Red Pine)	11.00	EA
626.121	Quazite Junction Box (36x24)	8.00	EA
626.122	Quazite Junction Box (18x11)	110.00	EA
626.22	Non-metallic Conduit	26,300.00	LF
626.31	18 inch Diameter Foundation	1.00	EA
626.32	24 inch Diameter Foundation	53.00	EA
626.33	30 inch Diameter, 8 feet or less Foundation	16.00	EA
626.332	30-Inch Diameter, Greater than 8-Feet Long, And all 36-Inch and 42-Inch Diameter Foundations	60.00	CY
626.35	Controller Cabinet Foundation	2.00	EA
627.712	White or Yellow Pavement Marking Line	65,000.00	LF
627.75	White or Yellow Pavement & Curb Marking	570.00	SF
627.77	Removing Existing Pavement Marking	8,470.00	SF
627.812	Temporary Raised Pavement Markers	100.00	EA
627.941	Pavement Marking Tape - Dotted White Lane Line, 6-Inch Width	430.00	LF
629.05	Hand Labor, Straight Time	40.00	HR
631.12	All Purpose Excavator (Including Operator)	40.00	HR
631.13	Bulldozer (Including Operator)	40.00	HR
631.172	Truck - Large (Including Operator)	80.00	HR
631.22	Front End Loader (Including Operator)	40.00	HR



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
631.32	Culvert Cleaner (Including Operators)	16.00	HR
631.36	Foreman	40.00	HR
634.2041	Luminaires	35.00	EA
634.208	Remove and Reset Light Standard	37.00	EA
634.21	Conventional Light Standard	16.00	EA
639.18	Field Office, Type A	1.00	EA
643.71	Traffic Signal Modifications at: Alewife Road w/ Fletcher Street	1.00	LS
643.801	Traffic Signal at: I-95 SB w/ Alewife	1.00	LS
643.802	Traffic Signal at: I-95 NB w/ Fletcher Street	1.00	LS
643.831	Video Detection System: I-95 SB with Alewife	1.00	LS
643.832	Video Detection System: I-95 NB with Fletcher Street	1.00	LS
643.911	Mast Arm Pole - 25' Mast Arm	3.00	EA
643.912	Mast Arm Pole - 30' Mast Arm	1.00	EA
643.913	Mast Arm Pole - 35' Mast Arm	2.00	EA
643.914	Mast Arm Pole - 40' Mast Arm	1.00	EA
643.92	Pedestal Pole - 8 Foot	1.00	EA
643.94	Dual Purpose Pole - 30' Mast Arm and 12' Luminaire Arm	1.00	EA
645.105	Remove and Stack Sign	135.00	EA
645.109	Remove and Reset Sign	45.00	EA
645.1211	Overhead Sign Structure and Guide Sign	1.00	LS
645.161	Breakaway Device Single Pole	10.00	EA
645.162	Breakaway Device Multi Pole	13.00	EA
645.251	Roadside Guide Signs, Type I	560.00	SF
645.252	Roadside Guide Signs, Type I - Supplied by Authority	420.00	SF
645.271	Regulatory, Warning, Confirmation and Route Assembly Sign, Type 1	570.00	SF
645.289	Steel H-Beam Poles	5,650.00	LBS
645.511	Radar Activated Flashing LED Yield Sign	1.00	EA
652.3	Flashing Arrow	2.00	EA
652.312	Type III Barricades	4.00	EA
652.33	Drum	490.00	EA
652.34	Cone	20.00	EA
652.35	Construction Signs	1,370.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	660.00	HR
652.41	Portable-Changeable Message Sign	2.00	EA
652.45	Truck Mounted Attenuator	12.00	CD
652.4501	Truck Mounted Attenuator - 24,000 LB	16.00	CD



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
652.451	Automated Trailer Mounted Speed Limit Sign	10.00	CD
655.102	#2 AWG Wire	13,150.00	LF
655.106	#6 AWG Wire	16,700.00	LF
655.11	#10 AWG Wire	5,850.00	LF
656.5	Baled Hay, In Place	20.00	EA
656.6	Temporary Berms	3,000.00	LF
656.62	Temporary Slope Drains	500.00	LF
656.632	30 inch Temporary Silt Fence	2,750.00	LF
659.1	Mobilization	1.00	LS
673.01	Stormwater Filter Bed	710.00	CY
801.1331	6" Sewer Force Main	1.00	LS
822.3408	8-Inch Ductile Iron Water Pipe	1,600.00	LF
822.411	8-Inch Ductile Iron Pipe Fittings	1,110.00	LB
823.325	8-Inch Gate Valve	3.00	EA
825.411	Food Truck Water Connection	1.00	LS
827.3641	Remove 8-Inch Asbestos-Cement Pipe	900.00	LF
830.27	Horizontal Directional Drilling, 3 inch HDPE Conduit	1,420.00	LF