



Maine Turnpike Authority *Schedule of Items*

Bridge Repairs - Route 236 Underpass (MM 1.25) & Route 1 On-Ramp (Ramp H) Underpass (MM 1.60)

Item No.	Description	Quantity	UOM
202.1211	Removing Existing Girder Haunches	6,360.00	LF
202.122	Removing Existing Structural Concrete	50.00	SF
202.202	Removing Pavement Surface	4,700.00	SY
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Surface)	470.00	TON
409.15	Bituminous Tack Coat RS-1 or RS1h - Applied	193.00	GAL
502.702	Replace Bridge Drain (Type A1)	10.00	EA
506.14	Field Painting of Existing Structural Steel (Ramp H)	1.00	LS
508.141	High Performance Waterproofing Membrane (Rt 236) (2,360SY)	1.00	LS
508.142	High Performance Waterproofing Membrane (Ramp H) (675 SY)	1.00	LS
515.201	Pigmented Protective Coating for Concrete Surfaces	1,530.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	910.00	SY
518.1	Abutment Repairs	195.00	SF
518.2	Pier Repairs	5.00	SF
518.391	Repairing Granite Curb Joint and Bedding Mortar	1,450.00	LF
518.4	Epoxy Injection Crack Repair	45.00	LF
518.75	Fascia and Overhang Repairs	10.00	SF
518.8	Partial Depth Concrete Deck Repairs	945.00	SF
518.81	Full Depth Concrete Deck Repairs	30.00	SF
518.82	Median Concrete Deck Repairs	170.00	SF
518.864	Elastomeric Concrete Header Repair	63.00	CF
518.92	Slope Protection Repairs	100.00	LF
520.23	Asphaltic Plug Joint (Route 236)	100.00	LF
520.234	Expansion Device - Silicone Coated and Pre-Compressed Seal	245.00	LF
520.5	Remove and Replace Gland Seal (RT 236)	1.00	EA
523.1201	Reset Steel Bearings	2.00	EA
524.7212	Jacking Existing Superstructure (Route 236)	1.00	LS
526.301	Temporary Concrete Barrier, Type 1	1,075.00	LF
527.341	Work Zone Crash Cushion - TL-3	2.00	U
527.343	Resetting Existing Work Zone Crash Cushion	2.00	U
609.11	Vertical Curb Type 1	35.00	LF
626.15	Electrical Service Box	1.00	EA
627.712	White or Yellow Pavement Marking Line	5,600.00	LF
627.73	Temporary 6" Pavement Marking Tape	5,250.00	LF
627.731	Temporary 6" Black Pavement Marking Tape	3,250.00	LF
627.77	Removing Existing Pavement Markings	225.00	SF
629.05	Hand Labor, Straight Time	60.00	HR
631.1	Air Compressor (including operator)	60.00	HR



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
631.11	Air Tool (including operator)	60.00	HR
631.12	All Purpose Excavator (including operator)	60.00	HR
631.171	Truck - small (including operator)	60.00	HR
631.36	Foreman	60.00	HR
634.1612	Removal of Bridge & Highway Lighting Including Wire	1.00	LS
652.3	Flashing Arrow	6.00	EA
652.312	Type III Barricade	6.00	EA
652.33	Drum	325.00	EA
652.34	Cone	100.00	EA
652.35	Construction Signs	1,953.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	425.00	HR
652.41	Portable Changeable Message Sign	4.00	EA
652.45	Truck Mounted Attenuator	160.00	CD
652.451	Automated Trailer Mounted Speed Limit Sign	115.00	CD
652.47	Sequential Flashing Warning Lights	90.00	EA
656.75	Temporary Soil Erosion and Water Pollution Control	1.00	LS
659.1	Mobilization	1.00	LS