



Maine Turnpike Authority

Schedule of Items

Pavement Rehabilitation & Safety Improvements MM 27.4 to MM 30.3

Item No.	Description	Quantity	UOM
202.202	REMOVING PAVEMENT SURFACE	182,900.00	SY
202.205	RUMBLE STRIPS	55,200.00	EA
203.2	COMMON EXCAVATION	10.00	CY
211.5	MEDIAN RESTORATION	14,200.00	LF
304.14	AGGREGATE BASE COURSE GRAVEL, TYPE A	5.00	CY
401.03	BALANCED MIX DESIGN DATA COLLECTION	1.00	LS
401.1	HOT MIX ASPHALT CONTINUOUS THERMAL PROFILING	1.00	LS
403.2081	HOT MIX ASPHALT - 12.5 MM (POLYMER MODIFIED)	18,600.00	T
403.2084	HOT MIX ASPHALT - 12.5 MM (INCIDENTALS)	100.00	T
403.211	HOT MIX ASPHALT (SHIMMING)	100.00	T
403.213	HOT MIX ASPHALT - 12.5 MM (BASE)	20.00	T
409.152	BITUMINOUS TACK COAT TRACKLESS, APPLIED	11,100.00	G
419.3	SAW CUTTING BITUMINOUS PAVEMENT	600.00	LF
424.3231	ASPHALT RUBBER MASTIC CRACK SEALER	9,800.00	LB
424.324	ASPHALT RUBBER MASTIC CRACK SEALER WITH AGGREGAT	2,500.00	LB
427.09	CRACK REPAIR	13,800.00	LF
459.06	BITUMINOUS CONCRETE WATERWAY, TYPE I	5.00	EA
459.061	BITUMINOUS CONCRETE WATERWAY, TYPE II	5.00	EA
470.08	BERM DROP OFF CORRECTION - GRINDINGS	19,300.00	LF
470.081	BERM CORRECTION	6,600.00	LF
604.182	CLEAN EXISTING CATCH BASIN AND MANHOLE	26.00	EA
604.184	REBUILDING CATCH BASIN TYPE II	20.00	EA
604.185	REBUILDING CATCH BASIN TYPE IV	5.00	EA
606.1307	31" W-BEAM GUARDRAIL - MID-WAY SPLICE FLARED TERMINA	1.00	EA
606.178	GUARDRAIL BEAM	200.00	LF
606.352	REFLECTORIZED BEAM GUARDRAIL DELINEATORS	350.00	EA
606.3621	GUARDRAIL ADJUST, SINGLE RAIL	1,000.00	LF
606.3622	GUARDRAIL ADJUST, DOUBLE RAIL	2,300.00	LF
606.47	SINGLE WOOD POST	1.00	EA
606.471	SINGLE OFFSET BLOCK - W-BEAM	15.00	EA
606.48	SINGLE GALVANIZED STEEL POST	10.00	EA
610.08	PLAIN RIPRAP	6.00	CY
613.319	EROSION CONTROL BLANKET	12,600.00	SY
618.14	SEEDING METHOD NUMBER 2	260.00	UN
619.12	MULCH	260.00	UN
619.1202	TEMPORARY MULCH	1.00	LS
620.58	EROSION CONTROL GEOTEXTILE	20.00	SY



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
627.73	TEMPORARY PAVEMENT MARKING TAPE	18,800.00	LF
627.75	WHITE OR YELLOW PAVEMENT & CURB MARKING	40.00	SF
627.78	TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	65,900.00	LF
627.94	PAVEMENT MARKING TAPE	1,200.00	LF
629.05	HAND LABOR, STRAIGHT TIME	40.00	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	25.00	HR
631.172	TRUCK - LARGE (INCLUDING OPERATOR)	25.00	HR
631.32	CULVERT CLEANER (INCLUDING OPERATOR)	10.00	HR
631.36	FOREMAN	25.00	HR
652.3	FLASHING ARROW BOARD	4.00	EA
652.35	CONSTRUCTION SIGNS	3,000.00	SF
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS
652.41	PORTABLE - CHANGEABLE MESSAGE SIGN	4.00	EA
652.4502	TRUCK MOUNTED ATTENUATOR	2.00	EA
652.4503	TRUCK MOUNTED ATTENUATOR	8.00	WK
656.5	BALED HAY, IN-PLACE	50.00	EA
659.1	MOBILIZATION	1.00	LS
661.1	TOLL STIPEND	1.00	LS