



Maine Turnpike Authority *Schedule of Items*

Pavement Rehabilitation, Clearzone and Drainage Improvements MM 20.0 TO MM 23.3

Item No.	Description	Quantity	UOM
202.202	Removing Pavement Surface - Shoulders	29,000.00	SY
202.203	Pavement Butt Joints	2,510.00	SY
202.205	Rumble Strips	69,696.00	EA
203.2	Common Excavation	280.00	EA
211.5	Median Restoration	11,616.00	LF
304.14	Aggregate Base Course - Type A	175.00	CY
403.2081	Hot Mix Asphalt, 12.5mm (Polymer Modified)- RAP	18,630.00	Ton
403.211	Hot Mix Asphalt 9.5mm (Outside 12' Shoulder NB/SB)	2,880.00	Ton
403.2111	Hot Mix Asphalt 9.5mm (shimming)	300.00	Ton
403.213	Hot Mix Asphalt, 12.5mm - RAP	4,110.00	Ton
409.152	Bituminous Tack Coat Trackless - Applied	16,500.00	GAL
419.3	Full Depth Bituminous Sawcut	11,796.00	LF
424.323	Asphalt Rubber Mastic Crack Sealant	16,000.00	LB
470.08	Berm Dropoff Correction - Grindings	1,220.00	Ton
470.081	Berm Correction	9,600.00	LF
606.178	Guardrail Beam	250.00	LF
604.184	Rebuild Catch Basin to Grade - Type II	16.00	EA
606.132	31" W-Beam Guardrail - mid-way Splice (7' Steel Posts, 8" offset Blocks, Double faced)	500.00	LF
606.353	Delineator Post	75.00	EA
606.355	Delineator Post - Remove and Stack	75.00	EA
606.3621	Guardrail Adjust, Single Rail	9,600.00	LF
606.3622	Guardrail Adjust, Double Rail	18,500.00	LF
606.47	Single Wood Post	20.00	EA
606.471	Single Offset Block - W-Beam	30.00	EA
606.48	Single Galvanized Steel Post	30.00	EA
613.319	Erosion Control Blanket	5,200.00	SY
615.07	Loam	50.00	CY
618.1401	Seeding Method Number 2, Plan Quantity	211.00	UNIT
619.1202	Temporary Mulch	1.00	LS
627.73	Temporary Pavement Marking Line Tape	5,228.00	LF
627.78	Temporary Pavement Marking Line	75,000.00	LF
627.812	Temporary Raised Pavement Markers	7,000.00	EA
627.94	Pavement Marking Tape	2,614.00	LF
629.05	Hand Labor, Straight Time	30.00	HR
631.1	Air Compressor (including operator)	10.00	HR
631.11	Air Tool (including operator)	10.00	HR



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
631.12	All Purpose Excavator (including operator)	20.00	HR
631.172	Truck - Large (including operator)	40.00	HR
631.36	Foreman	20.00	HR
652.3	Flashing Arrow	6.00	EA
652.35	Construction Signs	2,950.00	SF
652.3611	Maintenance of Traffic Control Devices	1.00	LS
652.411	Portable - Changeable Message Sign	2.00	EA
652.4502	Truck Mounted Attenuator	2.00	EA
652.4503	Truck Mounted Attenuator	16.00	WK
652.452	Automated Trailer Mounted Speed Limit Sign	2.00	EA
656.5	Baled Hay, in place	30.00	EA
656.632	30 inch Temporary Silt Fence	100.00	LF
659.1	Mobilization	1.00	LS