



Maine Turnpike Authority *Schedule of Items*

Interchange 103 Barrier Toll Plaza Open Road Tolling Conversion Mile 103.0

Item No.	Description	Quantity	UOM
201.11	CLEARING	4.00	AC
201.23	REMOVING SINGLE TREE TOP ONLY	4.00	EA
201.24	REMOVING STUMP	4.00	EA
202.071	REMOVING ASBESTOS CONTAINING MATERIALS, TOLL BOOTH LAB TOPS	1.00	LS
202.081	REMOVING EXISTING BUILDING	1.00	LS
202.15	REMOVING EXISTING MANHOLE OR CATCH BASIN	6.00	EA
202.17	REMOVING EXISTING STRUCTURAL CONCRETE	1.00	LS
202.202	REMOVING PAVEMENT SURFACE	27,850.00	SY
202.203	PAVEMENT BUTT JOINTS	1,910.00	SY
202.205	RUMBLE STRIPS	29,850.00	EA
202.206	REMOVING RUMBLE STRIPS	8,650.00	LF
203.2	COMMON EXCAVATION	88,000.00	CY
203.21	ROCK EXCAVATION	200.00	CY
203.231	UNDERGROUND STORAGE TANK REMOVAL	1.00	LS
203.2312	DISPOSAL / TREATMENT OF SPECIAL EXCAVATION	50.00	TON
203.25	GRANULAR BORROW	28,325.00	CY
206.082	STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	2,350.00	CY
304.09	AGGREGATE BASE COURSE - CRUSHED	11,285.00	CY
304.1	AGGREGATE SUBBASE COURSE - GRAVEL	18,135.00	CY
403.207	HOT MIX ASPHALT, 19.0 MM NOMINAL MAXIMUM SIZE	16,150.00	TON
403.208	HOT MIX ASPHALT, 12.5 MM	900.00	TON
403.2081	HOT MIX ASPHALT, 12.5 MM (POLYMER MODIFIED) - RAP	9,110.00	TON
403.209	HOT MIX ASPHALT, 9.5 MM NOMINAL MAXIMUM SIZE (SIDEWALKS, DRIVES, ISLANDS & INCIDENTALS)	100.00	TON
403.211	HOT MIX ASPHALT, 9.5 MM NOMINAL MAXIMUM SIZE (SHIMMING)	1,658.00	TON
403.213	HOT MIX ASPHALT, 12.5 MM NOMINAL MAXIMUM SIZE (BASE AND INTERMEDIATE BASE COURSE)	7,570.00	TON
409.152	BITUMINOUS TACK COAT NTSS - 1HM TRACKLESS - APPLIED	15,700.00	GAL
419.3	SAWING BITUMINOUS PAVEMENT	5,760.00	LF
470.08	BERM DROPOFF CORRECTION - GRINDINGS	248.00	TON
470.081	BERM CORRECTION	4,500.00	LF
502.231	STRUCTURAL CONCRETE, SPACE FRAME PEDESTALS & FOOTINGS	96.00	CY
502.232	STRUCTURAL CONCRETE, UTILITY PITS	145.00	CY
502.261	STRUCTURAL CONCRETE, ORT SLABS	210.00	CY
502.262	STRUCTURAL CONCRETE, CASH SLABS	280.00	CY
502.263	STRUCTURAL CONCRETE, PLAZA ISLANDS, BUMPERS, AND CURTAIN WALLS	200.00	CY
503.14	EPOXY-COATED REINFORCING STEEL, FABRICATED & DELIVERED	43,700.00	LB
503.15	EPOXY-COATED REINFORCING STEEL, PLACING	43,700.00	LB



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
503.181	GLASS FIBER REINFORCED POLYMER (GFRP) REINFORCING BARS (#5), FABRICATED & DELIVERED	83,500.00	LF
503.182	GLASS FIBER REINFORCED POLYMER (GFRP) REINFORCING BARS (#12), FABRICATED & DELIVERED	180.00	LF
503.191	GLASS FIBER REINFORCED POLYMER (GFRP) REINFORCING BARS (#5), PLACING	83,500.00	LF
503.192	GLASS FIBER REINFORCED POLYMER (GFRP) REINFORCING BARS (#12), PLACING	180.00	LF
503.9	SYNTHETIC FIBER REINFORCEMENT	2,450.00	LB
504.5	TOLL PLAZA CANOPIES	1.00	LS
504.8	SPACE FRAME CANOPIES, FABRICATED AND DELIVERED	1.00	LS
504.81	SPACE FRAME CANOPIES, ERECTION	1.00	LS
504.9	STEEL POST SUPPORT SYSTEMS	1.00	LS
504.91	MOUNTING BRACKET ASSEMBLIES	1.00	LS
504.96	METAL STAIRS	1.00	LS
508.14	HIGH PERFORMANCE WATERPROOFING MEMBRANE	1.00	LS
511.091	TEMPORARY EARTH SUPPORT SYSTEMS	1.00	LS
515.2011	PIGMENTED CONCRETE PROTECTIVE COATING - TUNNEL AND STAIRWAY WALLS & CEILING	750.00	SY
515.2012	PIGMENTED CONCRETE PROTECTIVE COATING - TUNNEL FLOOR	270.00	SY
515.202	CLEAR PROTECTIVE COATING FOR CONCRETE SURFACES	2,500.00	SY
515.23	EPOXY OVERLAY	225.00	SF
526.301	TEMPORARY CONCRETE BARRIER TYPE I (9,000 LF)	1.00	LS
526.351	MEDIAN BARRIER TYPE I	450.00	LF
526.3511	MEDIAN BARRIER TYPE IA - PRECAST	2,806.00	LF
526.3513	MEDIAN BARRIER TYPE IB - PRECAST	938.00	LF
526.3514	MEDIAN BARRIER TYPE IC - PRECAST	170.00	LF
526.3515	MEDIAN BARRIER TYPE ID - PRECAST	107.00	LF
526.3516	MEDIAN BARRIER TYPE IE - PRECAST	51.00	LF
526.352	MEDIAN BARRIER TYPE II	134.00	LF
526.3611	MEDIAN BARRIER TRANSITION TYPE IA - PRECAST	3.00	EA
526.3612	MEDIAN BARRIER TRANSITION TYPE IB - PRECAST	1.00	EA
526.362	MEDIAN BARRIER TRANSITION TYPE II - PRECAST	4.00	EA
526.371	MEDIAN BARRIER WITH MOUNTED LIGHT POLE TYPE I	17.00	EA
527.306	CENTER BARRIER CRASH ATTENUATOR	3.00	EA
527.342	WORK ZONE CRASH CUSHIONS - TL-2	5.00	UNIT
527.343	WORK ZONE CRASH CUSHIONS - TL-3	7.00	UNIT
535.7	PRECAST CONCRETE TUNNEL	1.00	LS



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
602.3	FLOWABLE CONCRETE FILL	8.00	CY
603.155	12 INCH REINFORCED CONCRETE PIPE - CLASS III	99.00	LF
603.165	15 INCH REINFORCED CONCRETE PIPE - CLASS III	95.00	LF
603.175	18 INCH REINFORCED CONCRETE PIPE - CLASS III	603.00	LF
603.195	24 INCH REINFORCED CONCRETE PIPE - CLASS III	73.00	LF
603.205	30 INCH REINFORCED CONCRETE PIPE - CLASS III	40.00	LF
603.28	CONCRETE COLLAR FOR REINFORCED CONCRETE PIPE	2.00	EA
604.072	CATCH BASIN TYPE A1-C	2.13	EA
604.09	CATCH BASIN TYPE B1	5.13	EA
604.097	60" CATCH BASIN TYPE B5-C	1.13	EA
604.15	MANHOLE	2.13	EA
604.18	ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	5.00	EA
604.245	CATCH BASIN TYPE F4-C	1.00	EA
604.26	CATCH BASIN TYPE B5	40.00	EA
605.09	6 INCH UNDERDRAIN TYPE B	1,729.00	LF
605.11	12 INCH UNDERDRAIN TYPE C	236.00	LF
605.111	12 INCH UNDERDRAIN TYPE C - SDR	600.00	LF
605.12	15 INCH UNDERDRAIN TYPE C	236.00	LF
605.13	18 INCH UNDERDRAIN TYPE C	140.00	LF
606.13	31" W-BEAM GUARDRAIL-MID-WAY SPLICE (7' STEEL POSTS, 8" OFFSET BLOCKS, SINGLE FACED)	2,940.63	LF
606.1306	31" W-BEAM GUARDRAIL-MIDWAY SPLICE TANGENT TERMINAL	7.00	EA
606.131	31" W-BEAM GUARDRAIL-MID-WAY SPLICE (8' STEEL POSTS, 8" OFFSET BLOCKS, SINGLE FACED)	662.50	LF
606.132	31" W-BEAM GUARDRAIL-MID-WAY SPLICE (7' STEEL POSTS, 8" OFFSET BLOCKS, DOUBLE FACED)	1,612.50	LF
606.1351	31" W-BEAM GUARDRAIL - MID-WAY SPLICE TERMINAL END - ANCHORED END	12.00	EA
606.1724	BRIDGE TRANSITION - TYPE III, MODIFIED	2.00	EA
606.2651	TERMINAL END - REMOVE AND RESET	1.00	EA
606.2652	TERMINAL END - REMOVE AND STACK	9.00	EA
606.275	TERMINAL END - DOUBLE RAIL - GALVANIZED STEEL	2.00	EA
606.352	REFLECTORIZED BEAM GUARDRAIL DELINEATOR	130.00	EA
606.353	DELINEATOR POST	94.00	EA
606.3561	DELINEATOR POST - REMOVE AND RESET	102.00	EA
606.3605	GUARDRAIL - REMOVE, MODIFY, AND RESET SINGLE RAIL	950.00	LF
606.3621	GUARDRAIL ADJUST, SINGLE RAIL	3,400.00	LF
606.82	GUARDRAIL - REMOVE AND STACK EXISTING CRASH END	1.00	EA
607.2326	AUTOMATIC ENTRY GATE	1.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
607.4	CHAIN LINK FENCE - 3' HIGH	510.00	LF
607.41	POST ASSEMBLY FOR SIGN OR CHAIN LINK FENCE	66.00	EA
607.4211	DUMPSTER ENCLOSURE	1.00	LS
608.08	REINFORCED CONCRETE SIDEWALK	110.00	SY
608.26	CURB RAMP DETECTABLE WARNING FIELD	36.00	SF
609.11	VERTICAL CURB TYPE 1	1,000.00	LF
609.12	VERTICAL CURB TYPE 1 - CIRCULAR	200.00	LF
609.234	TERMINAL CURB TYPE 1 - 4 FT	4.00	EA
609.238	TERMINAL CURB TYPE 1 - 8 FT	2.00	EA
610.08	PLAIN RIPRAP	34.00	CY
610.18	STONE DITCH PROTECTION	27.00	CY
610.181	TEMPORARY STONE CHECK DAM	325.00	CY
613.319	EROSION CONTROL BLANKET	13,750.00	SY
614.3	GEOCELL CONFINEMENT SYSTEM FOR SLOPE PROTECTION	16,000.00	SF
615.07	LOAM	7,690.00	CY
618.13	SEEDING METHOD NUMBER 1	45.00	UNIT
618.14	SEEDING METHOD NUMBER 2	584.00	UNIT
619.1201	MULCH - PLAN QUANTITY	629.00	UNIT
619.1202	TEMPORARY MULCH	1.00	LS
619.1401	EROSION CONTROL MIX	50.00	CY
620.58	EROSION CONTROL GEOTEXTILE	910.00	SY
621.043	EVERGREEN TREE (6' - 8') GROUP A	2.00	EA
621.396	DWARF EVERGREEN (18" - 24") GROUP B	8.00	EA
621.512	HYBRID RHODODENDRON (2' - 2.5')	3.00	EA
621.553	DECIDUOUS SHRUB (3' - 4') GROUP B	4.00	EA
625.106	WATER SERVICE SUPPLY LINE (<3 IN)	2,400.00	LF
626.121	QUAZITE JUNCTION BOX (36X24)	11.00	EA
626.122	QUAZITE JUNCTION BOX (18X11)	75.00	EA
626.13	4' X 6' SPLICE BOX WITH ACCESS DOOR	5.00	EA
626.21	METALLIC CONDUIT	310.00	LF
626.22	NON-METALLIC CONDUIT	35,500.00	LF
626.223	HORIZONTAL DIRECTIONAL DRILLED CONDUIT	530.00	LF
626.31	18 INCH DIAMETER FOUNDATION	33.00	EA
626.32	24 INCH DIAMETER FOUNDATION	94.00	EA
626.333	30 INCH DIAMETER FOUNDATION, 8 FEET OR LESS FOUNDATION	8.00	EA
626.36	REMOVE OR MODIFY CONCRETE FOUNDATION	66.00	EA
627.18	12 INCH SOLID WHITE PAVEMENT MARKING LINE	9,100.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
627.681	TEMPORARY 6 INCH PAINTED PAVEMENT MARKING LINE - YELLOW OR WHITE	97,400.00	LF
627.73	TEMPORARY 6 INCH PAVEMENT MARKING TAPE	7,050.00	LF
627.731	TEMPORARY 6 INCH BLACK PAVEMENT MARKING TAPE	7,050.00	LF
627.733	4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,520.00	LF
627.744	6" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	51,900.00	LF
627.75	WHITE OR YELLOW PAVEMENT & CURB MARKING	1,220.00	SF
627.77	REMOVING EXISTING PAVEMENT MARKING	37,650.00	SF
627.812	TEMPORARY RAISED PAVEMENT MARKERS	2,000.00	EA
627.94	PERMANENT PAVEMENT MARKING TAPE	335.00	LF
627.941	PAVEMENT MARKING TAPE – DOTTED WHITE LANE LINE, 6-INCH WIDTH	820.00	LF
627.944	PAVEMENT MARKING - RECESSED TAPE - WORDS, ARROWS AND STOP BARS	170.00	SF
629.05	HAND LABOR, STRAIGHT TIME	70.00	HR
631.1	AIR COMPRESSOR (INCLUDING OPERATOR)	70.00	HR
631.11	AIR TOOL (INCLUDING OPERATOR)	70.00	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	70.00	HR
631.14	GRADER (INCLUDING OPERATOR)	70.00	HR
631.171	TRUCK - SMALL (INCLUDING OPERATOR)	70.00	HR
631.18	CHAIN SAW RENTAL (INCLUDING OPERATOR)	30.00	HR
631.21	ROAD BROOM (INCLUDING OPERATORS AND HAULER)	10.00	HR
631.22	FRONT END LOADER (INCLUDING OPERATOR)	70.00	HR
631.32	CULVERT CLEANER (INCLUDING OPERATOR)	20.00	HR
631.36	FOREMAN	70.00	HR
631.5	JACKHAMMER (AIR TOOL INCLUDING OPERATOR)	60.00	HR
631.51	BUCKET TRUCK	60.00	HR
631.52	SCISSOR LIFT	60.00	HR
631.53	ELECTRICIAN	100.00	HR
631.54	ELECTRICIAN'S APPRENTICE	100.00	HR
631.55	PLUMBER	60.00	HR
632.01	OVER HEIGHT VEHICLE DETECTION SYSTEM: EXIT 103 AREA	1.00	LS
633.01	PROPANE SERVICE TRENCH	66.00	LF
633.21	PROPANE TANK SUPPORTS (12' X 4')	2.00	EA
633.31	PROPANE TANK PAD	27.00	SY
634.051	REMOVE AND STACK LIGHT STANDARD	9.00	EA
634.052	REMOVE HIGH MAST LIGHT STANDARD	2.00	EA
634.208	REMOVE AND RESET LIGHT STANDARD	1.00	EA
634.231	CONVENTIONAL LIGHT STANDARD WITH LED FIXTURE	81.00	EA
639.18	FIELD OFFICE, TYPE A	1.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
643.711	LANE USE SIGNAL INSTALLATION	6.00	EA
643.712	FLASHING BEACON - SOLAR POWERED	2.00	EA
645.105	REMOVE AND STACK SIGN	111.00	EA
645.107	REMOVE AND STACK CANOPY MOUNTED SIGN	10.00	EA
645.109	REMOVE AND RESET SIGN	7.00	EA
645.1092	CANOPY MOUNTED DYNAMIC MESSAGE SIGN	4.00	EA
645.121	OVERHEAD GUIDE SIGN NB 2 (STA. 7450+00)	1.00	LS
645.122	OVERHEAD GUIDE SIGN NB 3 (STA. 7463+00)	1.00	LS
645.123	OVERHEAD GUIDE SIGN NB 5 (STA. 7477+25)	1.00	LS
645.124	OVERHEAD GUIDE SIGN SB 1 (STA 4491+00)	1.00	LS
645.125	OVERHEAD GUIDE SIGN SB 2 (STA 4508+75)	1.00	LS
645.126	OVERHEAD GUIDE SIGN SB 3 (STA. 27+00)	1.00	LS
645.127	OVERHEAD GUIDE SIGN SB 4 (STA. 43+00)	1.00	LS
645.14	CANOPY MOUNTED SIGN	4.00	EA
645.151	CANTILEVER GUIDE SIGN NB 1 (STA. 7427+25)	1.00	LS
645.152	CANTILEVER GUIDE SIGN NB 4 (STA. 7471+75)	1.00	LS
645.155	VARIABLE SPEED LIMIT SIGN	2.00	EA
645.161	BREAKAWAY DEVICE SINGLE POLE	51.00	EA
645.162	BREAKAWAY DEVICE MULTI POLE	24.00	EA
645.251	ROADSIDE GUIDE SIGNS, TYPE I	1,065.00	SF
645.271	REGULATORY, WARNING, CONFIRMATION AND ROUTE ASSEMBLY SIGN, TYPE I	1,440.00	SF
645.289	STEEL H-BEAM POLES	24,020.00	LB
645.501	REMOVE AND RESET MAINLINE SIGN STA. 7401+23 (2 SIGNS)	1.00	LS
645.502	REMOVE AND RESET MAINLINE SIGN STA. 7440+50 (1 SIGN)	1.00	LS
645.503	REMOVE AND RESET MAINLINE SIGN STA. 7467+00 (1 SIGN)	1.00	LS
645.504	REMOVE AND RESET MAINLINE SIGN STA. 7470+29 (1 SIGN)	1.00	LS
645.505	REMOVE AND RESET MAINLINE SIGN STA. 3488+27 (1 SIGN)	1.00	LS
645.506	REMOVE AND RESET MAINLINE SIGN STA. 4474+00 (1 SIGN)	1.00	LS
645.507	REMOVE AND RESET MAINLINE SIGN STA. 789+50 (1 SIGN)	1.00	LS
645.508	REMOVE AND RESET MAINLINE SIGN STA. 8492+00 (1 SIGN)	1.00	LS
645.509	REMOVE AND RESET MAINLINE SIGN STA. 7515+00 (1 SIGN)	1.00	LS
645.601	REMOVE AND STACK OVERHEAD SIGN STRUCTURE (NB ORT)	1.00	LS
645.602	REMOVE AND STACK OVERHEAD SIGN STRUCTURE (SB CASH)	1.00	LS
648	INSTALL FLAGPOLE	1.00	EA
652.3	FLASHING ARROW	1.00	EA
652.312	TYPE III BARRICADES	21.00	EA
652.33	DRUM	200.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
652.34	CONE	50.00	EA
652.35	CONSTRUCTION SIGNS	4,100.00	SF
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS
652.38	FLAGGERS	100.00	HR
652.41	PORTABLE-CHANGEABLE MESSAGE SIGN	4.00	EA
652.45	TRUCK MOUNTED ATTENUATOR	540.00	CD
652.451	AUTOMATED TRAILER MOUNTED SPEED LIMIT SIGN	3.00	EA
652.46	TEMPORARY PORTABLE RUMBLE STRIP	50.00	UNIT
655.01	INSTALLATION OF ORT LANE CONTROLLER CABINET	2.00	EA
655.012	INSTALLATION OF CASH LANE CONTROLLER CABINET	6.00	EA
655.02	DVAS MOUNT INSTALLATION	10.00	EA
655.03	VCARS MOUNT INSTALLATION	16.00	EA
655.04	INSTALLATION OF SENSOR LOOPS	1.00	LS
655.05	INSTALLATION OF AVI ANTENNAS	20.00	EA
655.06	INSTALLATION OF AVI READERS	4.00	EA
655.07	TRAFFIC CONTROL PEDESTAL PREPARATION WORK	6.00	EA
655.08	OPUS MOUNT INSTALLATION	18.00	EA
655.09	ARMORED CABLE - 10/3	300.00	LF
655.1	#2/0 AWG WIRE	2,900.00	LF
655.1001	#1/0 AWG WIRE	1,600.00	LF
655.1004	#4/0 AWG WIRE	2,000.00	LF
655.101	#1 AWG WIRE	1,600.00	LF
655.102	#2 AWG WIRE	1,000.00	LF
655.104	#4 AWG WIRE	1,400.00	LF
655.106	#6 AWG WIRE	1,200.00	LF
655.108	#8 AWG WIRE	600.00	LF
655.11	#10 AWG WIRE	2,400.00	LF
655.12	#12 AWG WIRE	45,600.00	LF
655.14	4PR/24 (CATEGORY 5E) CABLE	31,200.00	LF
655.15	LMR 400 CABLE	2,040.00	LF
655.161	MULTIMODE FIBER OPTIC CABLE - 6 FIBER	2,000.00	LF
655.162	SINGLE MODE FIBER OPTIC CABLE - 6 FIBER	3,500.00	LF
655.17	IVIS HOMERUN LOOP CABLE (IMSA 50-2 #14)	7,140.00	LF
655.2	1 1/2" SCHEDULE 40 PVC CONDUIT	300.00	LF
655.2001	3/4" SCHEDULE 40 PVC CONDUIT	300.00	LF
655.2002	1" SCHEDULE 40 PVC CONDUIT	300.00	LF
655.2003	2" SCHEDULE 40 PVC CONDUIT	300.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
655.201	3" SCHEDULE 40 PVC CONDUIT	240.00	LF
655.202	4" SCHEDULE 40 PVC CONDUIT	360.00	LF
655.2021	1" SCHEDULE 80 PVC CONDUIT	420.00	LF
655.203	1 1/2" SCHEDULE 80 PVC CONDUIT	840.00	LF
655.2031	2" SCHEDULE 80 PVC CONDUIT	480.00	LF
655.204	3" SCHEDULE 80 PVC CONDUIT	2,550.00	LF
655.205	4" SCHEDULE 80 PVC CONDUIT	360.00	LF
655.2051	6" SCHEDULE 80 PVC CONDUIT	240.00	LF
655.2052	5" SCHEDULE 80 PVC CONDUIT	240.00	LF
655.206	1" GALVANIZED RIGID METAL CONDUIT	720.00	LF
655.2061	3/4" GALVANIZED RIGID METAL CONDUIT	720.00	LF
655.207	1 1/2" GALVANIZED RIGID METAL CONDUIT	420.00	LF
655.2071	2" GALVANIZED RIGID METAL CONDUIT	660.00	LF
655.208	3" GALVANIZED RIGID METAL CONDUIT	720.00	LF
655.209	1/2" LIQUID TIGHT METALLIC FLEXIBLE CONDUIT	480.00	LF
655.21	3/4" LIQUID TIGHT METALLIC FLEXIBLE CONDUIT	360.00	LF
655.2101	1 1/2" LIQUID TIGHT METALLIC FLEXIBLE CONDUIT	120.00	LF
655.2102	2" LIQUID TIGHT METALLIC FLEXIBLE CONDUIT	120.00	LF
655.211	1 1/2" ELECTRICAL METALLIC TUBING CONDUIT	120.00	LF
655.212	2" ELECTRICAL METALLIC TUBING CONDUIT	120.00	LF
655.213	3" ELECTRICAL METALLIC TUBING CONDUIT	120.00	LF
655.214	4" ELECTRICAL METALLIC TUBING CONDUIT	120.00	LF
655.215	3/4" ELECTRICAL METALLIC TUBING CONDUIT	120.00	LF
655.221	TYPE A PULL BOX INSIDE	20.00	EA
655.222	TYPE C PULL BOX IN TUNNEL/BOOTH PIT	24.00	EA
655.223	TYPE D PULL BOX OUTDOOR CANOPY	6.00	EA
655.224	TYPE E PULL BOX STEEL IN BOOTH	12.00	EA
655.225	TYPE F PULL BOX OUTSIDE	24.00	EA
655.3	12" X 12" X 6" GALVANIZED JUNCTION BOX	90.00	EA
655.31	18" X 18" X 6" GALVANIZED JUNCTION BOX	6.00	EA
655.4	18" X 24" X 12" JUNCTION BOX	8.00	EA
655.42	36" X 30" X 20" NEMA 4X CABINET	6.00	EA
655.431	60 AMP 3 PHASE PANELBOARD CABINET	8.00	EA
655.44	100 AMP 3 PHASE PANELBOARD CABINET	2.00	EA
655.45	150 AMP 3 PHASE PANELBOARD CABINET	2.00	EA
655.5	2" SCHEDULE 80 PVC CONDUIT CONDULETS	10.00	EA
655.51	4" SCHEDULE 80 PVC CONDUIT CONDULETS	10.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
655.511	3/4" RIGID METAL CONDUIT CONDULETS	10.00	EA
655.52	1" RIGID METAL CONDUIT CONDULETS	20.00	EA
655.53	1½" RIGID METAL CONDUIT CONDULETS	50.00	EA
655.54	2" RIGID METAL CONDUIT CONDULETS	50.00	EA
655.55	3" ELECTRICAL METAL TUBING CONDULETS	40.00	EA
655.56	2" ELECTRICAL METAL TUBING CONDULETS	40.00	EA
655.57	1½" ELECTRICAL METAL TUBING CONDULETS	40.00	EA
655.58	3/4" ELECTRICAL METAL TUBING CONDULETS	40.00	EA
655.59	1" ELECTRICAL METAL TUBING CONDULETS	40.00	EA
655.63	4-INCH X 4-INCH PVC NEMA 3R WIREWAY	540.00	LF
655.64	6-INCH X 6-INCH PVC NEMA 3R WIREWAY	500.00	LF
655.65	8-INCH X 8-INCH PVC NEMA 3R WIREWAY	300.00	LF
655.66	12-INCH X 12-INCH PVC NEMA 3R WIREWAY	300.00	LF
655.75	CONCRETE ENCASED CONDUIT	135.00	CY
655.8	LIGHTNING SUPPRESSION SYSTEM	1.00	LS
655.81	KEY SWITCH	10.00	EA
655.82	DUPLEX RECEPTACLE	20.00	EA
655.83	NEMA L5-20R RECEPTACLE	10.00	EA
655.84	QUADPLEX RECEPTACLE	10.00	EA
655.9	SPACE FRAME LIGHTING	1.00	LS
655.92	LED CANOPY LIGHT FIXTURE	12.00	EA
655.99	LED BUMPER BEACON	6.00	EA
656.41	GRAVEL WETLAND FILTER 1	1.00	LS
656.42	GRAVEL WETLAND FILTER 2	1.00	LS
656.5	BALED HAY, IN-PLACE	140.00	EA
656.6	TEMPORARY BERMS	3,000.00	LF
656.62	TEMPORARY SLOPE DRAINS	500.00	LF
656.632	30" TEMPORARY SILT FENCE	26,000.00	LF
659.1	MOBILIZATION	1.00	LS
670.01	SEWAGE DISPOSAL SYSTEM	1.00	LS
800.01	TOLL ADMINISTRATION BUILDING	1.00	LS
800.1	ELECTRICAL DEMOLITION	1.00	LS
800.2	MECHANICAL DEMOLITION	1.00	LS
800.22	HVAC AND ELECTRICAL TUNNEL AND BOOTHS	1.00	LS
800.3	TOLL PLAZA & BRIDGE DEMOLITION	1.00	LS
800.4	NEW TOLL BOOTH INSTALLATION	1.00	LS
800.41	STAIR ENCLOSURE & INSTALLATION	1.00	LS



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
800.9	GENERATOR PAD	1.00	LS
800.91	TRANSFORMER PAD	1.00	LS
803.01	TEST PITS	3.00	EA
832.41	TYPE A STEEL SITE BOLLARD	8.00	EA