

MAINE TURNPIKE AUTHORITY

ADDENDUM NO. 4

CONTRACT 2019.11

**NORTHERN BRIDGE REPAIRS, 6 LOCATIONS AND
EMERGENCY VEHICLE RAMPS AND
NEW GLOUCESTER TOLL PLAZA REHABILITATION
MILE 62.3 TO 95.6**

The following changes are made to the Proposal, Plans, and Specifications.

SPECIFICATIONS

Special Provision 506 Painting Structural Steel: sheet SP-45 is deleted and replaced with revised sheet SP-45 (Revised 3/20/19).

Special Provision 523 Bearings (Bearing Bolsters and Spacer Plates): sheet SP-60 is deleted and replaced with revised sheet SP-60 (Revised 3/20/19).

ATTACHMENTS

- Specifications (2 pages)

Notes: The above items shall be considered as part of the bid submittal.

The total number of pages included with this addendum is four (4).

All bidders are requested to acknowledge the receipt of the Addendum No. 4 by signing below and faxing this sheet to Nathaniel Carll, Purchasing Department, Maine Turnpike Authority at 207-871-7739. Bidders are also required to acknowledge receipt of this Addendum No. 4 on Page P-11 of the bid package.

Business Name

Print Name and Title

Signature

Date

March 20, 2019

Very truly yours,

MAINE TURNPIKE AUTHORITY

Nathaniel Carll
Purchasing Department
Maine Turnpike Authority

506.17 Handling and Storage

The coating shall be adequately cured before handling but under no circumstances shall the product be handled before the coating has achieved the manufacturer's published minimum cure time. Coated steel members shall be handled in a manner to avoid damage to the coating. Members shall be lifted and moved using non-metallic slings, padded chains and beam clamps, softeners or other non-injurious methods. Material shall be stored, both at the coating facility and in the field, in a manner that prevents damage to the coating.

506.18 through 506.19 Vacant

506.61 Basis of Payment

All work for Protective Coating shall be incidental to related contract items.

SPECIAL PROVISION

SECTION 523

BEARINGS

(Bearing Bolsters and Spacer Plates)

523.01 Description

The following paragraph is added:

This work shall also consist of furnishing and installing Steel Bolsters, Steel Spacer Plates, and all related fasteners and hardware. The specification requirements for Steel Rocker Bearings shall apply to this work.

523.50 Method of Measurement

The following paragraphs are added:

Bearing Bolsters and Spacer Plates, Fabricated and Delivered will be measured for payment by the Lump Sum which price shall include fabrication and delivery of all components and hardware required to satisfactorily complete the work.

Bearing Bolsters and Spacer Plates, Installed will be measured for payment by the Lump Sum which price shall include all equipment, labor and incidentals required to satisfactorily complete the work.

523.51 Basis of Payment

The following paragraphs are added:

The Lump Sum payment for Bearing Bolsters and Spacer Plates, Fabricated and Delivered shall be considered full compensation for all materials, equipment, labor and incidentals required to complete the fabrication and delivery work in accordance with the Plans and these Specifications.

The Lump Sum payment for Bearing Bolsters and Spacer Plates, Installed shall be considered full compensation for all materials, equipment, labor and incidentals required to remove the existing bearings, install the new bolsters, and reinstall the existing bearings, including, but not limited to, lead paint removal, field repair of existing paint, and repair of any incidental damage caused by Contractor activities to the satisfaction of the Resident, in accordance with the Plans and these Specifications.

Payment will be made under:

<u>Pay Item</u>		<u>Pay Unit</u>
523.522	Bearing Bolsters and Spacer Plates, Fabricated and Delivered	Lump Sum
523.524	Bearing Bolsters and Spacer Plates, Installed	Lump Sum