



Maine Turnpike Authority *Schedule of Items*

GRAY SERVICE PLAZA - FUEL SYSTEM REPLACEMENT MILE 58.8 NB

Item No.	Description	Quantity	UOM
202.17	Removing Existing Structural Concrete	1.00	LS
202.202	Removing Pavement Surface	80.00	SY
203.2	Common Excavation	660.00	CY
203.2312	Health and Safety Plan	1.00	LS
203.2333	Disposal/Treatment of Special Excavation	535.00	TON
203.2334	Disposal/Treatment of Contaminated Groundwater	300,000.00	GAL
206.061	Structural Earth Excavation - Drainage Minor Structures Below Grade	25.00	CY
304.1	Aggregate Subbase Course - Gravel	450.00	CY
304.14	Aggregate Base Course - Type A	90.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	220.00	Ton
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size	130.00	Ton
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate Base Course)	130.00	Ton
409.15	Bituminous Tack Coat, Applied	130.00	Gal
419.3	Sawing Bituminous Pavement	1,110.00	LF
502.701	Concrete Gas Island and Slab	74.00	CY
502.702	Concrete Diesel Island and Slab	37.00	CY
502.703	Concrete Fuel Tank Slab	39.00	CY
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	12,200.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	12,200.00	LB
524.3	Temporary Structural Support	1.00	EA
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority (500 LF)	1.00	LS
603.165	15 Inch Reinforced Concrete Pipe - Class III	60.00	LF
603.169	15 Inch Culvert Pipe Option III	300.00	LF
604.09	Catch Basin Type B1	1.00	EA
604.248	Catch Basin Type F6	1.00	EA
604.3	Oil-water Separator	1.00	EA
606.265	Terminal End - single rail- Galvanized steel	4.00	EA
606.356	Underdrain Delineator Post	3.00	EA
606.3605	Guardrail Remove and Reset	187.50	LF
607.18	6 Foot Chain Link Safety Fence	500.00	LF
609.31	Curb Type 3	120.00	LF
610.08	Plain Riprap	9.00	CY
613.319	Erosion Control Blanket	18.00	SY
615.07	Loam	80.00	CY
618.13	Seeding Method Number 1	5.00	Unit
619.1201	Mulch - Plan Quantity	5.00	Unit



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
619.1202	Temporary Mulch	1.00	LS
622.1	Transplanting Shrub	13.00	EA
626.13	18" X 12" X 18" Quazite Junction Box	1.00	EA
626.22	Non-Metallic Conduit	70.00	LF
626.32	24 Inch Diameter Foundation	2.00	EA
626.36	Remove or Modify Concrete Foundation	2.00	EA
627.73	Temporary 6 Inch Pavement Marking Tape	840.00	LF
627.731	Temporary 6 Inch Black Pavement Marking Tape	100.00	LF
627.733	4" White or Yellow Painted Pavement Marking Line	650.00	LF
629.05	Hand Labor, Straight Time	20.00	MH
631.12	All Purpose Excavator (including operator)	20.00	HR
631.172	Truck Large (including operator)	40.00	HR
631.221	Small Front End Loader (including operator)	20.00	HR
631.32	Culvert Cleaner (including operator)	12.00	HR
631.36	Foreman	20.00	HR
634.208	Remove and Reset Light Standards	2.00	EA
634.23	Temporary Lighting	1.00	LS
639.19	Field Office, Type B	1.00	EA
645.109	Remove and Reset Sign	1.00	EA
652.33	Drum	70.00	EA
652.34	Cones	25.00	EA
652.35	Construction Signs	140.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.41	Portable Changeable Message Sign	1.00	EA
655.101	#6 AWG Wire	180.00	LF
655.11	#10 AWG Wire	90.00	LF
656.5	Baled Hay, in place	12.00	EA
656.632	30 Inch Temporary Silt Fence	280.00	LF
659.1	Mobilization	1.00	LS
800.01	Removal of Underground Tanks (Gasoline and Diesel)	1.00	LS
800.02	Underground Tank Installation (Gasoline and Diesel)	1.00	LS
800.03	Aboveground Diesel Tank Installation	1.00	LS
800.04	Aboveground Gasoline Tank Installation	1.00	LS
800.5	New Canopy (Diesel)	1.00	LS