



Maine Turnpike Authority *Schedule of Items*

Parking Installation - Kennebunk Southbound Service Plaza MM 25.5 Paving Rehabilitation - Biddeford Interchange Mile 31.6 Bridge And Culvert Repairs - Crediford Brook Culvert MM 18.75, Route 111 Underpass MM 31.3, Biddeford Interchange Underpass MM 31.6

Item No.	Description	Quantity	UOM
201.23	Removing Single Tree Top Only	6.00	EA
201.24	Removing Stump	6.00	EA
202.12	Removing Existing Structural Concrete	10.00	CY
202.202	Removing Pavement Surface - Mainline	27,700.00	SY
202.2021	Removing Pavement Surface - Bridge Deck	2,950.00	SY
202.2026	Removing Pavement Surface - Drainage Paths	150.00	SY
203.2	Common Excavation	360.00	CY
304.1	Aggregate Subbase Course - Gravel	270.00	CY
304.14	Aggregate Base Course - Type A	36.00	CY
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size	162.00	TON
403.2081	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size, (Polymer Modified) - RAP	2,420.00	TON
403.2084	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Sidewalks, Drives, Islands & Incidentals)	25.00	TON
403.212	Hot Mix Asphalt, 4.75 mm Nominal Maximum Size	760.00	TON
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate Base Course)	195.00	TON
409.15	Bituminous Tack Coat - Applied	2,420.00	GAL
419.3	Sawing Bituminous Pavement	440.00	LF
424.323	Asphalt Rubber Fiber Crack Sealer	3,050.00	LB
470.08	Berm Dropoff Correction - Grindings	170.00	TON
502.21	Structural Concrete, Abutments and Retaining Walls	15.00	CY
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	3,600.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	3,600.00	LB
507.095	Aluminum Bridge Railing - Splice Modification	8.00	EA
514.06	Curing Box for Concrete Cylinders	2.00	EA
515.201	Pigmented Protective Coating for Concrete Surfaces	300.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	2,300.00	SY
518.39	Granite Curb Joint Mortar and Bedding Mortar Repair	180.00	LF
518.4	Epoxy Injection Crack Repair	170.00	LF
518.43	Parapet Joint Repair	1,070.00	LF
518.51	Repair of Upward Facing Surfaces - Below Reinforcing Steel < 8 inches	100.00	SF
518.511	Repair of Upward Facing Culvert Surfaces - Below Reinforcing Steel < 8 inches	160.00	SF
518.53	Culvert Floor Refacing	1,650.00	SF
518.6	Repair of Vertical Surfaces < 8 inches	260.00	SF
518.86	Bridge Joint Header Concrete Replacement	450.00	SF
520.2228	Metal Armor Repair	10.00	LF
520.2234	Joint Armor Modification	150.00	LF
520.23	Expansion Device - Asphaltic Plug Joint	97.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority	1.00	LS
527.342	Work Zone Crash Cushions - TL-2	2.00	UN
603.1753	18 Inch Reinforced Concrete Pipe - Class V	44.00	LF
603.28	Concrete Collar	1.00	EA
604.184	Rebuild Catch Basin to Grade - Type II	2.00	EA
606.1723	Bridge Transition - Type III	8.00	EA
606.178	Guardrail Beam	653.00	LF
606.278	Terminal End - Anchored End	1.00	EA
606.352	Reflectorized Beam Guardrail Delineator	290.00	EA
606.353	Delineator Post	88.00	EA
606.3562	Delineator Post - Remove and Stack	88.00	EA
606.3621	Guardrail Adjust, Single Rail	7,363.00	LF
606.3622	Guardrail Adjust, Double Rail	1,525.00	LF
606.369	Guardrail - Remove and Stack	150.00	LF
606.471	Single Offset Block - W-Beam	86.00	EA
606.48	Single Galvanized Steel Post	74.00	EA
607.24	Remove and Reset Fence	35.00	LF
609.15	Sloped Curb Type I	45.00	LF
609.238	Terminal Curb Type 1 - 8'	1.00	EA
609.441	Curbing Removed and Stacked	115.00	LF
615.07	Loam	20.00	CY
618.13	Seeding Method Number 1	2.00	UN
619.1201	Mulch - Plan Quantity	2.00	UN
619.1202	Temporary Mulch	1.00	LS
619.14	Erosion Control Mix	70.00	CY
626.12	36" x 24" x 36" Quazite Junction Box	3.00	EA
626.13	18" x 12" x 18" Quazite Junction Box	4.00	EA
626.22	Non-Metallic Conduit	240.00	LF
626.32	24" Diameter Concrete Foundation	1.00	EA
627.712	White or Yellow Pavement Marking Line	24,600.00	LF
627.77	Removing Existing Pavement Marking	520.00	SF
627.812	Temporary Raised Pavement Markers	1,170.00	EA
627.943	Pavement Marking Line - Recessed Tape, Solid White or Yellow Lane Line, 6 - inch width	1,300.00	LF
627.944	Pavement Markings - Recessed Tape, Words, Arrows, Stop Bars	490.00	SF
629.05	Hand Labor , Straight Time	70.00	HR
631.1	Air Compressor (including operator)	60.00	HR



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
631.11	Air Tool (including operator)	60.00	HR
631.12	All Purpose Excavator (including operator)	40.00	HR
631.172	Truck - large (including operator)	30.00	HR
631.36	Foreman	30.00	HR
631.4	Welder (including operator)	40.00	HR
631.53	Electrician	40.00	HR
631.54	Electrician's Apprentice	40.00	HR
634.208	Remove and Reset Light Standard	1.00	EA
643.901	Interconnect Wire IMSA 50-2 #14 AWG	480.00	LF
645.106	Demount Regulatory, Warning, Confirmation, and Route Marker Assembly Sign	3.00	EA
645.116	Reinstall Regulatory, Warning, Confirmation and Route Marker Assembly Sign	3.00	EA
652.3611	Traffic Control Devices and Maintenance of Traffic Control Devices: Crediford Brook	1.00	LS
652.3612	Traffic Control Devices and Maintenance of Traffic Control Devices: Kennebunk Service Plaza	1.00	LS
652.3613	Traffic Control Devices and Maintenance of Traffic Control Devices: Route 111	1.00	LS
652.3614	Traffic Control Devices and Maintenance of Traffic Control Devices: Biddeford	1.00	LS
652.38	Flagger	40.00	HR
652.41	Portable-Changeable Message Sign	5.00	EA
652.411	Portable-Changeable Message Sign	60.00	CD
652.45	Truck Mounted Attenuator	10.00	CD
652.451	Automated Trailer Mounted Speed Limit Sign	20.00	CD
655.101	#6 AWG Wire	1,000.00	LF
655.11	#10 AWG Wire	250.00	LF
655.204	3" Schedule 80 PVC Conduit	700.00	LF
656.5	Baled Hay, in place	42.00	EA
656.632	30 inch Temporary Silt Fence	1,200.00	LF
659.1	Mobilization	1.00	LS