



Maine Turnpike Authority *Schedule of Items*

Exit 103 I-295 Southbound Underpass Bridge Rehabilitation Mile 103.0

Item No.	Description	Quantity	UOM
202.1	REMOVE EXISTING SUPERSTRUCTURE PROPERTY OF CONTRACTOR	1.00	LS
202.12	REMOVING EXISTING STRUCTURAL CONCRETE	190.00	CY
202.202	REMOVING PAVEMENT SURFACE	22,200.00	SY
202.2026	REMOVING PAVEMENT SURFACE - DRAINAGE PATHS	680.00	SF
202.206	REMOVING RUMBLE STRIPS	7,000.00	LF
203.2	COMMON EXCAVATION	5,222.00	CY
203.21	ROCK EXCAVATION	58.00	CY
203.24	COMMON BORROW	8,600.00	CY
203.25	GRANULAR BORROW	3,950.00	CY
203.26	GRAVEL BORROW	720.00	CY
206.082	STRUCTURAL EARTH EXCAVATION-MAJOR STRUCTURES	520.00	CY
304.1	AGGREGATE SUBBASE COURSE - GRAVEL	1,200.00	CY
304.14	AGGREGATE BASE COURSE - TYPE A	1,300.00	CY
403.207	HOT MIX ASPHALT-19 MM	1,850.00	TON
403.2081	HOT MIX ASPHALT, 12.5 MM (POLYMER MODIFIED)	2,595.00	TON
403.209	HOT MIX ASPHALT -9.5 MM MAXIMUM SIZE (SIDEWALKS, DRIVES, & INCIDENTALS)	55.00	TON
403.211	HOT MIX ASPHALT - SHIM	1,770.00	TON
403.213	HOT MIX ASPHALT - 12.5 MM (BASE AND INTERMEDIATE COURSE)	970.00	TON
409.15	BITUMINOUS TACK COAT, APPLIED	2,080.00	GAL
419.3	SAWING BITUMINOUS PAVEMENT	4,465.00	LF
470.08	BERM DROP OFF CORRECTION - GRINDINGS	70.00	TON
470.081	BERM CORRECTION	4,800.00	LF
502.219	STRUCTURAL CONCRETE ABUTMENTS & RETAINING WALLS (360 CY)	1.00	LS
502.239	STRUCTURAL CONCRETE PIERS (97 CY)	1.00	LS
502.26	STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON STEEL BRIDGES (640 CY)	1.00	LS
502.264	STRUCTURAL CONCRETE PARAPETS (97 CY)	1.00	LS
502.31	STRUCTURAL CONCRETE APPROACH SLAB (83 CY)	1.00	LS
503.14	EPOXY-COATED REINFORCING STEEL, FABRICATED & DELIVERED	296,000.00	LB
503.15	EPOXY-COATED REINFORCING STEEL, PLACING	296,000.00	LB
503.17	MECHANICAL/WELDED SPLICE	1,426.00	EA
504.701	STRUCTURAL STEEL FABRICATED & DELIVERED, ROLLED (30150 LB)	1.00	LS
504.702	STRUCTURAL STEEL FABRICATED & DELIVERED, WELDED (184650 LB)	1.00	LS
504.71	STRUCTURAL STEEL ERECTION (214800 LB)	1.00	LS
505.08	SHEAR CONNECTORS (12714 EA)	1.00	LS
507.0849	BARRIER - MOUNTED ALUMINUM BRIDGE RAIL, 1 BAR	870.00	LF
508.14	HIGH PERFORMANCE WATERPROOFING MEMBRANE (2600 SY)	1.00	LS



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
511.091	TEMPORARY EARTH SUPPORT SYSTEMS	1.00	LS
512.081	FRENCH DRAINS (127 LF)	1.00	LS
513.09	SLOPE PROTECTION - PORTLAND CEMENT CONCRETE	669.00	SY
514.06	CURING BOX FOR CONCRETE CYLINDERS	1.00	EA
515.201	PIGMENTED PROTECTIVE COATING FOR CONCRETE SURFACES	870.00	SY
515.202	CLEAR PROTECTIVE COATING FOR CONCRETE SURFACES	1,350.00	SY
518.1	ABUTMENT REPAIRS	115.00	SF
518.2	PIER REPAIRS	600.00	SF
518.4	EPOXY INJECTION CRACK REPAIR	27.00	LF
521.23	EXPANSION DEVICE-FINGER JOINT	2.00	EA
523.33	REMOVE AND RESET BEARINGS	30.00	EA
523.52	BEARING INSTALLATION	10.00	EA
523.5405	SEISMIC ISOLATION BEARINGS - FABRICATED & DELIVERED	10.00	EA
524.301	TEMPORARY JACKING AND STRUCTURAL SUPPORT	1.00	LS
524.303	TEMPORARY DECK SUPPORT	1.00	LS
524.4	PROTECTIVE SHIELDING - STEEL GIRDERS	2,400.00	SY
526.304	TEMPORARY CONCRETE BARRIER, ANCHORED	1.00	LS
526.306	TEMPORARY CONCRETE BARRIER TYPE 1 - SUPPLIED BY AUTHORITY (5,000 LF)	1.00	LS
526.35	PIER PROTECTION CONCRETE BARRIER	600.00	LF
527.343	WORK ZONE CRASH CUSHIONS - TL-3	3.00	UNIT
603.225	42 INCH REINFORCED CONCRETE PIPE - CLASS III	8.00	LF
603.55	CONCRETE PIPE TIES	2.00	GP
606.13	31" W-BEAM GUARDRAIL - MID-WAY SPLICE (7' STEEL POSTS, 8" OFFSET BLOCKS, SINGLE FACED)	2,625.00	LF
606.132	31" W-BEAM GUARDRAIL - MID-WAY SPLICE (7' STEEL POSTS, 8" OFFSET BLOCKS, DOUBLE FACED)	88.00	LF
606.1351	TERMINAL END - ANCHORED END - 31" W-BEAM GUARDRAIL	2.00	EA
606.1723	BRIDGE TRANSITION - TYPE III	6.00	EA
606.1724	BRIDGE TRANSITION - TYPE III - MODIFIED	2.00	EA
606.352	REFLECTORIZED BEAM GUARDRAIL DELINEATOR	70.00	EA
606.356	UNDERDRAIN DELINEATOR POST	5.00	EA
606.3561	DELINEATOR POST - REMOVE AND RESET	14.00	EA
606.791	GUARDRAIL - FLARED TERMINAL - 31" W-BEAM	2.00	EA
606.82	GUARDRAIL - REMOVE AND STACK EXISTING CRASH END	2.00	EA
609.15	SLOPED CURB TYPE 1	820.00	LF
609.191	CONCRETE CURB TYPE 2	96.00	LF
610.08	PLAIN RIPRAP	15.00	CY
610.18	STONE DITCH PROTECTION	6.00	CY



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
610.181	TEMPORARY STONE CHECK DAM	50.00	CY
613.319	EROSION CONTROL BLANKET	6,500.00	SY
615.07	LOAM	1,150.00	CY
618.14	SEEDING METHOD NUMBER 2	27.00	UNIT
618.141	SEEDING METHOD NUMBER 3	62.00	UNIT
619.1201	MULCH - PLAN QUANTITY	89.00	UNIT
619.1202	TEMPORARY MULCH	1.00	LS
620.58	EROSION CONTROL GEOTEXTILE	36.00	SY
620.6012	HDPE GEOMEMBRANE	52.00	SY
627.681	TEMPORARY 6 INCH PAINTED PAVEMENT MARKING LINE - YELLOW OR WHITE	47,500.00	LF
627.73	TEMPORARY 6 INCH PAVEMENT MARKING TAPE	3,000.00	LF
627.744	6" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	26,800.00	LF
627.77	REMOVING EXISTING PAVEMENT MARKING	30,000.00	SF
627.812	TEMPORARY RAISED PAVEMENT MARKERS	1,850.00	EA
627.94	PAVEMENT MARKING TAPE	200.00	LF
629.05	HAND LABOR, STRAIGHT TIME	200.00	HR
631.1	AIR COMPRESSOR (INCLUDING OPERATOR)	40.00	HR
631.11	AIR TOOL (INCLUDING OPERATOR)	80.00	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	100.00	HR
631.171	TRUCK-SMALL (INCLUDING OPERATOR)	60.00	HR
631.172	TRUCK - LARGE (INCLUDING OPERATOR)	80.00	HR
631.36	FOREMAN	100.00	HR
639.18	FIELD OFFICE, TYPE A	1.00	EA
645.105	REMOVE AND STACK SIGN	4.00	EA
645.109	REMOVE AND RESET SIGN	2.00	EA
645.271	REGULATORY, WARNING, CONFIRMATION AND ROUTE ASSEMBLY SIGN, TYPE 1	40.00	SF
652.3	FLASHING ARROW	5.00	EA
652.33	DRUM	300.00	EA
652.34	CONE	100.00	EA
652.35	CONSTRUCTION SIGNS	1,710.00	SF
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS
652.41	PORTABLE-CHANGEABLE MESSAGE SIGN	4.00	EA
652.45	TRUCK MOUNTED ATTENUATOR	100.00	CD
652.452	AUTOMATED TRAILER MOUNTED SPEED LIMIT SIGN	1.00	EA
652.46	TEMPORARY PORTABLE RUMBLE STRIP	100.00	UNIT
656.6	TEMPORARY BERMS	1,900.00	LF
656.62	TEMPORARY SLOPE DRAINS	400.00	LF



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
656.632	30" TEMPORARY SILT FENCE	4,600.00	LF
659.1	MOBILIZATION	1.00	LS