



Maine Turnpike Authority *Schedule of Items*

Pavement Rehabilitation, Guardrail & Clear Zone Improvements MM 35.3 TO MM 42

Item No.	Description	Quantity	UOM
202.202	REMOVING PAVEMENT SURFACE	328,600.00	SY
202.2026	REMOVING PAVEMENT SURFACE - DRAINAGE PATHS	12,500.00	SF
202.205	RUMBLE STRIPS	68,860.00	EA
203.2	COMMON EXCAVATION	325.00	CY
211.5	MEDIAN RESTORATION	31,600.00	LF
304.14	AGGREGATE BASE COURSE GRAVEL - TYPE A	160.00	CY
403.2081	HOT MIX ASPHALT - 12.5 MM (POLYMER MODIFIED)	31,750.00	T
403.211	HOT MIX ASPHALT (SHIMMING)	300.00	T
403.213	HOT MIX ASPHALT - 12.5 MM BASE	175.00	T
409.152	BITUMINOUS TACK COAT TRACKLESS, APPLIED	19,850.00	G
419.3	SAWING BITUMINOUS PAVEMENT	525.00	LF
424.323	ASPHALT RUBBER MASTIC CRACK SEALER	45,400.00	LB
470.08	BERM DROP OFF CORRECTION - GRINDINGS	125.00	T
470.081	BERM CORRECTION	18,600.00	LF
604.182	CLEAN EXISTING CATCH BASIN AND MANHOLE	30.00	EA
606.1351	TERMINAL END - ANCHORED END	8.00	EA
606.178	GUARDRAIL BEAM	325.00	LF
606.352	REFLECTORIZED BEAM GUARDRAIL DELINEATORS	500.00	EA
606.353	DELINEATOR POST	5.00	EA
606.3621	GUARDRAIL ADJUST, SINGLE RAIL	19,500.00	LF
606.3622	GUARDRAIL ADJUST, DOUBLE RAIL	35,150.00	LF
606.471	SINGLE OFFSET BLOCK - W-BEAM	55.00	EA
606.48	SINGLE GALVANIZED STEEL POST	5.00	EA
610.08	PLAIN RIPRAP	40.00	CY
613.319	EROSION CONTROL BLANKET	31,000.00	SY
618.14	SEEDING METHOD NUMBER 2	650.00	UN
619.12	MULCH	650.00	UN
620.58	EROSION CONTROL GEOTEXTILE	110.00	SY
627.73	TEMPORARY PAVEMENT MARKING TAPE	10,450.00	LF
627.78	TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	279,500.00	LF
627.812	TEMPORARY RAISED PAVEMENT MARKERS	13,950.00	EA
627.94	PAVEMENT MARKING TAPE	5,220.00	LF
629.05	HAND LABOR, STRAIGHT TIME	40.00	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	25.00	HR
631.133	SKID STEER (INCLUDING OPERATOR)	20.00	HR
631.172	TRUCK - LARGE (INCLUDING OPERATOR)	25.00	HR
631.32	CULVERT CLEANER (INCLUDING OPERATOR)	10.00	HR



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
631.36	FOREMAN	25.00	HR
652.3	FLASHING ARROW BOARD	8.00	EA
652.331	DRUM	1.00	LS
652.35	CONSTRUCTION SIGNS	3,210.00	SF
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS
652.41	PORTABLE - CHANGEABLE MESSAGE SIGN	4.00	EA
652.45	TRUCK MOUNTED ATTENUATOR	134.00	CD
652.452	AUTOMATED TRAILER MOUNTED SPEED LIMIT SIGN	2.00	EA
656.5	BALED HAY, IN PLACE	240.00	EA
659.1	MOBILIZATION	1.00	LS