



Maine Turnpike Authority *Schedule of Items*

EVR - Littlefield Road - MM 17.30

Pavement Improvements - Littlefield Road Underpass - MM 17.30

Item No.	Description	Quantity	UOM
201.11	Clearing	0.55	AC
201.23	Removing Single Tree Top Only	2.00	EA
201.24	Removing Stump	2.00	EA
202.202	Removing Pavement Surface	860.00	SY
203.2	Common Excavation	2,220.00	CY
203.24	Common Borrow	100.00	CY
203.25	Granular Borrow	155.00	CY
304.1	Aggregate Subbase Course-Gravel	1,090.00	CY
304.14	Aggregate Base Course - Type A	340.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size (Base)	340.00	TON
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Surface)	280.00	TON
409.15	Bituminous Tack Coat RS-1 or RS1h - Applied	135.00	GAL
411.1	Untreated Aggregate Surface Course	55.00	CY
419.3	Sawing Bituminous Pavement	360.00	LF
526.301	Temporary Concrete Barrier, Type 1	1.00	LS
527.341	Work Zone Crash Cushion - TL-3	2.00	UNIT
603.179	18 inch Culvert Pipe Option III	120.00	LF
606.242	Guardrail Type 3d - Over 15 foot Radius	25.00	LF
606.265	Terminal End-Single Rail - Galvanized Steel	1.00	EA
606.278	Terminal End - Anchored End	1.00	EA
606.353	Reflectorized Flexible Guardrail Marker	2.00	EA
606.3561	Delineator Post - Remove and Stack	1.00	EA
606.369	Guardrail - Remove and Stack	25.00	LF
607.17	Chain Link Fence - 6 foot	40.00	LF
607.2325	Remove Chain Link Gate	1.00	EA
607.32	Bracing Assembly Type I - Metal Posts	4.00	EA
607.33	Bracing Assembly Type II - Metal Posts	2.00	EA
610.08	Plain Riprap	15.00	CY
610.181	Temporary Stone Check Dam	14.00	CY
613.319	Erosion Control Blanket	770.00	SY
615.07	Loam	430.00	CY
618.14	Seeding Method Number 2	36.00	UNIT
619.1201	Mulch - Plan Quantity	36.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	57.00	SY
627.712	White or Yellow Pavement Marking Line	750.00	LF
629.05	Hand Labor, Straight Time	30.00	HR



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
631.1	Air Compressor (including operator)	20.00	HR
631.11	Air Tool (including operator)	20.00	HR
631.12	All Purpose Excavator (including operator)	30.00	HR
631.14	Grader (including operator)	30.00	HR
631.171	Truck - small (including operator)	30.00	HR
631.36	Foreman	30.00	HR
645.109	Remove and Reset Sign	3.00	EA
645.11	Remove and Dispose Sign	1.00	EA
645.271	Regulatory, Warning, Confirmation and Route Assembly Sign, Type 1	33.00	SF
652.3	Flashing Arrow	2.00	EA
652.33	Drum	90.00	EA
652.34	Cone	50.00	EA
652.35	Construction Signs	1,140.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	100.00	HR
652.45	Truck Mounted Attenuator	10.00	CD
652.47	Sequential Flashing Warning Lights	60.00	EA
656.5	Baled Hay, in place	30.00	EA
656.632	30 inch Temporary Silt Fence	1,620.00	LF
659.1	Mobilization	1.00	LS
827.37	Electrical Conduit Trenching	305.00	LF
832.41	Type A Steel Bollard	6.00	EA