



Maine Turnpike Authority *Schedule of Items*

Bridge Repair - Androscoggin River Overpass Mile 78.9

Item No.	Description	Quantity	UOM
202.12	Removing Existing Structural Concrete	49.00	CY
202.202	Removing Pavement Surface - Mainline	11,700.00	SY
202.205	Rumble Strips - Shoulder	9,000.00	LF
202.206	Removing Rumble Strips	5,650.00	LF
203.2	Common Excavation	350.00	CY
304.1	Aggregate Subbase Course - Gravel	80.00	CY
304.14	Aggregate Base Course - Type A	150.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	190.00	Ton
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size	1,050.00	Ton
403.2101	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size (Polymer Modified)	490.00	Ton
403.211	Hot Mix Asphalt (Shim)	30.00	Ton
409.15	Bituminous Tack Coat, Applied	570.00	Gal
502.219	Structural Concrete, Abutments and Retaining Walls (18 CY)	1.00	LS
502.261	Structural Concrete Roadway and Sidewalk Slab on Steel Bridges (16 CY)	1.00	LS
502.264	Structural Concrete Repairs, Parapet (15 CY)	1.00	LS
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	12,000.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	12,000.00	LB
504.885	Post-Tensioning Sleeve Replacement	7.00	EA
504.886	Post-Tensioning Sleeve Repair	37.00	EA
507.095	Aluminum Bridge Railing Post Replacement	2.00	EA
507.811	Aluminum Bridge Rail, 1 Bar - Repair	152.00	LF
508.14	High Performance Waterproofing Membrane (34 SY)	1.00	LS
508.15	Membrane Waterproofing (58 SY)	1.00	LS
514.06	Curing Box for Concrete Cylinders	1.00	EA
515.202	Clear Protective Coating for Concrete Surfaces	2,650.00	SY
518.39	Granite Curb Joint Mortar Repair	430.00	LF
518.4	Epoxy Injection Crack Repair	100.00	LF
518.43	Parapet Joint Repair	1,300.00	LF
518.51	Repair of Upward Facing Surfaces - below Reinforcing Steel < 8 inches	60.00	SF
518.6	Repair of Vertical Surface < 8 inches	60.00	SF
518.611	Full Depth Concrete Repairs - Parapets	19.00	CY
522.06	Modular Expansion Devices	4.00	EA
524.45	Protective Shielding - Median (27 Panels)	1.00	LS
524.46	Protective Shielding - Outside (30 Panels)	1.00	LS
526.306	Temporary Concrete Barrier, Type 1 - Supplied by Authority (5,750 LF)	1.00	LS
527.341	Work Zone Crash Cushions, TL-3	2.00	UN
603.1515	Slotted Drain	1,400.00	LF



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
603.155	12 Inch RCP Class III	12.00	LF
604.18	Adjusting Manhole or Catch Basin to Grade	9.00	EA
604.248	Catch Basin Type F6	1.00	EA
604.4	Secure Catch Basin Grate	10.00	EA
606.1723	Bridge Transition - Type III	2.00	EA
606.1724	Bridge Transition - Type III Modified	2.00	EA
606.24	Guardrail Type 3d - Single Rail	50.00	LF
606.3561	Delineator Posts - Remove and Reset	4.00	EA
606.64	Guardrail Thrie Beam - Double Rail	1,850.00	LF
606.701	Asymmetrical Thrie Beam Transition	4.00	EA
627.712	White or Yellow Pavement Marking Lines	8,900.00	LF
627.73	Temporary 6" Pavement Marking Tape, White or Yellow	59,700.00	LF
627.731	Temporary 6" Black Pavement Marking Tape	29,500.00	LF
629.05	Hand Labor, Straight Time	20.00	HR
631.1	Air Compressor (including operator)	10.00	HR
631.11	Air Tool (including operator)	10.00	HR
631.12	All Purpose Excavator (including operator)	10.00	HR
631.172	Truck - large (including operator)	20.00	HR
631.36	Foreman	10.00	HR
639.18	Field Office, Type A	1.00	EA
644.1	Glare Screen	1,950.00	LF
652.3	Flashing Arrow	2.00	EA
652.33	Drum	160.00	EA
652.34	Cone	50.00	EA
652.35	Construction Signs	680.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.41	Portable-Changeable Message Sign	2.00	EA
659.1	Mobilization	1.00	LS