



Maine Turnpike Authority *Schedule of Items*

Pavement Rehabilitation and Drainage Improvements MM 88.6 TO MM 98.0

Item No.	Description	Quantity	UOM
202.202	Removing Pavement Surface - Mainline	342,000.00	SY
202.2026	Removing Pavement Surface - Drainage Paths	2,500.00	SF
202.2031	Pavement Butt Joints - 103 ORT	4,880.00	LF
202.205	Rumble Strips	135,000.00	EA
203.2	Common Excavation	550.00	CY
203.25	Granular Borrow	350.00	CY
304.1	Aggregate Subbase Course - Gravel	105.00	CY
304.14	Aggregate Base Course - Type A	45.00	CY
403.2081	Hot Mix Asphalt, 12.5mm (Polymer Modified)- RAP	34,000.00	Ton
403.2084	Hot Mix Asphalt, 12.5mm Nominal Maximum Size(sidewalks, drives, islands & incidentals)	150.00	Ton
403.209	Hot Mix Asphalt 9.5mm Nominal Maximum Size(sidewalks, drives, islands & incidentals)	175.00	Ton
403.211	Hot Mix Asphalt 9.5mm (shimming)	200.00	Ton
409.152	Bituminous Tack Coat Trackless - Applied	22,600.00	GAL
419.3	Full Depth Bituminous Sawcut	1,900.00	LF
424.323	Asphalt Rubber Mastic Crack Sealant	49,000.00	LB
459.061	Bituminous Concrete Waterway - Type II	5.00	EA
470.08	Berm Dropoff Correction - Grindings	3,120.00	Ton
470.081	Berm Correction	50,000.00	LF
603.179	18 inch Culvert Pipe - Option III	78.00	LF
603.199	24 inch Culvert Pipe - Option III	171.00	LF
603.209	30 inch Culvert Pipe - Option III	120.00	LF
603.219	36 inch Culvert Pipe - Option III	36.00	LF
603.28	Concrete Collar	19.00	EA
604.184	Rebuild Catch Basin to Grade - Type II	22.00	EA
604.186	Rebuild Catch Basin to Grade - Type IV	5.00	EA
606.132	31" W-Beam Guardrail - Mid-Way Splice (7' Steel Posts, 8" Offset Blocks, Double Faced)	2,005.00	LF
610.08	Plain Rip Rap	225.00	CY
610.18	Stone Ditch Protection	150.00	CY
613.319	Erosion Control Blanket	2,000.00	SY
615.07	Loam	245.00	CY
618.1401	Seeding Method Number 2, Plan Quantity	15.00	UNIT
619.1201	Mulch, Plan Quantity	15.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	900.00	SY
627.73	Temporary Pavement Marking Line Tape	7,300.00	LF



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
627.78	Temporary Pavement Marking Line	291,200.00	LF
627.812	Temporary Raised Pavement Markers	19,410.00	EA
627.94	Pavement Marking Tape	3,650.00	LF
629.05	Hand Labor, Straight Time	30.00	HR
631.1	Air Compressor (including operator)	10.00	HR
631.11	Air Tool (including operator)	10.00	HR
631.12	All Purpose Excavator (including operator)	20.00	HR
631.172	Truck - Large (including operator)	40.00	HR
631.18	Chain Saw Rental (including operator)	20.00	HR
631.36	Foreman	20.00	HR
652.3	Flashing Arrow	4.00	EA
652.35	Construction Signs	4,134.00	SF
652.3611	Maintenance of Traffic Control Devices	1.00	LS
652.411	Portable - Changeable Message Sign	2.00	EA
652.45	Truck Mounted Attenuator	175.00	CD
652.452	Automated Trailer Mounted Speed Limit Sign	4.00	EA
656.5	Baled Hay, in place	50.00	EA
656.632	30 inch Temporary Silt Fence	400.00	LF
659.1	Mobilization	1.00	LS