



Maine Turnpike Authority *Schedule of Items*

Portland Area Widening & Safety Improvements MM 43.0 to 46.4

Item No.	Description	Quantity	UOM
201.11	Clearing	6.10	AC
201.23	Removing Single Tree Top Only	7.00	EA
201.24	Removing Stump	7.00	EA
202.12	Removing Existing Structural Concrete	14.00	CY
202.15	Removing Existing Manhole or Catch Basin	51.00	EA
202.202	Removing Pavement Surface	9,950.00	SY
202.206	Removing Rumble Strips	8,600.00	LF
203.2	Common Excavation	148,700.00	CY
203.21	Rock Excavation	13,370.00	CY
203.211	Presplitting Rock	4,440.00	LF
203.25	Granular Borrow	37,400.00	CY
203.33	Special Fill	54.00	CY
203.34	Lightweight Fill	290.00	CY
203.52	Low Permeability Fill	960.00	CY
304.1	Aggregate Subbase Course - Gravel	29,100.00	CY
304.14	Aggregate Base Course - Type A	19,950.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	18,050.00	TON
403.2072	19.0mm Asphalt Rich Base HMA	19,650.00	TON
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate Base Course)	4,080.00	TON
403.2081	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Polymer Modified)	7,900.00	TON
409.15	Bituminous Tack Coat RS1 or RS1h - Applied	11,850.00	GAL
419.3	Sawing Bituminous Pavement	59,925.00	LF
470.08	Berm Dropoff Correction - Grindings	650.00	TON
501.231	Dynamic Loading Test	2.00	EA
501.5	Steel H-beam Piles 89 lb/ft, delivered	1,760.00	LF
501.501	Steel H-beam Piles 89 lb/ft, in place	1,760.00	LF
501.9	Pile Tips	16.00	EA
501.91	Pile Splices	16.00	EA
501.92	Pile Driving Equipment and Mobilization	1.00	LS
509.202	Culvert Sliplining	1.00	LS
511.071	Cofferdam - Red Brook NB	1.00	LS
511.072	Cofferdam - Red Brook SB	1.00	LS
511.073	Cofferdam - Long Creek NB	1.00	LS
511.074	Cofferdam - Long Creek SB	1.00	LS
511.091	Temporary Earth Support System	1.00	LS
513.09	Slope Protection - Portland Cement Concrete	552.00	SY



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
514.06	Curing Box for Concrete Cylinders	1.00	EA
515.201	Pigmented Protective Coating for Concrete Surfaces	20.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	110.00	SY
518.6	Repair of Vertical Surfaces < 8 inches	150.00	SF
526.301	Temporary Concrete Barrier, Type I	31,600.00	LF
526.306	Temporary Concrete Barrier, Type 1 - Supplied by MTA (7,000 LF)	1.00	LS
526.307	Concrete Barrier Type 1 - Stormwater Filter	120.00	LF
526.351	Median Barrier - Type A (11,250 LF)	1.00	LS
526.352	Median Barrier - Type B (3,575 LF)	1.00	LS
526.353	Median Barrier - Type C (280 LF)	1.00	LS
526.354	Median Barrier - Type D (1,550 LF)	1.00	LS
526.355	Earth Retaining Barrier (882.5 LF)	1.00	LS
526.362	Type C Transition Barrier	2.00	EA
526.363	Type D Transition Barrier	12.00	EA
526.364	OHSS Foundation Transition Barrier	6.00	EA
526.365	Median Guardrail Transition Barrier	1.00	EA
526.366	Guardrail Transition Barrier	6.00	EA
527.341	Work Zone Crash Cushions - TL-3	17.00	UNIT
527.3411	Work Zone Crash Cushions - TL-3 - Left In Place	3.00	UNIT
602.3	Flowable Concrete Fill	50.00	CY
603.155	12 inch Reinforced Concrete Pipe - Class III	930.00	LF
603.159	12 Inch Culvert Pipe Option III	460.00	LF
603.165	15 inch Reinforced Concrete Pipe - Class III	175.00	LF
603.175	18 inch Reinforced Concrete Pipe - Class III	1,744.00	LF
603.195	24 inch Reinforced Concrete Pipe - Class III	440.00	LF
603.205	30 inch Reinforced Concrete Pipe - Class III	210.00	LF
603.215	36 inch Reinforced Concrete Pipe - Class III	75.00	LF
603.225	42 inch Reinforced Concrete Pipe - Class III	56.00	LF
603.28	Concrete Collar	11.00	EA
603.5	78 inch Reinforced Concrete Pipe - Class IV	8.00	LF
604.09	Catch Basin Type B1	22.38	EA
604.096	60" Catch Basin Type B1-C	1.00	EA
604.18	Adjusting Manhole or Catch Basin to Grade	4.00	EA
604.182	Cleaning Existing Catch Basin and Manhole	9.00	EA
604.248	Catch Basin Type F6	118.00	EA
604.26	Catch Basin Type B5	42.00	EA
604.4	Secure Catch Basin Grate	9.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
605.016	6 Inch PVC Underdrain	3,700.00	LF
605.018	8 Inch PVC Underdrain	550.00	LF
605.09	6 Inch Underdrain Type B	5,800.00	LF
605.11	12 Inch Underdrain Type C	5,300.00	LF
605.12	15 Inch Underdrain Type C	2,900.00	LF
605.13	18 Inch Underdrain Type C	1,537.00	LF
605.15	24 Inch Underdrain Type C	80.00	LF
606.1301	31" W Beam Guardrail - Mid-way Splice (7' Steel Post, 8" Offset Blocks, Single Faced)	2,850.00	LF
606.1307	31" W-Beam Guardrail - Mid-way Splice Flared Terminal	8.00	EA
606.132	31" W Beam Guardrail - Mid-way Splice (7' Steel Post, 8" Offset Blocks, Double Faced)	340.00	LF
606.1351	31" W-Beam Guardrail - Mid-way Splice Terminal End - Anchored End	5.00	EA
606.1723	Bridge Transition - Type III	5.00	EA
606.1724	Bridge Transition - Type III, Modified	2.00	EA
606.353	Reflectorized Flexible Guardrail Marker	16.00	EA
606.356	Underdrain Delineator Post	127.00	EA
606.3561	Delineator Post-Remove and Reset	202.00	EA
606.3605	Guardrail - Remove, Modify and Reset Single Rail	100.00	LF
606.3631	Guardrail - Remove and Dispose	20,250.00	LF
607.17	Chain Link Fence - 6 foot	820.00	LF
610.08	Plain Riprap	612.00	CY
610.18	Stone Ditch Protection	530.00	CY
610.181	Temporary Stone Check Dam	623.00	CY
613.319	Erosion Control Blanket	46,950.00	SY
615.07	Loam	11,390.00	CY
618.14	Seeding Method Number 2	928.00	UNIT
618.143	Special Seeding	25.00	UNIT
619.1201	Mulch - Plan Quantity	895.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.56	Drainage Geotextile	3,200.00	SY
620.561	Impervious Liner	3,150.00	SY
620.58	Erosion Control Geotextile	2,146.00	SY
620.6	Separation Geotextile	7,000.00	SY
626.122	Quazite Junction Box (18x11)	47.00	EA
626.22	Non-metallic Conduit	6,550.00	LF
626.223	Horizontal Directional Drilled Conduit	250.00	LF
626.31	18 Inch Diameter Foundation	1.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
626.32	24 Inch Diameter Foundation	46.00	EA
626.33	30 Inch Diameter, 8 Feet or Less Foundation	7.00	EA
626.332	30-Inch Diameter, Greater than 8-Feet Long, All 36 Inch and 42 Inch Diameter Foundations	24.00	CY
626.38	Ground Mounted Cabinet Foundation	2.00	EA
626.701	VMS Foundations - Crosby	1.00	LS
627.712	White or Yellow Pavement Marking Line	256,900.00	LF
627.73	Temporary 6 Inch Pavement Marking Tape	2,000.00	LF
627.731	Temporary 6 Inch Black Pavement Marking Tape	2,000.00	LF
627.77	Removing Existing Pavement Marking	43,850.00	SF
627.78	Temporary Pavement Marking Line, White or Yellow	230,500.00	LF
629.05	Hand Labor, Straight Time	230.00	HR
631.1	Air Compressor (Including Operator)	20.00	HR
631.11	Air Tool (Including Operator)	20.00	HR
631.12	All Purpose Excavator (Including Operator)	230.00	HR
631.13	Bulldozer (Including Operator)	200.00	HR
631.14	Grader (Including Operator)	30.00	HR
631.171	Truck - Small (Including Operator)	30.00	HR
631.172	Truck-Large (Including Operator)	200.00	HR
631.22	Front End Loader (Including Operator)	230.00	HR
631.32	Culvert Cleaner (Including Operators)	180.00	HR
631.36	Foreman	230.00	HR
634.175	Replacement LED Fixture	1.00	EA
634.208	Remove and Reset Light Standard	24.00	EA
634.2083	Remove and Stack Lighting Standard	6.00	EA
634.221	Temporary Highway Light	4.00	EA
634.231	Conventional Light Standard With LED Fixture	10.00	EA
639.181	Field Office, Type A-P	1.00	EA
645.105	Remove and Stack Sign	12.00	EA
645.109	Remove and Reset Sign	5.00	EA
645.1099	Remove and Dispose Sign	32.00	EA
645.12	Overhead Guide Sign: (STA 2133+14)	1.00	LS
645.161	Breakaway Device Single Pole	10.00	EA
645.162	Breakaway Device Multi Pole	15.00	EA
645.251	Roadside Guide Sign, Type I	1,380.00	SF
645.2511	Sheet Aluminum Overlay, Type I	288.00	SF
645.271	Regulatory, Warning, Confirmation and Route Assembly Sign, Type I	500.00	SF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
645.289	Steel H-Beam Poles	11,600.00	LB
645.501	Remove and Reset Mainline Sign No. 1	1.00	LS
645.502	Remove and Reset Mainline Sign No. 2	1.00	LS
645.503	Remove and Reset Mainline Sign No. 3	1.00	LS
645.504	Remove and Reset Mainline Sign No. 4	1.00	LS
645.505	Remove and Reset Mainline Sign No. 5	1.00	LS
645.506	Remove and Reset Mainline Sign No. 6	1.00	LS
645.507	Remove and Reset Mainline Sign No. 7	1.00	LS
645.508	Remove and Reset Mainline Sign No. 8	1.00	LS
645.509	Remove and Reset Mainline Sign No. 9	1.00	LS
645.51	Remove and Reset Mainline Sign No. 10	1.00	LS
645.511	Remove and Reset Mainline Sign No. 11	1.00	LS
645.512	Remove and Reset Mainline Sign No. 12	1.00	LS
645.513	Remove and Reset Mainline Sign No. 13	1.00	LS
645.514	Remove and Reset Mainline Sign No. 14	1.00	LS
645.515	Remove and Reset Mainline Sign No. 15	1.00	LS
645.516	Remove and Reset Mainline Sign No. 16	1.00	LS
645.517	Remove and Reset Mainline Sign No. 17	1.00	LS
645.518	Remove and Reset Mainline Sign No. 18	1.00	LS
645.519	Remove and Reset Mainline Sign No. 19	1.00	LS
645.52	Remove and Reset Mainline Sign No. 20	1.00	LS
645.521	Remove and Reset Mainline Sign No. 21	1.00	LS
645.522	Remove and Reset Mainline Sign No. 22	1.00	LS
645.523	Remove and Reset Mainline Sign No. 23	1.00	LS
645.524	Remove and Reset Mainline Sign No. 24	1.00	LS
645.525	Remove and Reset Mainline Sign No. 25	1.00	LS
645.526	Remove and Reset Mainline Sign No. 26	1.00	LS
645.527	Remove and Reset Mainline Sign No. 27	1.00	LS
645.528	Remove and Reset Overhead Mainline Sign No. 28	1.00	LS
645.529	Remove and Reset Mainline Sign No. 29	1.00	LS
650.101	Variable Message Sign (VMS) System - Holmes Road	1.00	LS
650.102	Variable Message Sign (VMS) System - Crosby	1.00	LS
650.201	VMS Ground Mounted Control Cabinet - Holmes Road	1.00	EA
650.202	VMS Ground Mounted Control Cabinet - Crosby	1.00	EA
650.801	VMS Power System - Holmes	1.00	LS
650.802	VMS Power System - Crosby	1.00	LS
652.3	Flashing Arrow	6.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
652.312	Type III Barricades	23.00	EA
652.33	Drum	770.00	EA
652.332	Drum, Left In Place	50.00	EA
652.34	Cone	300.00	EA
652.35	Construction Signs	5,400.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.41	Portable Changeable Message Sign	7.00	EA
652.44	Pace Vehicle	250.00	CD
652.45	Truck Mounted Attenuator	2,730.00	CD
652.47	Sequential Flashing Warning Lights	100.00	EA
652.452	Automated Trailer Mounted Speed Limit Sign	7.00	EA
656.5	Baled Hay, In Place	30.00	EA
656.6	Temporary Berms	165.00	LF
656.62	Temporary Slope Drains	138.00	LF
656.632	30 Inch Temporary Silt Fence	26,300.00	LF
659.1	Mobilization	1.00	LS
673.01	Stormwater Soil Filter Bed	1,030.00	CY
674.11	Prefabricated Concrete Modular Gravity Wall - Red Brook	1.00	LS
674.12	Prefabricated Concrete Modular Gravity Wall - Long Creek	1.00	LS
801.03	Test Pits	10.00	EA