



MAINE TURNPIKE AUTHORITY







THE GOLD STAR **MEMORIAL HIGHWAY**

MAINE TURNPIKE AUTHORITY

MICHAEL J. CIANCHETTE, CHAIR JANE L. LINCOLN, VICE CHAIR THOMAS J. ZUKE, MEMBER ANDREW MCLEAN MEMBER NINA A. FISHER, MEMBER EMILY BECKER, MEMBER BRUCE A. VAN NOTE, MEMBER EX-OFFICIO

ANDRE J. BRIERE, EXECUTIVE DIRECTOR

CONTRACT 2025.12 SLOPE AND DRAINAGE REPAIRS MM 0.00 to 109.10

INIDEA	OF	CHEETC
		ULLLIU

SHEET NO.	SHEET NO.	DESCRIPTION
1		TITLE SHEET
2	C-1	ESTIMATED QUANTITIES AND GENERAL NOTES
3	P-i	ONE LINE DIAGRAM
4	P-2	DRAINGE DETAILS I
5	P-3	DRAINGE DETAILS II
Ь	P-4	EROSION CONTROL DETAILS
7-12	P-5-10	SITE PLANS
13	P-11	MM 2.7 DETAILS



ESTIMATED QUANTITIES

ITEM	DESCRIPTION	UNIT	QUANTITY
NO.			TOTAL
203.20	Common Excavation	CY	35.00
304.10	Aggregate Subbase Course Gravel	CY	25.00
459.06	Bituminous Concrete Waterway, Type I	EA	2.00
602.40	Pumped Grout Fill	CY	3.00
603.159	12 inch Culvert Pipe Option III	LF	154.00
603.229	42 inch Culvert Pipe Option III	LF	14.00
603.28	Concrete Collar	EA	2.00
604.242	Catch Basin Type F3	EA	1.00
604.244	Catch Basin Type F4	EA	1.00
610.08	Plain Riprap	CY	55.00
613.319	Erosion Control Blanket	SY	1,000.00
615.07	Loam	CY	18.00
618.1401	Seeding Method Number 2, Plan Quantity	UNIT	5.00
619.1201	Mulch, Plan Quantity	UNIT	5.00
619.1202	Temporary Mulch	LS	1.00
620.58	Erosion Control Geotextile	SY	95.00
629.05	Hand Labor, Straight Time	HR	10.00
631.12	All Purpose Excavator (including operator)	HR	10.00
631.172	Truck - Large (including operator)	HR	10.00
631.36	Foreman	HR	10.00
631.37	Earthwork Crew (slope/pipe repairs)	HR	24.00
656.50	Baled Hay, in place	EA	15.00
656.632	30 inch Temporary Silt Fence	LF	50.00
659.10	Mobilization	LS	1.00
659.101	Mobilization (crew)	Shift	3.00
659.102	Mobilization (lowbed equipment)	HR	5.00

GENERAL NOTES

- 1. EXISTING UTILITIES ON THESE PLANS WERE COMPLIED FROM EXISTING PLANS AND VARIOUS OTHER SOURCES. LOCATIONS ARE NOT GUARANTEED TO BE ACCURATE NOR IS IT GUARANTEED THAT ALL UTILITIES ARE SHOWN. NO SEPARATE OR ADDITIONAL COMPENSATION WILL BE ALLOWED TO THE CONTRACTOR DUE TO ANY VARIANCE BETWEEN THE DATA SHOWN ON THE PLANS AND THE ACTUAL FIELD CONDITIONS ENCOUNTERED, NO WORK SHALL BE STARTED UNTIL THE OWNERS OF THE VARIOUS UTILITIES ARE NOTIFIED BY THE CONTRACTOR OF THE PROPOSED CONSTRUCTION. THE CONTRACTOR IS ALSO REQUIRED TO CALL DIG SAFE AT 1-888-344-7233 AT LEAST 72 HOURS PRIOR TO THE START OF THE WORK.
- 2. THE CONTRACTOR SHALL NOTIFY ALL NON-MEMBERS THROUGH WWW.OKtoDIG.COM OR AS OTHERWISE REQUIRED BY THE MAINE PUBLIC UTILITIES COMMISSION. ALL PROPOSED SIGN LOCATIONS AND EXCAVATION LOCATIONS SHALL BE MARKED AT THE NOTIFICATION TIME. NO EXCAVATION SHALL BE PERMITTED UNTIL THE AUTHORITY HAS LOCATED AND MARKED ITS UNDERGROUND UTILITIES. THE RESIDENT ENGINEER SHALL BE PROVIDED AN ELECTRONIC COPY OF TALL DIG SAFE TICKETS WITHIN 24 HOURS OF THEIR RELEASE FOR PROJECT NOTIFICATIONS AND 3RD PARTY UTILITY LOCATER COORDINATION.
- 3. THE CONTRACTOR SHALL NOTIFY THE RESIDENT 10 CALENDAR DAYS PRIOR TO SUBMITTING A UTILITY LOCATE REQUEST THROUGH DIG SAFE SO THAT THE RESIDENT CAN ARRANGE FOR MAINE TURNPIKE UNDERGROUND UTILITY LOCATION. ALL PROPOSED SIGN LOCATIONS AND EXCAVATION LOCATIONS SHALL BE MARKED AT THE NOTIFICATION TIME.
- 4. FOLLOWING THE COMPLETION OF THE INITIAL UTILITY LOCATE THE CONTRACTOR WILL GPS LOCATE ALL UTILITIES WITHIN THE PROJECT LIMITS AND PROVIDE A COPY OF THE DIG SAFE RECORDS TO THE AUTHORITY. THE CONTRACTOR, ACTING AS THE AUTHORITY'S THIRD PARTY LOCATOR SHALL BE RESPONSIBLE FOR REMARKING ALL MAINE TURNPIKE FACILITIES WHEN A DIG SAFE UTILITY LOCATE IS CALL FOR IN THE PROJECT. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 5. ALL WORK AND MATERIALS REQUIRED TO REMOVE AND REPLACE CATCH BASINS SHALL BE INCLUDED IN THE 604.24 ITEM, CATCH BASIN TYPE F4.
- 6. ALL EXCAVATION SHALL FALL UNDER HOURLY RENTAL ITEM 631.12, ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)
- 7. MTA WILL PROVIDE ALL TRAFFIC CONTROL
- 8. THE LOAM, SEED AND EROSION CONTROL BLANKET CAN NOT BE PLACED UNTIL THE BITUMINOUS CURB IS INSTALLED, WHICH IS CONTRACT 2025.14 AND TO BE INSTALLED BY AUGUST 15, 2025.
- 9. TYPICAL LOAM DEPTH IS 4 INCHES NOMINAL.

DRAINAGE NOTES

- 1. NO EXISTING DRAINAGE SHALL BE ABANDONED, REMOVED OR PLUGGED WITHOUT APPROVAL OF THE RESIDENT.
- 2. DRAINAGE WORK CONSISTS OF RCP PIPE END REPAIRS, EXCAVATION AND CATCH BASIN REPLACEMENT.

EROSION CONTROL

- 1. ADDITIONAL MEASURES MAY BE PROPOSED BY THE CONTRACTOR DUE TO SITE OR WEATHER CONDITIONS. THE RESIDENT MAY DIRECT THE CONTRACTOR TO IMPLEMENT ADDITIONAL MEASURES, ANY ADDITIONAL MEASURES APPROVED BY THE RESIDENT WILL BE MEASURED FOR PAYMENT.
- 2. ALL TEMPORARY EROSION CONTROL DEVICES SHALL BE INSTALLED IN ACCORDANCE WITH THE MAINE DEPARTMENT OF TRANSPORTATION BEST MANAGEMENT PRACTICES.
- 3. EROSION CONTROL REPAIRS CONSIST OF BASIC SLOPE EROSION AND WASHOUT REPAIRS.

Scale:

NOT TO SCALE

By Date Revision

Date

Checked

JRL | 04/30/25

BMB 04/30/25

By Date

HJM 04/30/25

In Charge of SRT 04/30/25

Designed by:


Designed

MAINE TURNPIKE AUTHORITY 2360 Congress Street Portland, ME 04102 TEL (207) 871-7771 FAX (207) 879-5567





ESTIMATED QUANTITIES AND GENERAL NOTES

SHEET NUMBER: C-1




K:\Contracts\2025 Construction Project Files\2025.12 Exit 103 Slop





BITUMINOUS CONCRETE WATERWAY, TYPE I N.T.S.

SECTION A-A




SECTION A-A

<u>CATCH BASIN</u>

N.T.S.


-2" HMA 9.5 MM



-PROVIDE AND COMPACT ADDITIONAL RECLAIM AS REQUIRED

- 1. INSTALL MINIMUM OF 3 HAY BALES UP STREAM.
- 2. THE EXACT LOCATION AND NUMBER OF BALES SHALL BE AS DIRECTED BY THE RESIDENT.

PROPOSED EROSION CONTROL AT MEDIAN N.T.S.



Designed by:

MAINE TURNPIKE AUTHORITY 2360 Congress Street Portland, ME 04102 TEL (207) 871-7771 FAX (207) 879-5567



DRAINAGE DETAILS I

SHEET NUMBER: P-2

MTA PROJECT MANAGER: Harold James Mason, P.E.

4 of 13 CONTRACT: 2025.12

Scale:


D	A (FT)	B (FT)	C (FT)	E (FT)	F (FT)	G (FT)	STONE DEPTH (FT)	
12"	1.00	4.00	3.00	2.00	6.00	1.00	1.50	1.30
15"	1.00	4.50	3.37	2.25	6.75	1.63	1.50	1.70
18"	1.00	5.00	3.75	2.50	7.50	2.25	1.50	2.09
24"	1.00	6.00	4.50	3.00	9.00	3.50	1.50	3.12
30"	1.00	7.00	5.25	3.50	10.50	4.75	1.50	4.33

DIMENSIONS	FOR	SLOPE	OF	4:
------------	-----	-------	----	----

_		_1 1 0 1 0	2110	1 01	<u> </u>			<u> </u>
D	A (FT)	B (FT)	C (FT)	E (FT)	F (FT)	G (FT)	STONE DEPTH (FT)	STON (CY)
12"	1.00	8.00	6.00	2.00	6.00	0.00	1.50	2.20
15"	1.00	9.00	6.75	2.25	6.75	0.00	1.50	2.80
18"	1.00	10.00	7.50	2.50	7.50	0.00	1.50	3.40
24"	1.00	12.00	9.00	3.00	9.00	0.00	1.50	4.86
30"	1.00	14.00	10.50	3.50	10.50	0.00	1.50	6.58




D	A (FT)	B (FT)	C (FT)		F (FT)		STONE DEPTH (FT)	
12"	0.50	9.00	7.50	1.50	4.50	0.00	1.50	2.30
15"	0.50	10.50	8.75	1.75	5.50	0.00	1.50	2.93
18"	0.50	12.00	10.00	2.00	6.50	0.00	1.50	3.57
24"	0.50	15.00	12.50	2.50	8.00	0.00	1.50	5.44
30"	0.50	18.00	15.00	3.00	9.50	0.00	1.50	7.71




-RCP PIPE

- CONCRETE


COLLAR






	WIDTH VARIES	FINISH GRA	DE
NON-WOVEN GEOTEXTILE TO BE WRAPPED AROUND CONNECTION	SEE SCHEDULE	CAST IN PLACE CONCRETE COLLAR	EXCAVATION
	A	CLASS I BEDDING TO SUPPORT CONCRETE COLLA	


CONCRETE COLLAR	WIDTH SCHEDULE
PIPE DIA. (INCHES)	WIDTH OF CONC. (INCHES)
12	24
15	24
18	24
24	24
30	30
36	36
42	48
48	48





CONCRETE COLLAR N.T.S.

<u>SECTION</u>



ROADWAY CULVERT END SLOPE TREATMENT N.T.S.

NOTES:

- 1. THE DIMESIONS SHOWN ARE APPROXIMATE AND MAY BE MODIFIED BY THE RESIDENT.
- 2. STONE QUANTITIES ARE FOR ONE END OF THE PIPE.

NOTES:

- 1. CONNECTION AND PIPE TO BE BACKFILLED PER ASTM D2321 (CRUSHED STONE).
- 2. CONCRETE SHALL BE CLASS A FIBER REINFORCED.
- 3. SEE CONCRETE COLLAR WIDTH SCHEDULE FOR DIMENSIONS.
- 4. CONCRETE COLLAR SHALL BE FORMED IN PLACE.

Scale:				Designed	by:
	NOT TO SCALE				
No.	Revision	Ву	Date		
					E
				Designed	JF

Date

Checked

JRL 04/30/25

BMB 04/30/25

 By
 Date

 HJM
 04/30/25

In Charge of SRT 04/30/25

MAINE TURNPIKE AUTHORITY 2360 Congress Street Portland, ME 04102 TEL (207) 871-7771 FAX (207) 879-5567




THE GOLD STAR MEMORIAL HIGHWAY

DRAINAGE DETAILS II

SHEET NUMBER: P-35 of 13


MTA PROJECT MANAGER: Harold James Mason, P.E.



NOTE:

STONE FOR STONE DOWNSPOUTS SHALL MEET THE REQUIREMENTS OF MDOT SPECIFICATION 703.29 AND WILL BE PAID FOR UNDER ITEM 610.08, PLAIN RIPRAP.

SLOPE REPAIR DETAILS EXIT 103 SB OFF RAMP N.T.S.



SECTION A-A

CONSTRUCTION ELEMENTS AND GENERAL SEQUENCE

- 1. REMOVE EXISTING MATERIAL UP TO 1'OR UNTIL APPROPRIATE BASE IS REACHED, WHICHEVER IS LESS. APPROPRIATE BASE TO BE DETERMINED BY RESIDENT.
- 2. ADD ADDITIONAL COMMON BORROW INCIDENTAL TO RIP RAP.
- 3. PLACE RIP RAP ON GEOTEXTILE.

By Date HJM 04/30/25

NOT TO SCALE By Date Revision By Date JRL 04/30/25 Checked Designed BMB 04/30/25 In Charge of SRT 04/30/25

Designed by:

MAINE TURNPIKE AUTHORITY 2360 Congress Street Portland, ME 04102 TEL (207) 871-7771 FAX (207) 879-5567




EROSION CONTROL DETAILS


SHEET NUMBER: P -4

MTA PROJECT MANAGER: Harold James Mason, P.E.

CONTRACT: 2025.12

Scale:





By Date Revision Designed

MAINE TURNPIKE

 By
 Date

 JRL
 04/30/25

BMB 04/30/25

Checked

MAINE TURNPIKE AUTHORITY 2360 Congress Street Portland, ME 04102 TEL (207) 871-7771 FAX (207) 879-5567

 By
 Date

 HJM
 04/30/25

In Charge of SRT 04/30/25


MAINE TURNPIKE

THE GOLD STAR MEMORIAL HIGHWAY

SITE PLAN WEST GARDINER ORT

> SHEET NUMBER: P - 5 7 of 13

MTA PROJECT MANAGER: Harold James Mason, P.E.



By Date Revision Designed

Designed by:

| By | Date | Checked | HJM | 04/30/25 | In Charge of | SRT | 04/30/25 |
 By
 Date

 JRL
 04/30/25
 BMB 04/30/25

MAINE TURNPIKE AUTHORITY 2360 Congress Street Portland, ME 04102 TEL (207) 871-7771 FAX (207) 879-5567




SITE PLAN II EXIT 103 SOUTHBOUND OFF RAMP

SHEET NUMBER: P - 6

MTA PROJECT MANAGER: Harold James Mason, P.E.

8 of 13 CONTRACT: 2025.12





By Date Revision Designed

By Date JRL 04/30/25

BMB 04/30/25

| By | Date | Checked | HJM | 04/30/25 | In Charge of | SRT | 04/30/25 |

MAINE TURNPIKE AUTHORITY 2360 Congress Street Portland, ME 04102 TEL (207) 871-7771 FAX (207) 879-5567



SITE PLAN III MM 100.4 STA. 5127+20 NB


SHEET NUMBER: P - 7


MTA PROJECT MANAGER: Harold James Mason, P.E.

9 of 13 CONTRACT: 2025.12









BMB 04/30/25 In Charge of SRT 04/30/25

Designed

By Date HJM 04/30/25

MAINE TURNPIKE AUTHORITY 2360 Congress Street Portland, ME 04102 TEL (207) 871-7771 FAX (207) 879-5567




THE GOLD STAR MEMORIAL HIGHWAY

SITE PLAN V MM 21.9 STA. 1028+87 MEDIAN

SHEET NUMBER: P - 8

MTA PROJECT MANAGER: Harold James Mason, P.E.





By Date Revision Designed

 By
 Date

 JRL
 04/30/25

BMB 04/30/25

| By | Date | Checked | HJM | 04/30/25 | In Charge of | SRT | 04/30/25 |


MAINE TURNPIKE AUTHORITY 2360 Congress Street Portland, ME 04102 TEL (207) 871-7771 FAX (207) 879-5567



SITE PLAN VI MM 10.0 STA. 407+56 MEDIAN

SHEET NUMBER: P - 9 11 of 13

MTA PROJECT MANAGER: Harold James Mason, P.E.



By Date Revision Designed

| By | Date | Checked | HJM | 04/30/25 | In Charge of | SRT | 04/30/25 |
 By
 Date

 JRL
 04/30/25
 BMB 04/30/25

MAINE TURNPIKE AUTHORITY 2360 Congress Street Portland, ME 04102 TEL (207) 871-7771 FAX (207) 879-5567




THE GOLD STAR MEMORIAL HIGHWAY

SITE PLAN VII MM 2.7 STA. 74+40 MEDIAN

SHEET NUMBER: P - 10

MTA PROJECT MANAGER: Harold James Mason, P.E.

12 of 13 CONTRACT: 2025.12



NOTES:

- 1. SAWCUTTING AND CORING INTO EXISTING CATCH BASIN SHALL BE INCIDENTAL TO THE PIPE.
- 2. CONTRACTOR SHALL NOT UNDERMINE GRAVEL AND PAVEMENT OF ADJACENT SHOULDER.
- 3. CONTRACT 2025.14 SHALL FINE GRADE AND PAVE DISTURBED MEDIAN.

Scal No.	Revision By Date	Designed by: MAINE TURNPIKE	MAINE TURNPIKE AUTHORITY 2360 Congress Street Portland, ME 04102 TEL (207) 871-7771 FAX (207) 879-5567	THE GOLD STAR MEMORIAL HIGHWAY	SITE PLAN VIII EXIT 52 SB OFF STA. 2566+50 MEDIAN	
		By Date By Date Designed JRL 04/30/25 Checked HJM 04/30/25 Drawn BMB 04/30/25 In Charge of SRT 04/30/25	FAX (207) 879-5567	MTA PROJECT MANAGER: Harold James Mason, P.E.	SHEET NUMB CONTRACT: 2025.12	BER: P - 11 13 of 13

K:\Contracts\2025 Construction Project Files\2025.12 Exit 103 Slope