



Maine Turnpike Authority

Schedule of Items

Bridge Rehabilitation - Cobboseecontee Stream Overpass Mile 99.2

Item No.	Description	Quantity	UOM
201.31	Removal of Debris	1.00	LS
202.202	Removing Pavement Surface	12,550.00	SY
202.2026	Removing Pavement Surface - Drainage Paths	22.00	SF
202.206	Removing Rumble Strips	100.00	LF
202.1	Removing Existing Superstructure Property of Contractor	1.00	LS
202.12	Removing Existing Structural Concrete	140.00	CY
202.13	Removing Existing Railings Retained by Authority	980.00	LF
203.2	Common Excavation	930.00	CY
203.25	Granular Borrow	500.00	CY
203.43	Geofoam Lightweight Fill	280.00	CY
203.45	Leveling Sand	69.00	CY
206.082	Structural Earth Excavation - Major Structures, Plan Quantity	420.00	CY
206.1	Structural Earth Excavation - Piers	700.00	CY
304.1	Aggregate Subbase Course - Gravel	250.00	CY
304.14	Aggregate Base Course - Type A	230.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	700.00	Ton
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size	130.00	Ton
403.2081	Hot Mix Asphalt, 12.5 mm (Polymer Modified) - RAP	1,300.00	Ton
403.2084	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (sidewalks, drives, islands & incidentals)	80.00	Ton
403.212	Hot Mix Asphalt, 4.75 mm Nominal Maximum Size	210.00	Ton
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate Base Course)	620.00	Ton
409.15	Bituminous Tack Coat - Applied	1,435.00	Gal
419.3	Sawing Bituminous Pavement	1,980.00	LF
470.08	Berm Dropoff Correction - Grindings	16.00	Ton
470.081	Berm Correction	1,350.00	LF
501.231	Dynamic Loading Test	4.00	EA
501.38	Steel H-beam Piles 42 lb/ft, delivered	510.00	LF
501.381	Steel H-beam Piles 42 lb/ft, in place	510.00	LF
501.9	Pile Tips	16.00	EA
501.91	Pile Splices	5.00	EA
501.92	Pile Driving Equipment Mobilization	1.00	LS
502.219	Structural Concrete, Abutments and Retaining Walls	1.00	LS
502.239	Structural Concrete Piers	1.00	LS
502.24	Structural Concrete Piers (placed under water)	310.00	CY
502.26	Structural Concrete Roadway and Sidewalk Slab on Steel Bridges	1.00	LS
502.264	Structural Concrete Parapets	1.00	LS



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
502.31	Structural Concrete Approach Slab	1.00	LS
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	243,000.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	243,000.00	LB
504.702	Structural steel, fabricated and delivered, welded	1.00	LS
504.71	Structural steel erection	1.00	LS
504.885	Post-Tensioning Sleeve Repair	13.00	EA
505.08	Shear Connectors	1.00	LS
506.9102	Zinc Rich Coating System (Shop Applied)	1.00	LS
506.9105	Field Touch-Up of Existing Steel	1.00	LS
507.091	Aluminum Bridge Railing, 1 Bar	1.00	LS
508.14	High Performance Waterproofing Membrane	1.00	LS
511.071	Cofferdam Pier 1 - NB	1.00	LS
511.072	Cofferdam Pier 1 - SB	1.00	LS
511.073	Cofferdam Pier 2 - NB	1.00	LS
511.074	Cofferdam Pier 2 - SB	1.00	LS
511.075	Cofferdam Pier 3 - NB	1.00	LS
511.076	Cofferdam Pier 3 - SB	1.00	LS
514.06	Curing Box for Concrete Cylinders	2.00	EA
515.201	Pigmented Protective Coating for Concrete Surfaces	1,400.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	4,300.00	SY
515.23	Anti-Graffiti Coating	900.00	SY
518.4	Epoxy Injection Crack Repair	355.00	LF
518.401	Epoxy Injection Crack Repair - Below Waterline	485.00	LF
518.51	Repair of Upward Facing Surfaces - Below Reinforcing Steel < 8 inches	67.00	SF
518.6	Repair of Vertical Surfaces < 8 inches	2,993.00	SF
518.601	Repair of Vertical Surfaces < 8 inches - Below Waterline	55.00	SF
518.7	Repair of Overhead Surfaces < 8 inches	91.00	SF
520.23	Asphaltic Plug Joint	160.00	LF
520.224	Joint Armor Repair	1.00	LS
523.52	Bearing Installation	60.00	EA
523.5401	Laminated Elastomeric Bearings, Fixed	12.00	EA
523.54021	PTFE Elastomeric Bearings, Expansion	48.00	EA
523.56	Cleaning and Painting Bearing	42.00	EA
523.561	Repair Bearing	1.00	EA
523.562	Repair Bearing Keeper Strap	10.00	EA
524.301	Temporary Structural Support - Androscoggin Jacking	1.00	LS
524.302	Temporary Structural Support - Cobbosseecontee Girders	1.00	LS



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
524.303	Temporary Structural Support - Cobbosseecontee Braces	1.00	LS
524.4	Protective Shielding - Steel Girders	2,250.00	SY
524.6	Temporary Access Platforms for Pier Inspection and Repair	1.00	LS
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority	1.00	LS
527.301	Energy Absorbing System (CAT) - New	3.00	EA
527.341	Work Zone Crash Cushions - TL-3	3.00	Unit
603.159	12 inch Culvert Pipe Option III	148.00	LF
603.179	18 inch Culvert Pipe Option III	65.00	LF
603.28	Concrete Collar	3.00	EA
604.184	Rebuild Catch Basin to Grade - Type II	9.00	EA
604.242	Catch Basin Type F3	1.00	EA
604.4	Secure Catch Basin Grate	2.00	EA
606.13	31" W-Beam Guardrail - Mid-Way Splice (7' Steel Post, 8" Offset Blocks, Single Faced)	1,037.50	LF
606.1723	Bridge Transition - Type III	4.00	EA
606.1724	Bridge Transition - Type III, Modified	2.00	EA
606.1351	Terminal End - Anchored End - 31" W-Beam Guardrail	1.00	EA
606.279	Terminal End - Anchored End, Thrie Beam	1.00	EA
606.353	Reflectorized Flexible Guardrail Marker	3.00	EA
606.354	Remove and Reset Reflectorized Flexible Guardrail Marker	3.00	EA
606.64	Guardrail Thrie Beam - Double Rail	1,225.00	LF
606.65	Guardrail Thrie Beam - Single Rail	115.00	LF
606.791	Guardrail - Flared Terminal - 31" W-Beam Guardrail	1.00	EA
607.09	Woven Wire Fence - Metal Posts	120.00	LF
607.33	Bracing Assembly, Type II - Metal Post	2.00	EA
607.4311	Snow Drift Fence	280.00	LF
609.15	Sloped Curb Type 1	970.00	LF
610.08	Plain Riprap	1,108.00	CY
610.18	Stone Ditch Protection	17.00	CY
613.319	Erosion Control Blanket	160.00	SY
615.07	Loam	310.00	CY
618.141	Seeding Method Number 3	25.00	Unit
619.1201	Mulch - Plan Quantity	25.00	Unit
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	85.00	SY
620.7	HDPE Geomembrane	700.00	SY
627.712	White or Yellow Pavement Marking Line	21,600.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
627.73	Temporary 6 Inch Pavement Marking Tape	14,650.00	LF
627.731	Temporary 6 Inch Black Pavement Marking Tape	6,650.00	LF
627.77	Removing Existing Pavement Marking	7,850.00	SF
627.94	Pavement Marking Tape	140.00	LF
629.05	Hand Labor, Straight Time	40.00	HR
631.1	Air Compressor (including operator)	30.00	HR
631.11	Air Tool (including operator)	30.00	HR
631.12	All Purpose Excavator (including operator)	20.00	HR
631.172	Truck - Large (including operator)	40.00	HR
631.36	Foreman	20.00	HR
644.1	Glare Screen - Supplied by Authority	1,100.00	LF
652.3	Flashing Arrow	4.00	EA
652.312	Type III Barricade	1.00	EA
652.33	Drum	206.00	EA
652.34	Cone	170.00	EA
652.35	Construction Signs	1,510.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	10.00	HR
652.41	Portable-Changeable Message Sign	4.00	EA
652.45	Truck Mounted Attenuator	48.00	CD
652.451	Automated Trailer Mounted Speed Limit Sign	48.00	CD
652.46	Temporary Portable Rumble Strip	48.00	Unit
656.5	Baled Hay, in place	20.00	EA
656.632	30 inch Temporary Silt Fence	960.00	LF
656.64	Boom Supported Floating Silt Fence	418.00	LF
659.1	Mobilization	1.00	LS