



Maine Turnpike Authority *Schedule of Items*

Bridge Repairs - Route 1 Off-Ramp (Ramp J) Underpass (MM 1.50) Wilson Road Underpass (MM 2.00) Littlefield Road (MM 17.30)

Item No.	Description	Quantity	UOM
202.202	Removing Pavement Surface	3,310.00	SY
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Surface)	331.00	TON
409.15	Bituminous Tack Coat RS-1 or RS1h - Applied	132.00	GAL
502.702	Replace Bridge Drain (Type A1)	11.00	EA
508.141	High Performance Waterproofing Membrane (Ramp J) (994 SY)	1.00	LS
508.142	High Performance Waterproofing Membrane (Wilson Rd) (927 SY)	1.00	LS
515.201	Pigmented Protective Coating for Concrete Surfaces	1,030.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	1,020.00	SY
518.1	Abutment Repairs	730.00	SF
518.2	Pier Repairs	20.00	SF
518.391	Repairing Granite Curb Joint and Bedding Mortar	1,480.00	LF
518.4	Epoxy Injection Crack Repair	90.00	LF
518.48	Reseal Joints	125.00	LF
518.7	Repair of Overhead Surfaces < 8 inches	5.00	SF
518.75	Fascia and Overhang Repairs	147.00	SF
518.76	Partial Concrete Curb Reconstruction	280.00	LF
518.8	Partial Depth Concrete Deck Repairs	515.00	SF
518.81	Full Depth Concrete Deck Repairs	175.00	SF
518.864	Elastomeric Concrete Header Repair	10.00	CF
518.92	Slope Protection Repairs	170.00	LF
518.921	Slope Protection Concrete Repairs	80.00	SF
518.93	Parapet Repairs	110.00	SF
518.94	Parapet Surface Repairs	361.00	LF
520.234	Expansion Device - Silicone Coated and Pre-Compressed Seal	36.00	LF
520.2407	Bridge Joint Steel Modification	4.00	EA
520.5	Remove and Replace Gland Seal (Wilson Rd)	2.00	EA
523.1201	Reset Steel Bearings	5.00	EA
524.4	Protective Shielding - Steel Girders	360.00	SY
524.7212	Jacking Existing Superstructure (Ramp J)	1.00	LS
526.301	Temporary Concrete Barrier, Type 1	750.00	LF
527.341	Work Zone Crash Cushion - TL-3	4.00	UNIT
527.343	Resetting Existing Work Zone Crash Cushion	4.00	UNIT
627.712	White or Yellow Pavement Marking Line	11,540.00	LF
627.73	Temporary 6" Pavement Marking Tape	72.00	LF
627.77	Removing Existing Pavement Markings	3,135.00	SF
629.05	Hand Labor, Straight Time	100.00	HR
631.1	Air Compressor (including operator)	100.00	HR



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
631.11	Air Tool (including operator)	100.00	HR
631.12	All Purpose Excavator (including operator)	100.00	HR
631.171	Truck - small (including operator)	100.00	HR
631.36	Foreman	100.00	HR
639.19	Field Office, Type B	1.00	EA
643.72	Temporary Traffic Signal	1.00	LS
652.3	Flashing Arrow	4.00	EA
652.312	Type III Barricade	14.00	EA
652.33	Drum	230.00	EA
652.34	Cone	50.00	EA
652.35	Construction Signs	2,040.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	300.00	HR
652.41	Portable Changeable Message Sign	3.00	EA
652.45	Truck Mounted Attenuator	50.00	CD
652.451	Automated Trailer Mounted Speed Limit Sign	35.00	CD
652.47	Sequential Flashing Warning Lights	90.00	EA
656.75	Temporary Soil Erosion and Water Pollution Control	1.00	LS
659.1	Mobilization	1.00	LS
830.17	Utility Conduit Hanger System Hardware	1.00	LS