



# Maine Turnpike Authority

## *Schedule of Items*

### Exit 45 Embankment Preload Mile 44.9

Item No.	Description	Quantity	UOM
201.11	CLEARING	3.00	AC
202.15	REMOVING EXISTING MANHOLE OR CATCH BASIN	2.00	EA
202.202	REMOVING PAVEMENT SURFACE	830.00	SY
203.2	COMMON EXCAVATION	33,400.00	CY
203.24	COMMON BORROW	133,000.00	CY
203.25	GRANULAR BORROW	72.00	CY
209.29	PREFABRICATED VERTICAL DRAINS	2,343,000.00	LF
304.1	AGGREGATE SUBBASE COURSE - GRAVEL	173,000.00	CY
304.14	AGGREGATE BASE COURSE - TYPE A	21.00	CY
403.207	HOT MIX ASPHALT, 19.0 mm NOMINAL MAXIMUM SIZE	170.00	Ton
403.208	HOT MIX ASPHALT, 12.5 mm NOMINAL MAXIMUM SIZE	580.00	Ton
403.212	HOT MIX ASPHALT, 4.75 mm NOMINAL MAXIMUM SIZE	1,350.00	Ton
403.213	HOT MIX ASPHALT, 12.5 mm NOMINAL MAXIMUM SIZE (BASE AND INTERMEDIATE BASE COURSE)	790.00	Ton
409.15	BITUMINOUS TACK COAT RS-1 OR RS-1H - APPLIED	320.00	GAL
419.3	SAWING BITUMINOUS PAVEMENT	620.00	LF
526.306	TEMPORARY CONCRETE BARRIER, TYPE I - SUPPLIED BY AUTHORITY (3,000 LF)	1.00	LS
527.341	WORK ZONE CRASH CUSHIONS - TL-3	1.00	UN
527.3411	WORK ZONE CRASH CUSHIONS - TL-3 LEFT IN PLACE	1.00	UN
527.3421	WORK ZONE CRASH CUSHIONS - TL-2 LEFT IN PLACE	5.00	UN
602.3	FLOWABLE CONCRETE FILL	2.00	CY
603.155	12 INCH REINFORCED CONCRETE PIPE - CLASS III	56.00	LF
603.159	12 INCH CULVERT PIPE OPTION III	72.00	LF
603.169	15 INCH CULVERT PIPE OPTION III	99.00	LF
603.175	18 INCH REINFORCED CONCRETE PIPE - CLASS III	36.00	LF
603.195	24 INCH REINFORCED CONCRETE PIPE - CLASS III	480.00	LF
603.205	30 INCH REINFORCED CONCRETE PIPE - CLASS III	780.00	LF
603.215	36 INCH REINFORCED CONCRETE PIPE - CLASS III	76.00	LF
603.255	60 INCH REINFORCED CONCRETE PIPE - CLASS III	180.00	LF
603.28	CONCRETE COLLAR	2.00	EA
604.09	CATCH BASIN TYPE B1	4.00	EA
604.093	60" CATCH BASIN TYPE B1	2.00	EA
604.244	CATCH BASIN TYPE F4	1.00	EA
606.1724	BRIDGE TRANSITION - TYPE II - MODIFIED	1.00	EA
606.278	TERMINAL END - ANCHORED END	1.00	EA
606.352	REFLECTORIZED BEAM GUARDRAIL DELINEATOR	280.00	EA
606.356	UNDERDRAIN DELINEATOR POST	24.00	EA



## Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
606.3562	DELINEATOR POST - REMOVE AND STACK	60.00	EA
606.3606	GUARDRAIL - REMOVE, MODIFY, AND RESET DOUBLE RAIL	25.00	LF
607.09	WOVEN WIRE FENCE - METAL POSTS	650.00	LF
607.17	CHAIN LINK FENCE - 6 FOOT	1,200.00	LF
607.23	CHAIN LINK FENCE GATE	1.00	EA
607.32	BRACING ASSEMBLY TYPE I - METAL POSTS	8.00	EA
607.33	BRACING ASSEMBLY TYPE II - METAL POSTS	3.00	EA
609.31	CURB TYPE 3	18.00	LF
610.08	PLAIN RIPRAP	170.00	CY
610.18	STONE DITCH PROTECTION	45.00	CY
610.181	TEMPORARY STONE CHECK DAM	45.00	CY
613.319	EROSION CONTROL BLANKET	7,350.00	SY
615.07	LOAM	5,200.00	CY
618.14	SEEDING METHOD NUMBER 2	420.00	UNIT
619.1201	MULCH - PLAN QUANTITY	420.00	UNIT
619.1202	TEMPORARY MULCH	1.00	LS
620.58	EROSION CONTROL GEOTEXTILE	570.00	SY
626.121	QUAZITE JUNCTION BOX (36X24)	5.00	EA
626.122	QUAZITE JUNCTION BOX (18X11)	6.00	EA
626.131	ADJUST EXISTING JUNCTION BOX TO GRADE	10.00	EA
626.22	NON-METALLIC CONDUIT	100.00	LF
627.77	REMOVING EXISTING PAVEMENT MARKING	5,350.00	SF
627.78	TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	15,300.00	LF
627.812	TEMPORARY RAISED PAVEMENT MARKERS	1,400.00	EA
629.05	HAND LABOR, STRAIGHT TIME	20.00	HR
631.12	ALL PURPOSED EXCAVATOR (INCLUDING OPERATOR)	40.00	HR
631.172	TRUCK - LARGE (INCLUDING OPERATOR)	40.00	HR
631.22	FRONT END LOADER (INCLUDING OPERATOR)	40.00	HR
631.32	CULVERT CLEANER (INCLUDING OPERATORS)	20.00	HR
631.36	FOREMAN	40.00	HR
634.2083	REMOVE AND STACK LIGHT STANDARD	4.00	EA
634.221	TEMPORARY HIGHWAY LIGHT	4.00	EA
639.18	FIELD OFFICE, TYPE A	1.00	EA
639.26	INSTRUMENTATION (GEOTECHNICAL)	1.00	LS
645.105	REMOVE AND STACK SIGN	4.00	EA
652.3	FLASHING ARROW	3.00	EA
652.312	TYPE III BARRICADES	10.00	EA



## Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
652.33	DRUM	560.00	EA
652.332	DRUM LEFT IN PLACE	170.00	EA
652.34	CONE	50.00	EA
652.35	CONSTRUCTION SIGNS	1,850.00	SF
652.351	CONSTRUCTION SIGNS LEFT IN PLACE	530.00	SF
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS
652.38	FLAGGERS	80.00	HR
652.41	PORTABLE-CHANGEABLE MESSAGE SIGN	8.00	EA
652.45	TRUCK MOUNTED ATTENUATOR	20.00	CD
652.4501	TRUCK MOUNTED ATTENUATOR - 24,000 LB	30.00	CD
652.451	AUTOMATED TRAILER MOUNTED SPEED LIMIT SIGN	20.00	CD
656.5	BALED HAY, IN PLACE	100.00	EA
656.6	TEMPORARY BERMS	1,800.00	LF
656.62	TEMPORARY SLOPE DRAINS	210.00	LF
656.632	30 INCH TEMPORARY SILT FENCE	17,400.00	LF
659.1	MOBILIZATION	1.00	LS