



Maine Turnpike Authority *Schedule of Items*

Bridge And Culvert Repairs - 4 Locations Mile 75.8 To Mile 91.9

Item No.	Description	Quantity	UOM
202.127	REMOVING OF EXISTING BITUMINOUS PAVEMENT (2075 SY)	1.00	LS
202.191	REMOVING EXISTING DRAIN TROUGHS	1.00	LS
202.202	REMOVING PAVEMENT SURFACE	1,290.00	SY
203.24	COMMON BORROW	5.00	CY
403.208	HOT MIX ASPHALT, 12.5MM NOMINAL MAXIMUM SIZE	278.00	TON
403.213	HOT MIX ASPHALT, 12.5MM NOMINAL MAXIMUM SIZE (BASE AND INTERMEDIATE COURSE)	171.00	TON
409.15	BITUMINOUS TACK COAT - APPLIED	218.00	GAL
507.095	ALUMINUM BRIDGE RAILING - SPLICE MODIFICATION	38.00	EA
508.14	HIGH PERFORMANCE WATERPROOFING MEMBRANE (2075 SY)	1.00	LS
511.07	COFFERDAM	1.00	LS
515.201	PIGMENTED PROTECTIVE COATING FOR CONCRETE SURFACES	1,015.00	SY
515.202	CLEAR PROTECTIVE COATING FOR CONCRETE SURFACES	1,720.00	SY
518.10	ABUTMENT REPAIRS	70.00	SF
518.20	PIER REPAIRS	260.00	SF
518.39	GRANITE CURB JOINT MORTAR AND BEDDING MORTAR REPAIR	270.00	LF
518.40	EPOXY INJECTION CRACK REPAIR	65.00	LF
518.43	PARAPET JOINT REPAIR	1,310.00	LF
518.75	FASCIA AND OVERHANG REPAIRS	105.00	SF
518.80	PARTIAL DEPTH CONCRETE DECK REPAIRS	570.00	SF
518.81	FULL DEPTH CONCRETE DECK REPAIRS	30.00	SF
520.22111	EXPANSION DEVICE MODIFICATIONS (DANVILLE CORNER ROAD)	2.00	EA
520.22112	EXPANSION DEVICE MODIFICATIONS (FISHER FARM ROAD)	2.00	EA
520.22113	EXPANSION DEVICE MODIFICATIONS (CENTER ROAD)	2.00	EA
526.306	TEMPORARY CONCRETE BARRIER, TYPE 1 - SUPPLIED BY AUTHORITY	1.00	LS
527.341	WORK ZONE CRASH CUSHIONS - TL-3	6.00	UNIT
603.91	PRESSURE TREATED WOOD DRAIN TROUGH	70.00	LF
607.17	CHAIN LINK FENCE - 6 FOOT	355.00	LF
607.171	CHAIN LINK FENCE - 6 FOOT PVC PRIVACY FENCE	1,750.00	LF
607.23	CHAIN LINK FENCE GATE	2.00	EA
607.34	BRACING ASSEMBLY CHAIN LINK FENCE	20.00	EA
610.08	PLAIN RIPRAP	8.00	CY
615.07	LOAM	60.00	CY
618.14	SEEDING METHOD NUMBER 2	5.00	UNIT
619.1201	MULCH - PLAN QUANTITY	5.00	UNIT
619.1202	TEMPORARY MULCH	1.00	LS
619.1401	EROSION CONTROL MIX	50.00	CY



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
620.58	EROSION CONTROL GEOTEXTILE	24.00	SY
627.733	4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,990.00	LF
643.712	FLASHING BEACON - SOLAR POWERED	1.00	EA
652.30	FLASHING ARROW BOARD	6.00	EA
652.312	TYPE III BARRICADES	12.00	EA
652.331	DRUM	1.00	LS
652.35	CONSTRUCTION SIGNS	5,250.00	SF
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS
652.38	FLAGGERS	208.00	HR
652.41	PORTABLE-CHANGEABLE MESSAGE SIGN	4.00	EA
652.45	TRUCK MOUNTED ATTENUATOR	42.00	CD
652.451	AUTOMATED TRAILER MOUNTED SPEED LIMIT SIGN	42.00	CD
652.46	TEMPORARY PORTABLE RUMBLE STRIPS	42.00	UNIT
656.632	30 INCH TEMPORARY SILT FENCE	325.00	LF
659.10	MOBILIZATION	1.00	LS